

REPUBLIC OF LEBANON
MINISTRY OF ENERGY AND WATER
COUNCIL FOR DEVELOPMENT AND RECONSTRUCTION

PROJECT No

CONTRACT No

**CONSTRUCTION OF WATER WORKS IN OUADI ED
DELEM – QABB ELIAS AND MRAIJAT**

VOLUME 5

BILL OF QUANTITIES

Part A – Preamble to Bill of Quantities
Part B – Bill of Quantities

DECEMBER 2023

**BUREAU TECHNIQUE POUR
LE DEVELOPPEMENT (B.T.D.)**
P.O.Box : 70-492 Antélias
Tel : 04/712157-712158
Fax: 04/712159
Email: btd@btd-lb.com

**MINISTRY OF ENERGY AND
WATER**
**COUNCIL FOR DEVELOPMENT
AND RECONSTRUCTION**

GENERAL TABLE OF CONTENTS

Volume 1 **Bid Conditions and Procedures – Conditions of Contract**

Volume 2 **Not Used**

Volume 3 **Technical Specifications**

Part 1 General Requirements

Part 2 Civil Works

Part 3 Mechanical Works

Part 4 Electrical Works

Part 5 Instrumentation and Control

Part 6 Testing and Commissioning

Part 7 Boreholes

Volume 4 **Particular Specifications**

Part 1 General Requirements

Part 2 Civil Works

Part 3 Mechanical Works

Part 4 Electrical Works

Part 5 Instrumentation and Control

Part 6 Testing and Commissioning

Part 7 Boreholes

Volume 5 **Bill of Quantities**

Part A Preamble to Bill of Quantities

Part B Bill of Quantities

Volume 6 **Drawings**

PART A

PREAMBLE TO BILL OF QUANTITIES

TABLE OF CONTENTS

GENERAL

	PAGE NO.
1.000 INTRODUCTION	1
1.010 GENERAL	1
1.011 ITEMS DESCRIPTION	1
1.012 DEFINITIONS OF BILL OF QUANTITY CATEGORIES	1
1.012.1 CIVIL WORKS	1
1.012.2 ELECTRO-MECHANICAL WORKS	2
1.012.3 TRANSMISSION PIPELINES	2
1.012.4 BOREHOLES	2
1.013 RATES AND PRICES	3
1.014 MEASUREMENT	3
1.014.1 LUMP SUM	3
1.014.2 MEASURED QUANTITIES	3
1.015 DEFINITIONS	4
1.016 DEALING WITH WATER	4
1.017 WATER AND POWER	4
1.018 RECORDS AND “AS-BUILT” DRAWINGS	4
1.019 TRAFFIC REGULATION CONTROL AND SAFETY PROVISION	4
 2.000 BILL A - CIVIL WORKS	 6
2.010 TOPOGRAPHIC SURVEY AND SITE DELIMITATION	6
2.011 SITE CLEARANCE	6
2.012 SITE REARRANGEMENT AFTER CONSTRUCTION	6
2.013 CONSTRUCTION OF ACCESS ROAD	6
2.014 SOIL INVESTIGATIONS	7
2.015 EXCAVATION AND TRANSPORT OF UNSUITABLE BACKFILLING MATERIALS	7
2.016 PREPARATION OF FORMATION UNDER RESERVOIRS AND OTHER CONSTRUCTIONS	7
2.017 BACKFILLING AND COMPACTION	7
2.018 BLINDING AND MASS CONCRETE C20	7
2.019 REINFORCED CONCRETE GRADE C37, C30 (RESERVOIRS)	8
2.020 REINFORCED CONCRETE C30 (BUILDINGS)	8
2.021 FAIR FACE CONCRETE (WALLS, CEILINGS)	8
2.022 LEVELLING WITH MECHANICAL FLOAT	9
2.023 CYCLOPEAN CONCRETE	9
2.024 STEEL REINFORCEMENT FOR RESERVOIRS AND OTHER BUILDING	9
2.025 WATERSTOP	9
2.026 NEOPRENE PADS	9
2.027 HOLLOW CONCRETE BLOCK WALL (20 CM THICK)	9
2.028 RENDERING OR PLASTERING OF INTERIOR AND EXTERIOR SURFACES	10
2.029 EXTERIOR RENDERING WITH COLORED BUSH HAMMERED RENDER	10
2.030 CLADDING WITH NATURAL OR BUSH HAMMERED STONES	10
2.031 BUSH-HAMMERED STONE (STONE JAMBS, LINTELS, SKIRTING AND CAPPING)	10
2.032 SUPPLY AND INSTALLATION OF ROOF BRICKS OR TILES	10
2.033 INTERNAL LINING FOR RESERVOIR	11
2.034 WATERPROOFING OF RESERVOIRS AND OTHER BUILDINGS ROOF SLABS WITH THERMAL INSULATION	11
2.035 WATER TESTING AND DISINFECTION OF RESERVOIRS	11
2.036 EXTERIOR STEEL DOORS AND WINDOWS INCLUDING GLAZING AND PAINTING	11
2.037 CEMENTITIOUS WATERPROOFING	12
2.038 BITUMINOUS MEMBRANE SHEET WATERPROOFING	12

2.039	METALWORK	12
2.040	ALUMINIUM WORKS	12
2.041	INDUSTRIAL FLOORING	12
2.042	WASHABLE PAINT INTERNAL OR EXTERNAL USE COATING	13
2.043	FENCE	13
2.044	ACCESS GATE	13
2.045	ASPHALTING	13
2.046	SUPPLY AND INSTALLATION OF PIPES	14
2.047	SUPPLY AND INSTALLATION OF GATE VALVES	14
2.048	FLOOR DRAIN	14
2.049	SUPPLY AND INSTALLATION OF FLOAT VALVE	14
2.050	SUPPLY AND INSTALLATION OF SUCTION STRAINERS	14
2.051	SUPPLY AND INSTALLATION OF LEVEL INDICATOR	14
2.052	SUPPLY AND INSTALLATION OF DOUBLE AIR RELEASE VALVES	15
2.053	SUPPLY AND INSTALLATION OF WATER METERS	15
2.054	SUPPLY AND INSTALLATION OF MANOMETERS	15
2.055	SUPPLY AND INSTALLATION OF INSERTS	15
2.056	CHANGES IN COST AND LEGISLATION (BILL A – CIVIL WORKS)	16
3.000	BILL B - ELECTROMECHANICAL WORKS	18
3.010	MECHANICAL & ELECTRICAL EQUIPMENT	18
3.010.1	PUMPING SYSTEM	18
3.010.2	PIPING AND ACCESSORIES	18
3.010.3	WELL RISING COLUMN	18
3.010.4	GAS CHLORINATION EQUIPMENT	18
3.010.5	SURGE SUPPRESSION EQUIPMENT	18
3.010.6	SURGE ANTICIPATION VALVE (ANTI WATER HAMMER VALVE) (NOT APPLICABLE)	19
3.010.7	LIFTING AND HANDLING EQUIPMENT (NOT APPLICABLE)	19
3.010.8	ELECTRICAL SYSTEM	19
3.010.9	EDL ELECTRICAL POWER TRANSFORMER	19
3.010.10	STANDBY GENERATOR SET	20
3.010.11	UNINTERRUPTIBLE POWER SUPPLY	20
3.010.12	INSTRUMENTATION AND CONTROL SYSTEM	21
3.010.13	DOMESTIC LIGHTING AND ELECTRICAL SYSTEM	21
3.020	ELECTRO-MECHANICAL WORKS	22
3.020.1	MECHANICAL, ELECTRICAL AND CONTROL	22
3.020.2	MECHANICAL & ELECTRICAL WORKS	22
3.020.3	TECHNICAL SCHEDULES	24
3.021	CHANGES IN COST AND LEGISLATION (BILL B – ELECTROMECHANICAL WORKS)	27
4.000	BILL C –TRANSMISSION PIPELINES	29
4.010	GENERAL	29
4.011	TOPOGRAPHIC SURVEY	29
4.012	TRIAL PIT	29
4.013	TRIAL TRENCH	29
4.014	AS-BUILT DRAWINGS	29
4.015	SUPPLY OF DUCTILE IRON K9 PIPES INCLUDING ALL NECESSARY FITTINGS	30
4.016	SUPPLY OF HDPE PIPES INCLUDING ALL NECESSARY FITTINGS	30
4.017	TRENCH EXCAVATION	30
4.018	SAND BEDDING AND SURROUNDS	31
4.019	LAYING OF PIPES	31
4.020	BACKFILLING OF TRENCHES	31
4.021	EXTRA OVER FOR MANUAL WORKS	32
4.022	SUPPLY AND INSTALLATION OF AIR RELEASE VALVES	32
4.023	SUPPLY AND INSTALLATION OF PRESSURE REGULATING VALVES	32
4.024	SUPPLY AND INSTALLATION OF PRESSURE REGULATING, PRESSURE SUSTAINING VALVE AND WATERMETER	32

4.025	SUPPLY AND INSTALLATION OF PRESSURE SUSTAINING VALVE AND WATERMETER	32
4.026	SUPPLY AND INSTALLATION OF WATERMETER	33
4.027	SUPPLY AND INSTALLATION OF WASHOUTS	33
4.028	SUPPLY AND INSTALLATION OF CONNECTIONS TO EXISTING RESERVOIRS OR CATCHMENT STRUCTURES	33
4.029	CONNECTION TO EXISTING PIPES	33
4.030	SUPPLY AND INSTALLATION OF BRIDGE OR CULVERT CROSSING	34
4.031	CONSTRUCTION OF PRE-CAST OR CAST IN SITU, REINFORCED CONCRETE VALVE CHAMBERS	34
4.032	SUPPLY AND INSTALLATION OF VALVE CHAMBER COVER AND FRAME	34
4.033	SUPPLY AND INSTALLATION OF SURFACE BOX UNITS	34
4.034	CONCRETE WORKS	34
4.035	TESTING AND COMMISSIONING OF POTABLE WATER PIPES	35
4.036	ROAD REINSTATEMENT	35
4.036.1	CUTTING	35
4.036.2	REINSTATEMENT	35
4.037	CHANGES IN COST AND LEGISLATION (BILL C –TRANSMISSION PIPELINES)	37
5.000	BILL D - BOREHOLES	39
5.010	MOBILIZATION	39
5.011	DRILLING	39
5.012	GEOPHYSICAL LOGGING	39
5.013	VERTICALITY AND ALIGNMENT TEST	39
5.014	CASINGS	39
5.015	SCREENS	39
5.016	WELL GROUTING	40
5.016.1	SUPPLY OF CEMENT	40
5.016.2	INJECTION OF CEMENT IN THE ANNULAR SPACE	40
5.017	WELL DEVELOPMENT BY PUMPING	40
5.017.1	SUPPLY AND INSTALL OF PUMPING EQUIPMENT	40
5.017.2	WELL DEVELOPMENT (PUMPING AT DIFFERENT RATES)	40
5.018	PUMPING TESTS	40
5.018.1	STEP DRAWDOWN TEST	40
5.018.2	CONSTANT RATE TEST	40
5.019	WATER ANALYSIS	41
5.019.1	COLLECTION AND DELIVERY OF WATER SAMPLES TO AN APPROVED LABORATORY	41
5.019.2	PHYSICO-CHEMICAL ANALYSIS	41
5.019.3	BACTERIOLOGICAL ANALYSIS	41
5.020	REPORTS AND AS-BUILT DRAWINGS	41
5.020.1	DAILY DRILLER’S LOG, DETAILED REPORT AND AS-BUILT DRAWINGS	41
5.020.2	FINAL WELL REPORT	41
5.021	CHANGES IN COST AND LEGISLATION (BILL E – BOREHOLES)	42

1.000 INTRODUCTION

1.010 GENERAL

The Bill of Quantities is not and does not purport to be either exhaustive or explanatory of all the obligations and duties of the Contractor who shall be deemed to have satisfied himself as to the correctness and sufficiency of the rates and prices entered by him in the Bill of Quantities all of which shall cover all his obligations under the Contract (including those in respect of the supply of goods, materials, plant or services or of contingencies for which there is a Provisional Sum) and all matters and things necessary for the proper execution and completion of the Works and the remedying of any defects therein and which may reasonably be inferred to be necessary for the Works as described in the Contract whether expressly mentioned therein or not.

1.011 ITEMS DESCRIPTION

A detailed description of the items and of the conditions under which and the manner in which the work is to be done and measured is not set out in each item of the Bill of Quantities. Reference should be made to this Preamble and all other documents forming the Contract.

1.012 DEFINITIONS OF BILL OF QUANTITY CATEGORIES

The Bill of Quantities is divided into several categories, listed below, to group the prices under the following:

- A) Civil Works
- B) Electro-mechanical Works
- C) Transmission Pipelines
- D) Boreholes

1.012.1 Civil Works

The Civil Works category shall include, but not be limited to, a complete topographic survey, soil investigations, demolition, excavation works, backfilling, road works, concrete works, accessories, blockworks, cladding, plastering, waterproofing, thermal insulation, aluminium works, glazing, rendering, painting, fencing, and all necessary works not mentioned above and needed for a good finishing and exploitation of the different structures. Also this category shall include, but not be limited to, the prices to supply and install all necessary hydraulic accessories needed for equipment of the reservoirs and related valve chambers.

1.012.2 Electro-mechanical Works

1.012.2.1 Mechanical, Electrical and Control Equipment

The Mechanical, Electrical, and Control Equipment category of the BOQ shall include all the prices to supply the specified equipment including factory cost, factory tests, Engineer fees for factory tests and inspection, reports, packaging, shipping, handling, delivery on site and storage.

1.012.2.2 Mechanical, Electrical and Control Installation, etc...

The Mechanical, Electrical, and Control Installation, etc... category of the BOQ shall include the prices for installation, trenching, backfilling, interconnections, connection to power supply, operation and maintenance manuals, testing and commissioning for a complete system in place according to specifications and design drawings.

1.012.3 Transmission Pipelines

The relevant activities shall comprise, but not be limited to, a complete topographic survey and a survey of the existing facilities using the GPR technique or others if approved by the Engineer.

Also included are trial tests and as-built drawings.

Besides, the pipeworks shall mainly consist of the supply of the required pipes with all necessary fittings, trench excavation, preparation of suitable bedding and surrounds, pipe laying and trench backfilling. Special provision shall be made for stretches of pipes crossing highways, railways, and bridges.

Furthermore, the Works relating to transmission pipelines shall include the supply and installation of hydraulic accessories, such as gate valves, butterfly valves, air release valves, and others.

Also comprised are valve chambers in addition to their frames and covers.

The concrete works form an important element of these activities, especially regarding pipe supports, anchor blocks, thrust blocks, and others.

Moreover, the testing and commissioning of the pipes, besides road reinstatement where necessary, are also required.

1.012.4 Boreholes

Boreholes shall include the following:

- Supply, delivery and storage on site of temporary casing.
- Supply, delivery and storage on site of the final casing and screen column.
- Drilling of the wells by percussion or rotary method.
- Determining the hydrodynamic characteristics of the aquifer.
- Determining the physical and chemical quality of the pumped water.
- Installation of temporary casing.
- Grouting works.
- Installation of the final casing and screen column.
- Well development works.
- Well development control.

- Pumping test works.

1.013 RATES AND PRICES

The Contractor shall be deemed to have inserted against each item in the Bills such rates and prices as he may deem necessary to cover the requirements of the Contract. Where neither price nor rate is entered against an item or if the term “included” or any such similar term is used it shall be deemed to have been included in the other priced items in the BOQ and measured accordingly. All rates and prices entered against any item in the BOQ shall be deemed to include all the detailed requirements of the General and Particular Specifications and the requirements of volume 1.

Rates and prices shall be inserted in the unit rate column of the Bill of Quantities. Each part of the Bill of Quantities shall be totalled and the totals carried to the Summary and Grand Summary.

1.014 MEASUREMENT

The Bill of Quantities includes items as lump sum and others as measured quantities.

1.014.1 Lump Sum

The lump sum items shall not be subject to re-measurement, and shall include the prices for all necessary construction, installation, testing and commissioning among others. The lump sum entered in the Bills shall include the price for a complete installation as described in the specifications.

The prices shall include all work necessary for completion of the Works and shall include the prices for all necessary building work such as forming box outs, supports plinths, cable trenches, and the like and all necessary safety and access works including guards, handrails, fire fighting equipment and the like.

1.014.2 Measured Quantities

All measurements in the Bill of Quantities are taken strictly net. The principle of net measurements shall apply to all Works executed. All quantities measured for payment shall be measured by the Engineer on the basis of actual net quantities of Work fixed in position. Item “not used” shall neither be measured nor included by the Contractor in his statements.

The quantities given in the Bill are the estimated quantities. In no sense shall such quantities be considered as limiting or extending the amount of the work to be done by the Contractor and of the materials to be supplied by him. The Contractor shall be responsible for checking quantities and for making any necessary surveys and investigations prior to placing any order for materials.

1.015 DEFINITIONS

The following definitions shall apply to items in the Bill of Quantities.

- **Extra - Over**

Any “Extra-Over” (EO) item shall be measured and paid for in addition to the measurement of the basic item to which it relates.

- **Included**

Where the term included is used in the Preamble or in the Bills, items stated to be included within other items shall not be subject to measurement and their costs shall be deemed to be included within the rates of the billed items.

1.016 DEALING WITH WATER

Unit rates of items in the Bills of Quantities especially excavation items or excavation works shall be deemed to include the prices for dealing with water flows (especially for water courses crossing, or excavation along a water course) and keeping the Works free of water, and shall include prices for dewatering and supporting of trenches and excavation limits for pipeline works and structure works (for reservoirs, pumping stations, etc...). The above-mentioned works shall not be measured and shall not be paid separately.

1.017 WATER AND POWER

Unless otherwise explicitly stated in the Contract, water and power for the purpose of constructing, cleaning, and testing the Works shall be provided by the Contractor at his own expense, and shall not be measured separately.

1.018 RECORDS AND “AS-BUILT” DRAWINGS

After the work has been completed, the Contractor shall submit “as-built” drawings prepared whilst surveying during construction, showing the Works as constructed together with all other information that may either be required or be useful for the operation and maintenance of the Works in the future, such as type of soil, dimensions and location of structures, size of existing pipelines and cables encountered during excavation.

The cost of preparing the shop drawings, “as-built” Drawings and Records shall be deemed to be included by the Contractor in his unit rates for the various items in the Bill of Quantities and shall not be paid for separately. The As-built Drawings shall be submitted, if required by the Engineer, on computer CDs.

1.019 TRAFFIC REGULATION CONTROL AND SAFETY PROVISION

The provision of traffic control, safety equipment, signs, diversions, control systems including obtaining approvals and liaison with third parties for work in public roads and streets or in private sector will not be measured separately but shall be included in pipes rates, and shall include but not by way of limitation:

- Preparing all necessary plans, details and schedules and submission to the Employer/Engineer to obtain all necessary approvals.

- Liaison with third parties, to get all the needed permits from the concerned authorities.
- Erecting, maintaining, moving and removal of safety barriers, signs and traffic control equipment.
- Establishment and management of road diversions.
- Watching and lighting.
- Maintaining roads and streets clean and free from construction debris.

2.000 BILL A - CIVIL WORKS

2.010 TOPOGRAPHIC SURVEY AND SITE DELIMITATION

The price per site of the topographical surveys shall include checking, completing and/or performing land surveying based on approved benchmarks, the existing ground elevation, property lines, northing and easting coordinates, topographical maps, layouts, delimitation of plots (official delimitation from the concerned Authorities), implantation of foundations and buildings, the measurement of earthworks etc.... as well as all other additional tasks imposed by the site and/or the Engineer. It also includes all necessary topographical works, official delimitation certificates and approved plans, labour expenses, transport costs as well as all expenses resulting from calculations and data transfer on drawings and/or on technical sheets that will accelerate the progress of works.

The site survey shall be supplied on paper duly signed and stamped, and shall be supplied also as digital data suitable for automated plotting.

2.011 SITE CLEARANCE

The lump sum price shall include cleaning the entire surface of the site and clearing it from any obstacle (material or equipment) located within the area of works, it shall also include the demolition of existing unused structures (reservoirs, valve chamber, reinforced concrete structures, etc....), labours, necessary equipment, transport of soil or wastes to public dumps (permit from the concerned Authorities is required to use these public dumps) and all tasks to deliver the site clear for excavation.

2.012 SITE REARRANGEMENT AFTER CONSTRUCTION

The lump sum price shall include the reinstatement of the site after completion of the works according to the drawings and to the engineer's instructions. It also includes backfilling all around the structures and foundations with selected materials and/or backfill in order to deliver the site in a good condition and prepared for the proposed improvements.

2.013 CONSTRUCTION OF ACCESS ROAD

The lump sum price of the access road shall include, but not be limited to the following:

- Excavation in all kinds of soil and rocks and transport of the excavated material to disposal sites approved by the Engineer.
- Backfilling and compacting.
- Supply and transport of sub-base material (hard stones, gravel, ...) and sub-base preparation (scraping, levelling, compaction, ...).
- Supply, transport and laying of base course materials (hard crushed aggregate, ...) including any earthwork, scraping, levelling, compacting to a final thickness of 20 cm and a minimum width of 3 meters.
- Supply, transport and laying of bituminous prime coat and asphalt (minimum width 3m), and all necessary materials, labor and expenses, for laying asphalt to the satisfaction of the Engineer.

2.014 SOIL INVESTIGATIONS

The lump sum price of soil investigations according to BS 1377 (Methods of test for soil for civil engineering purposes) shall include various boreholes according to the nature of soil, in situ and laboratory tests, report determining the specifications and settlement description of the layers, the bearing capacity of the soil, the nature of foundations and the retaining structures if needed, level of water table, installation of piezometer, labour, mobilization and demobilization of equipment, tests, reports etc..., and this according to the detailed requirements of the general specifications.

2.015 EXCAVATION AND TRANSPORT OF UNSUITABLE BACKFILLING MATERIALS

The price per cubic meter of excavation shall include but not be limited to:
Excavation in all kinds of soils and rocks for structures and for access roads, demolition of existing concrete structures use of all adequate equipment, transport of soil or unsuitable backfill material to disposal sites approved by the Engineer, labour, dewatering, temporary and/or final retaining structures for trenches or open digs. The volume of excavations shall be measured from the geometric dimensions of structures and levels determined according to the site layout and drawings. No excess excavations or earthworks shall be paid for unless otherwise stated by the Engineer.

2.016 PREPARATION OF FORMATION UNDER RESERVOIRS AND OTHER CONSTRUCTIONS

The price per cubic meter for preparation of formation under the constructions foundation or slabs on grade shall include compacted gravels, sand, polyethylene sheet (150 μ), compaction equipment, labour and all material and equipment necessary to achieve the subbase and base to receive the concrete, the volume shall be measured according to geometric dimensions shown on the drawings.

2.017 BACKFILLING AND COMPACTION

The price of cubic meter of backfilling shall include backfilling layers (25 cm thickness each before compaction) placed and compacted for the needed area and behind retaining walls or other locations if ordered by written instructions from the Engineer or shown on the drawings. It shall also include geotextile sheets and drainage system if needed (minimum thickness 1.2mm, mass $\geq 300 \text{ g/m}^2$), bituminous coating, etc....

The volume of backfill materials shall be computed according to the dimensions shown on the drawings and the site layout and shall be composed of selected material for each case.

The price shall also include material, equipment, labour, etc... and all necessary tasks to achieve the work in perfect conditions.

2.018 BLINDING AND MASS CONCRETE C20

The price per cubic meter shall include all material, equipment, labour, transport, ... blinding and/or mass concrete and shall be composed of at least 250 kg of cement per cubic meter of concrete and shall be measured according to the geometric shapes shown on the layout drawings and/or Standard Drawings. Any quantity executed in excess of the indicated dimensions shall not be paid for. Any quantity less than that required in the Contract drawings and according to

the specification documents shall be deducted or completed according to the instructions given by the Engineer.

2.019 REINFORCED CONCRETE GRADE C37, C30 (RESERVOIRS)

The price per cubic meter shall include all material, equipment, labour, transport, admixtures (retarders, plasticizers, waterproofing materials, ...) batching, mixing, placing, vibrating, curing, testing, finishing, scaffolding, reservations for equipment, formwork, wrought formwork (fair face), surface levelling with mechanical float, etc... Dosage of cement shall be 400 kg/cu.m. for concrete C37, and reservoirs and retaining aqueous liquid structures. All joints or sealing systems shall be included in the price. Measurement shall be determined according to the geometric shapes indicated on the layout drawings and/or buildings drawings; any quantity executed in excess of the indicated dimensions shall not be paid for. Any quantity less than that required in the Contract drawings and according to the specification documents shall be deducted or completed according to the instructions given by the Engineer.

The price shall also include all materials, equipment, labour, transport, storage, placing, bending, scaffolding, etc... reinforcing steel supplied, placed, bended, etc... with all needed materials, accessories and tasks to achieve the works in perfect conditions. Detailed bar bending schedules and sheets should be submitted for approval before placing and installation.

The price shall also include all needed works, labor, material, transport, formwork, etc... to execute a fair faced concrete for interior and exterior walls and ceilings, and leveling of horizontal surfaces of slabs on grade by a mechanical trowel.

2.020 REINFORCED CONCRETE C30 (BUILDINGS)

The price per cubic meter shall include all material, equipment, labour, transport, admixtures (retarders, plasticizers, waterproofing materials, ...) batching, mixing, placing, vibrating, curing, testing, finishing, scaffolding, reservations for equipment, formwork, wrought formwork (fair face), surface levelling, etc... Dosage of cement shall be 350 kg/cu.m. for technical buildings, channels, retaining walls, foundations, wellhead manholes, etc... All joints or sealing systems shall be included in the price. Measurement shall be determined according to the geometric shapes indicated on the layout drawings and/or buildings drawings; any quantity executed in excess of the indicated dimensions shall not be paid for. Any quantity less than that required in the Contract drawings and according to the specification documents shall be deducted or completed according to the instructions given by the Engineer.

The price shall also include all materials, equipment, labour, transport, storage, placing, bending, scaffolding, etc... of reinforcing steel supplied, placed, bended, etc... with all needed materials, accessories and tasks to achieve the works in perfect conditions. Detailed bar bending schedules and sheets should be submitted for approval before placing and installation.

The price shall also include all needed works, labor, material, transport, formwork, etc, to execute a fair faced concrete for interior and exterior walls and ceilings of technical rooms.

2.021 FAIR FACE CONCRETE (WALLS, CEILINGS)

An extra over payment shall be added for every visible square meter of wrought formwork (fair face) for interior and exterior reservoir walls, and/or ceilings, interior walls and ceilings of technical buildings, interior and exterior walls and ceilings of technical rooms.

2.022 LEVELLING WITH MECHANICAL FLOAT

The price per square meter includes material, equipment, transport, labour,... and consists in levelling horizontal surfaces of large areas of slabs on grade (reservoirs and/or technical buildings) by a mechanical trowel.

2.023 CYCLOPEAN CONCRETE

The price per cubic meter of cyclopean concrete shall include material, equipment, transport, supply, placing, mixing, labour ... and shall be composed of 300 kg of cement per cubic meter of concrete and a maximum of 40% of hard rocks ($\leq 200\text{mm}$). Formwork and scaffolding are included and cyclopean concrete shall be measured according to geometric shapes determined by written instructions of the engineer. All tasks necessary for the completion of the work are deemed to be included in the price.

2.024 STEEL REINFORCEMENT FOR RESERVOIRS AND OTHER BUILDING

The price per ton include all materials, equipment, labors, transport, storage, placing, bending, scaffolding, etc... of reinforcing steel supplied, placed, bended, etc... with all needed materials, accessories and tasks to achieve the works in perfect conditions.

The price shall be paid per ton of reinforcement steel supplied, bended and placed, and shall be measured according with the dimensions figured on the drawings. Detailed bar bending schedules and sheets should be submitted for approval before placing and installation, these bar bending schedules and sheets will be used for calculation of reinforcing steel weight.

2.025 WATERSTOP

The price per linear meter of P.V.C. water-stop joints (expansion, contraction,...) and/or hypalon strip of 15 cm width shall include the supply, transport and the installation of the water-stop strips (up to 25cm width) according to drawings (essentially between mat foundations and walls of reservoirs). Any additional water-stop strips to be used according to particular methods of execution shall not be taken into account for measurement and written instructions from the engineer shall be obligatory. The price also includes the backing rod, sealant and fibre boards if needed.

2.026 NEOPRENE PADS

The price per linear meter of neoprene pads placed between reservoir roofs, slabs and walls shall include preparation and application of neoprene pads which shall withstand all strains exerted by the roof cover. It shall also includes the supply and application of polystyrene, polyethene sheets as well as equipment, materials, scaffolding, accessories and others that turn out to be necessary for a good execution.

2.027 HOLLOW CONCRETE BLOCK WALL (20 CM THICK)

The price per square meter of built areas of hollow concrete blocks (20 cm thick) shall include concrete blocks, sand and cement for mortar, all materials, equipment, labour, expenses, scaffolding, placing, junctions, concrete lintels, openings, ... and shall be measured according to net areas built from one side.

2.028 RENDERING OR PLASTERING OF INTERIOR AND EXTERIOR SURFACES

The price of rendering per square meter shall include all materials: cement, sand, water, equipment, labour, scaffolding, expenses, ... supply, transport, placing mortars and shall be measured according to geometric shapes of rendered areas, no excess and no measurement shall be paid for re-entrant or salient angles of openings, chamfered angles or others. The rendering shall consist of three coats according to specifications.

2.029 EXTERIOR RENDERING WITH COLORED BUSH HAMMERED RENDER

The lump sum price shall include the supply and transport of all needed materials (cement, sand, water, scaffolding, equipment,...) in addition to labour and any other expenses needed for rendering works wherever needed and to the satisfaction of the Engineer. It also includes cleaning and removing all unacceptable bush hammered render.

Rendering shall consist of three coats according to the specifications and the final coat shall be of a colored and bush-hammered render to the satisfaction of the Engineer.

2.030 CLADDING WITH NATURAL OR BUSH HAMMERED STONES

The price per square meter of natural stones (5 cm thick – 25 cm wide minimum) or bush hammered stones (3 cm thick – 25 cm wide minimum) shall include supply, transport, installation and placing of materials (cement, sand, and stones), joints, scaffolding, ladders, equipment, labor, technical expenses, openings and all necessary tasks needed to accomplish the work.

The surfaces shall be measured according to geometric shapes of built areas shown on elevations and counted from one side. No measurement and no excess shall be paid for stones laid on re-entrant or salient angles of openings.

2.031 BUSH-HAMMERED STONE (STONE JAMBS, LINTELS, SKIRTING AND CAPPING)

The price per linear meter of bush-hammered stone (3 cm thick – 25 cm wide minimum) shall include supply, transport, installation and placing of materials (cement, sand, and stones), joints, scaffolding, ladders, equipment, labor, technical expenses, openings and all necessary tasks needed to accomplish the work.

The surfaces shall be measured according to geometric shapes of built areas shown on elevations and counted from one side. No measurement and no excess shall be paid for stones laid on re-entrant or salient angles of openings.

2.032 SUPPLY AND INSTALLATION OF ROOF BRICKS OR TILES

The price per square meter of bricks laid on the roof with their steel bases shall include supply, transport and installation of materials (cement, sand, metal, epoxy paint and bricks), scaffolding, equipment, labor, technical expenses, and all necessary tasks needed to execute the works to the satisfaction of the Engineer.

The surfaces shall be measured according to geometric shapes of built areas.

2.033 INTERNAL LINING FOR RESERVOIR

The price per square meter of internal surface waterproofing coating for reservoirs shall include preparation of the surface (sand blasting, water blasting), treatment of singular points (contraction or expansion joints, pipe penetration,...) material, transport, scaffolding, application in several layers, labour, expenses,... in conformity with the technical sheet of approved material, quality tests, structures test, before and after application, warranty. Crystallisation or mineralisation products shall be applied on reservoirs walls and slabs on ground, and flexible protective and waterproofing slurry products on bottom faces of roof slabs or domes.

2.034 WATERPROOFING OF RESERVOIRS AND OTHER BUILDINGS ROOF SLABS WITH THERMAL INSULATION

The price per square meter of roof slab waterproofing shall include material, transport, equipment, labour, supply, installation, preparation of support (screed,...), treatment of singular point (rain outlet, ventilations, openings,...), and shall be composed of a vapour barrier SBS or APP; thickness ≥ 2.5 mm fixed by adherence or semi-adherence, a thermal insulation with minimum thickness of 50 mm and a thermal conductivity $\alpha = 0.037$ Kcal/h.m²/°C, and a waterproofing membranes (SBS/APP) 4 mm thick minimum. Vertical upstands shall be aluminium self-protected, supply and installation of concrete protection grade C20 or concrete paving slabs and a non woven polyester sheet 200 g/m². Supply and installation works of necessary roof drains are deemed to be included in this item and shall not be paid for separately.

The membranes shall be measured only for horizontal surfaces and no measurements or excess shall be paid for vertical surfaces.

2.035 WATER TESTING AND DISINFECTION OF RESERVOIRS

The lump sum price of water testing of reservoirs per site shall include:

- Supply, transport and filling of reservoir with water, and checking for leaks. This operation shall be repeated to the Engineer's satisfaction.
- Water sampling for analysis and transport in an adequate packing to the laboratory, suppliers, labour,....
- Bacteriological analysis type B2 (2 per reservoir)
- Cleaning and disinfection including all material, scaffolding, labour, expenses and all tasks necessary to accomplish the work.

2.036 EXTERIOR STEEL DOORS AND WINDOWS INCLUDING GLAZING AND PAINTING

The price per square meter of exterior steel doors and windows shall include all material, equipment, transport, labour, expenses, water-resistant hardware, glazing (8mm glass) ventilation, mechanical protections, epoxy paint, louvers, openings, locking system, supply, installation, anchoring, reinstatement of support, finishing and all tasks and accessories, necessary to a perfect execution. Metal sheets shall be 3mm thick minimum.

2.037 CEMENTITIOUS WATERPROOFING

The price shall be measured in square meter of surface and includes, all materials, equipment, transport, labor, expenses preparation of the support, scaffolding and application of two layers of cementitious mortar for waterproofing of the water tank.

2.038 BITUMINOUS MEMBRANE SHEET WATERPROOFING

The price per square meter of roof slab waterproofing shall include material, transport equipment, labor, supply, installation, preparation of support (screed,...), treatment of singular point (rain outlet, manholes wall, openings,...) and shall be composed of primer and waterproofing membranes (SBS/APP) 4 mm thickness. Vertical upstands shall be aluminium self-protected aluminium, flashing, supply and apply extruded polystyrene panels and removable tiling. Supply and installation works of necessary roof drains are deemed to be included in this item and shall not be paid for separately.

The membrane shall be measured only for horizontal surfaces and no measurements or excess shall be paid for vertical surfaces.

2.039 METALWORK

The price per kilogram of metalwork (protection bars, louvers, ventilation, ladders, grating, railings, trap doors,...) shall include all material, equipment, transport, labour, expenses, hardware glazing (8mm glass), epoxy paint, supply, installation, anchoring, locking system, reinstatement of support, finishing and all tasks and accessories necessary to a perfect execution.

2.040 ALUMINIUM WORKS

The price per square meter of interior doors and exterior windows shall include all material, equipment, labour, expenses, manufacture, supply, transport, installation, glazing (8mm glass), anchoring, locking system, reinstatement of support, finishing and all tasks and accessories necessary to a perfect execution.

2.041 INDUSTRIAL FLOORING

The price per square meter of industrial flooring shall include all material, equipment, transport, labour, expenses, application, preparation of support, scaffolding, curing, finishing, cleaning, singular points, screed if necessary, and shall be composed of heavy duty chemical and abrasion resistant epoxy resin floor (5mm thick). For walls, 2mm thick of epoxy resin will be sufficient (the number of layers should be in compliance with the manufacturer recommendation and the Engineer's approval).

The surfaces shall be measured according to geometric shapes of painted area (floor, wall or ceiling), no measurement and no excess shall be paid for re-entrant or salient angles of openings.

2.042 WASHABLE PAINT INTERNAL OR EXTERNAL USE COATING

The price per square meter of washable paint includes all materials, equipment, transport, labour, expenses, scaffolding, application, preparation of support, finishing, cleaning, singular points, and shall be composed of a double layer of mastic, primer and a minimum of two coats of washable paint (latex emulsion and/or vinyl acrylic emulsion).

The surfaces shall be measured according to geometric shapes of painted area, no measurement and no excess shall be paid for re-entrant or salient angles of openings.

2.043 FENCE

The price per linear meter of fence shall include all excavation, reinforced concrete, galvanised mesh vinyl coated, tie rods and trusses, metalwork, epoxy paint, finishing, material, labour, equipment, supply, transport, anchor bolts, reinstatement of property line, and all tasks necessary for a perfect execution. In case the fence has to be fixed on retaining walls and/or existing or new concrete structures, the contractor must take this constraint in consideration according to each site and adapt his price accordingly.

2.044 ACCESS GATE

The lump sum price of access gate per site shall include all excavation, reinforced concrete, steel access gate, locking system, epoxy paint, water resistant hardware, anchors, finishing material, labour, equipment, formwork, scaffolding, supply, transport, reinstatement of property line and all tasks necessary for a perfect execution. For access gate width refer to site implantation.

2.045 ASPHALTING

The price per square meter of asphaltting for structures and access roads layout shall include earthwork, sub-base preparation (scraping, levelling, compaction,...), sub-base material layer (hard stones, gravel, ...), base course material (hard crushed aggregate,...) bituminous tack coats, asphalt and all material, equipment, supply, transport, labour, expenses, drainage system, testing, quality control, hauling, spreading and compaction, and all necessary tasks for laying, jointing and a perfect execution and shall include, but not be limited to:

- Base course: supply, and transport of materials, earth work, scraping, levelling, compaction, labour, final thickness after compaction 20 cm, testing, quality control and all necessary tasks for a perfect execution.
- Asphalt: supply and transport of materials, bituminous, tack coat, asphalt and all necessary materials, labour, expenses, testing, quality, control, hauling, spreading and compaction and all necessary tasks for laying, jointing and a perfect execution.

RESERVOIRS HYDRAULIC ACCESSORIES

2.046 SUPPLY AND INSTALLATION OF PIPES

Pipes shall be classified for payment according to diameter and material and shall be measured in linear meters of pipeline in place measured along the crown of the pipeline.

The length measured for payment shall include the lengths of all fittings, valves and specials installed in the line.

The price shall cover all fittings, bends, joints, reducers, flanges, holderbats, supports, puddle flanges, inserts, bolts, nuts, brackets, bell mouths, as well as hauling, transport, unloading, staking and all necessary labour and accessories to provide a complete installation.

2.047 SUPPLY AND INSTALLATION OF GATE VALVES

Gate valves shall be classified for payment by nominal diameter and nominal pressure class and shall be measured by number.

Price shall include for all fittings necessary to joint the assembly to the pipeline (either new or existing), including thrust flanges, flexible joints, dismantling joints, supports and all items necessary to make a complete installation.

2.048 FLOOR DRAIN

Floor drains shall be measured by number, and shall include for floor drain pipe DN 80mm, excavation, backfilling, reinstatement of the concrete surface level, flap valve, bends and all components necessary to provide a complete installation.

2.049 SUPPLY AND INSTALLATION OF FLOAT VALVE

Float valves shall be classified for payment by nominal diameter and nominal pressure class and shall be measured by number. Price shall include all the requirements as stipulated in item “Gate valves” above.

2.050 SUPPLY AND INSTALLATION OF SUCTION STRAINERS

Suction strainers shall be measured by number according to nominal diameter. Material shall be stainless steel, coated cast iron or bronze.

Price shall include for all fittings necessary to install the suction strainer inside the reservoir on the outlet pipe including flanges, joints, bolts, nuts and all accessories to make a complete installation.

2.051 SUPPLY AND INSTALLATION OF LEVEL INDICATOR

Level indicators shall be measured by number, and the price shall include for all necessary fittings to install the level indicator, civil works, concrete drilling, grouting with suitable material, level indicator, testing, bolts, nuts, etc...

2.052 SUPPLY AND INSTALLATION OF DOUBLE AIR RELEASE VALVES

Air valves shall be measured by number for each air valve size and nominal pressure, and shall include for tees, ARV, gate valves, riser pipes, flanges, bolts, nuts, supports and all components necessary to provide a complete installation.

2.053 SUPPLY AND INSTALLATION OF WATER METERS

Water meters shall be measured by number for each nominal diameter and nominal pressure class, and shall include for **filters/Y strainers, flow straighteners** (both having same DN and PN as water meters. Moreover, flow straighteners should be of the type which eliminate the need for any straight length of pipe before and after the water meter), flanges, dismantling joints, supports, bolts, nuts and all components necessary to provide a complete installation.

2.054 SUPPLY AND INSTALLATION OF MANOMETERS

Manometers shall be measured by number regardless of the calibre of the pressure gauge and the diameter of the tapping collar. Price shall include for manometers (case 10 cm, glycerine filled), isolating valves (DN = 15 mm, PN 25), tapping collars, bolts, nuts and all components necessary to provide a complete installation.

2.055 SUPPLY AND INSTALLATION OF INSERTS

Inserts shall be classified for payment by nominal diameters, and shall be measured by number, price shall include for material, inserts, installation, grouting, bolts, nuts, flanges, etc...

2.056 CHANGES IN COST AND LEGISLATION (BILL A – CIVIL WORKS)

ITEM Nb	DESCRIPTION	PRICE ADJUSTMENT FORMULA
2.0000	General	
2.0001	Topographic survey and site delimitation	NOT APPLICABLE
2.0002	Site clearance	NOT APPLICABLE
2.0003	Site rearrangement after construction	NOT APPLICABLE
2.0004	Construction of access road	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
2.1000	Earthworks	
2.1100	Soil investigations	NOT APPLICABLE
2.1200	Excavation	
2.1201	Excavation in all types of soils and rocks and demolition of existing concrete structures and transport of unsuitable backfilling material to disposal sites	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
2.1300	Preparation of formation under reservoirs and other constructions	
2.1301	Supply, preparation and compaction of the gravel and sand beds in addition to laying the polyethylene sheet under the construction's foundations.	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
2.1400	Backfilling	
2.1401	Backfilling and compaction	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
2.2100	Concrete works	
2.2101	Blinding and mass concrete Class C20	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.2102	Reinforced concrete Class C30, 400 kg of cement /cu.m, for reservoirs, including formwork	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.2103	Reinforced concrete Class C30, 350 kg of cement /cu.m, for other buildings, including formwork	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.2104	Extra over items 2.2102 and 2.2103 for fair faced concrete in reservoirs and other buildings	NOT APPLICABLE
2.2106	Concrete surface leveling with mechanical float	NOT APPLICABLE
2.2107	Cyclopean concrete	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.2108	Reinforcement in reservoir and other building structures (all diameters)	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\}$
2.2200	Water stop and bearing pads	
2.2201	Water stop up to 25 cm in width	NOT APPLICABLE
2.2202	Neoprene pads between walls and roof slab	NOT APPLICABLE
2.3000	Blockwork, cladding, and plastering	
2.3001	Hollow concrete block wall	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.3002	Rendering or plastering of interior and exterior surfaces	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.3003	Exterior rendering with bush-hammered render	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.3004	Cladding with natural stone (minimum thick.5 cm)	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.3005	Bush - Hammered stone (Stone Jambes, Lintels, Skirting & Capping)	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
2.3006	Supply and installation of roof bricks	$P_1 = 80\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\} + 20\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmb_1 / Lmb_0 * E_1 / E_0 + 0.15\}$
2.4000	Waterproofing, thermal insulation, and water quality control	
2.4001	Internal lining for reservoirs	NOT APPLICABLE
2.4002	Waterproofing of reservoirs and other buildings roof slabs with thermal insulation	NOT APPLICABLE
2.4003	Water testing and disinfection for reservoirs	NOT APPLICABLE
2.4004	Cementitious waterproofing	NOT APPLICABLE
2.4005	Bituminous membrane sheet waterproofing	NOT APPLICABLE
2.5000	Metal and aluminium works	
2.5100	Metal works	
2.5101	Supply and installation of exterior steel doors and windows including glazing and painting	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmb_1 / Lmb_0 * E_1 / E_0 + 0.15\}$
2.5102	Supply and installation of metal works: steel protection bars for exterior windows, metallic ladders with or without safety hoops, gratings for channels, railings, locks and all other metal works, including painting	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmb_1 / Lmb_0 * E_1 / E_0 + 0.15\}$
2.5200	Aluminium works	
2.5201	Supply and installation of interior aluminium doors and exterior aluminium windows, including glazing.	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.10 * Ver_1 / Ver_0 * E_1 / E_0 + 0.60 * Alu_1 / Alu_0 * E_1 / E_0 + 0.15\}$

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM – QABB ELIAS AND MRAIJAT
VOLUME 5 - BILL OF QUANTITIES PART A - PREAMBLE TO BILL OF QUANTITIES

ITEM Nb	DESCRIPTION	PRICE ADJUSTMENT FORMULA
2.6000	Finishing works	
2.6100	Industrial flooring	
2.6101	Supply and application of industrial flooring	NOT APPLICABLE
2.6200	Washable Paint internal or external use coating	
2.6201	Supply and application of washable internal or external use coating	NOT APPLICABLE
2.7000	Fence	
2.7001	Supply and installation of site's external fence, including painting	$P_1 = 25\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\} + 75\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmb_1 / Lmb_0 * E_1 / E_0 + 0.15\}$
2.7002	Supply and installation of the access gate (L = 4m)	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmb_1 / Lmb_0 * E_1 / E_0 + 0.15\}$
2.7003	Supply and installation of the access gate (L = 1.2m)	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmb_1 / Lmb_0 * E_1 / E_0 + 0.15\}$
2.8000	Asphalting	
2.8001	Subgrade compaction, sub-base and base preparation, and asphalting	$P_1 = 50\% * P_0 * \{0.15 + 0.15 * L_1 / L_0 + 0.45 * [(1.12 * B_1 + 66) / (1.12 * B_0 + 66)] + 0.25 * F_1 / F_0\} + 50\% * P_0$
2.9000	Hydraulic Accessories	
2.9100	Supply and installation of flanged ductile iron K9 pipes including all necessary fittings	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Tt_1 / Tt_0 * E_1 / E_0 + 0.15\}$
2.9200	Supply and installation of gate valves (including bolts, nuts, etc...)	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9300	Supply and installation of double function air release valves	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9400	Supply and installation of water meters including filters, Y-strainers, ...	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9500	Supply and installation of float valves	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9600	Supply and installation of suction strainers	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9700	Supply and installation of level indicators	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9800	Supply and installation of floor drains	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
2.9900	Supply and installation of inserts	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$

For all the parameters figuring in the price adjustment formulas, refer to Volume 1, Conditions of Contract, Clause 70.1.

3.000 BILL B - ELECTROMECHANICAL WORKS

3.010 MECHANICAL & ELECTRICAL EQUIPMENT

3.010.1 Pumping system

The price of the pumping system items shall include, but not limited to, factory witness test and report, supply of the complete pumpset, packaging, shipping and handling, customs fees, delivery on site, spare parts, storage, and supply of any other items and accessories deemed necessary for the complete installation and trouble free operation of the pumpset.

3.010.2 Piping and accessories

The price of the piping and accessories items, shown on drawings, shall include, but not limited to, supply of the complete piping system, all hydraulic equipment and accessories, packaging, shipping and handling, customs fees, delivery on site, spare parts, storage and any other items and accessories deemed necessary for the complete installation and trouble free operation of the mechanical system.

3.010.3 Well rising column

The price of the well rising column item shall include, but not limited to, supply, transportation, storage, installation and testing of seamless black steel pipes for the rising column in the well, including all necessary fittings and accessories (steel plates, couplings, reducers...).

Seamless black steel pipes shall be:

- Connected by threading,
- Able to withstand a working pressure of at least 80 bars,
- Able to withstand their own weight and the weight of the submersible pump set,
- Coated on both sides with epoxy suitable for use with potable water.

Seamless black steel pipes shall be measured by linear meters and shall be classified for payment according to pipe diameter.

3.010.4 Gas chlorination equipment

The price of the gas chlorination equipment items shall include, but not limited to, supply of the complete gas chlorination system, all equipment and accessories, packaging, shipping and handling customs fees, delivery on site, spare parts, storage, and any other items and accessories deemed necessary for the complete installation and trouble free operation of the complete gas chlorination system.

3.010.5 Surge Suppression Equipment

The price of the surge protection system items shall include, but not limited to, supply of the complete surge suppression system, all hydraulic equipment and accessories, packaging, shipping and handling customs fees, delivery on site, spare parts, storage, and any other items and accessories deemed necessary for the complete installation and trouble free operation of the surge suppression system.

3.010.6 Surge Anticipation Valve (Anti Water Hammer Valve) (Not applicable)

The price of the surge anticipation valve shall include, but not limited to, supply of the complete valve, all hydraulic equipment and accessories packaging, shipping and handling, customs fees, delivery on site, storage and any other items and accessories deemed necessary for the complete installation and trouble free operation of the surge anticipation valve.

3.010.7 Lifting and Handling Equipment (Not applicable)

The lump sum price of the lifting and handling equipment shall include but not limited to, supply of the complete lifting and handling equipment, all steel works, all controls and electric panels, packaging shipping and handling customs fees, delivery on site storage and any other items and accessories deemed necessary for the complete installation and trouble free operation of the lifting and handling equipment.

3.010.8 Electrical system

The price of the electrical system items shall include, but not limited to, supply of all electrical equipment, all electrical cables & wires, supply of all electrical control panels, supply of Software, spare parts, packaging, shipping and handling customs fees, delivery on site, storage, and any other items and accessories deemed necessary for the complete installation and trouble free operation of the electrical system.

3.010.9 EDL electrical power transformer

The price of the EDL electrical power transformer shall include, but not limited to:

- a) supply, transmission, storage, installation and testing of a pole-mounted oil-filled power transformer with ratings as specified, cooling by natural oil and air circulation (ONAN), connection type DYn11, including:

- Pole including foundations and support chassis.
- MV disconnect switch.
- Pole-mounted metallic box.
- LV circuit breaker.
- MV & LV cable terminations.
- LV cable connecting transformer secondary to LV circuit breaker.
- Neutral earthing.
- Transformer protection relay.
- All necessary fixing and mounting accessories.

Note: Contractor is to submit shop drawings of pole and transformer to EDL for approval. Price shall also include all fees required by EDL including supervision fees.

- b) Supply, transmission, storage, installation and testing of all equipment and materials for the construction of a medium-voltage overhead power network, including:

- Poles including foundations.
- Conductor insulators.
- Bare copper conductors.
- Connection to existing MV grid.
- Connection to transformer MV terminals.
- Mounting, fixing and connection accessories.

Note: Contractor is to submit shop drawings of overhead lines routing, poles and accessories to EDL for approval. Price shall also include all fees required by EDL including supervision fees.

- c) Insuring a LV subscription to EDL power including: (NOT WITHIN THIS CONTRACT)
- Undertaking all administrative and legal procedures for subscribing to EDL power on the behalf of the Owner.
 - All fees as required by EDL for the connection of the required power including the kWh meter, taxes, deposit...

This item shall be measured in unit of EDL electrical power transformer and power network, completely installed and tested and shall be classified for payment according to transformer's rated power.

3.010.10 Standby Generator Set

The price of the standby generator shall include, but not limited to, supply, transportation, storage, installation and testing of a standby generator set as shown and specified including:

- Diesel engine, 1500 rpm.
- Alternator, 400/230 V, 50 Hz, 3 phase, 4 wire, with standby power as specified.
- Cooling system including radiator, belt-driven fan, piping, make-up tanks and accessories.
- Starting system including batteries and battery charger.
- Exhaust system including a residential type silencer, piping, insulation, etc.
- Soundproof and weatherproof enclosure suitable for exposed outdoor installation.
- Fuel system including fuel tank, daily fuel tank, piping, fittings and related accessories.
- Control and instrumentation panel/cubicle to include automatic start-up on normal power failure.
- Main circuit breaker.
- Termination of cables to generating sets and control panels including cable terminal boxes and accessories.
- All necessary mechanical and electrical work.

This item shall be measured in unit of standby generator set completely installed and tested and shall be classified for payment according to generator's rated standby power.

3.010.11 Uninterruptible power supply

The price of the uninterruptible power supply shall include, but not limited to, supply, transportation, storage, installation and testing of an uninterruptible power supply (UPS) as shown and specified including:

- Sealed nickel-cadmium batteries.
- Batteries rack.
- Cables and cable connection up to the ICA compartment of MCC.

This item shall be measured by number of uninterruptible power supply completely installed and tested and shall be classified for payment according to UPS rated power.

3.010.12 Instrumentation and control system

The price of the instrumentation and control system items shall include, but not limited to, supply of the complete instrumentation, control and monitoring systems, supply of all wires and cables, supply of all furniture, packaging, shipping and handling customs fees, delivery on site, spare parts, storage, and any other items and access deemed necessary for the complete instrumentation and trouble free operation of the instrumentation, control and monitoring systems.

3.010.13 Domestic Lighting and Electrical System

The lump sum price for the domestic lighting and electrical installation shall include, but not limited to, supply of all electrical panel boards and their accessories, supply of all cables, conduits, junction boxes and their accessories, supply of all lighting fixtures, switches, sockets, plugs and their accessories, packaging, shipping and handling, customs fees, delivery on site, spare parts, storage, and any other items and accessories deemed necessary for the complete installation and trouble free operation of the domestic lighting and electrical system.

3.020 ELECTRO-MECHANICAL WORKS

3.020.1 Mechanical, Electrical and Control

3.020.1.1 Mechanical, Electrical and Control Installation, Supply, Testing, and Commissioning

The Mechanical, Electrical, and Control Installation, Testing, Commissioning category of the BOQ shall include the prices for operation and maintenance manuals, installation, trenching, backfilling, interconnections, connection to power supply, testing and commissioning for a complete system in place according to specifications and design drawings.

3.020.1.2 Lump Sum

The lump sum items shall not be subject to remeasurement, and shall include the prices for all necessary construction, installation, testing and commissioning among others. The lump sum entered in the Bills shall include for a complete installation as described in the specifications.

The prices shall include all work necessary for completion of the Works and shall include the prices for all necessary building work such as forming box outs, supports plinths, cable trenches, and the like and all necessary safety and access works including guards, handrails, firefighting equipment and the like.

3.020.2 MECHANICAL & ELECTRICAL WORKS

3.020.2.1 Pumping system

The lump sum price of the pumping system shall include, but not limited to, concrete base, installation on site of the complete pumpset, connection to hydraulic piping system, connection to electric power system, connection to control and monitoring systems, preparation O & M manuals and any other items and accessories deemed necessary for the complete installation and trouble free operation of the pumpset.

3.020.2.2 Piping and accessories

The lump sum price of the piping, shown on drawings, and accessories shall include, but not limited to, installation on site of the complete piping system all hydraulic equipment and accessories, connection to electrical, control and monitoring systems, preparation of O & M manuals and any other items and accessories deemed necessary for the complete installation and trouble free operation of the mechanical system.

3.020.2.3 Gas Chlorination Equipment

The lump sum price of the gas chlorination equipment shall include, but not limited to, installation on site of the gas chlorination system, all controls and electric panels, connection to pipework, connection to electrical, control and monitoring systems, preparation of O & M manuals and any other items and accessories deemed necessary for the complete installation and trouble free operation of the complete lifting system.

3.020.2.4 Surge Suppression Equipment

The lump sum price of the surge protection system shall include, but not limited to, installation on site of the complete surge suppression system, all hydraulic equipment and accessories, connection to hydraulic, electrical, control and monitoring systems, surge analysis and reports, preparation of O & M manuals and any other items and accessories deemed necessary for the complete installation and trouble free operation of the surge suppression system.

3.020.2.5 Surge Anticipation Valve (Not applicable)

The lump sum price of the surge anticipation valve shall include, but not limited to installation on site of the surge anticipation valve, all hydraulic equipment and accessories, connection to hydraulic, electrical, control and monitoring systems, preparation of O&M manuals and any other items and accessories deemed necessary for the complete installation and trouble free operation of the surge anticipation valve.

3.020.2.6 Lifting and Handling Equipment (Not applicable)

The lump sum price of the lifting and handling equipment shall include but not limited to installation on site of the complete lifting and handling system, all steel works, all controls and electric panels, packaging shipping and handling customs fees, delivery on site storage and any other items and accessories deemed necessary for the complete installation and trouble free operation of the lifting and handling equipment.

3.020.2.7 Electrical system

The lump sum price of the electrical system shall include, but not limited to, installation on site of all electrical equipment, all electrical cables & wires and all electrical control panels, preparation of O & M manuals, connection to the electric power system of (E.D.L.), connection to control and monitoring systems and any other items and accessories deemed necessary for the complete installation and trouble free operation of the electrical system.

3.020.2.8 Instrumentation and control system

The lump sum price of the instrumentation and control system shall include, but not limited to, installation on site of the complete instrumentation, control and monitoring systems, of all wires and cables, of all furniture, preparation of O & M manuals, installation, configuration and commissioning of all Software, connection to electrical and hydraulic systems, and any other items and access deemed necessary for the complete instrumentation and trouble free operation of the instrumentation, control and monitoring systems.

3.020.2.9 Training, testing and commissioning

The lump sum price for training, testing and commissioning shall include, but not limited to, on site tests for all, electrical, mechanical, control, and performance tests on equipment and systems, all measurements, equipment, apparatus, materials, power supply, and labor, tests reports, supply of necessary training sessions, training material and documentation, supply, transportation, accommodation and expenses of trainers and commissioners, and any other items and accessories deemed necessary for the comprehensive training of water authority and appointed personnel, and necessary for the on-site testing and commissioning of the plant.

3.020.2.10 Water analysis

The lump sum price for water analysis shall include, but not limited to, taking samples, transport to laboratory, perform the required analysis, submit reports, supply of any chemicals required for water analysis and any other items and accessories deemed necessary for the performance of the complete water analysis.

3.020.2.11 Domestic Lighting and Electrical System

The lump sum price for the domestic lighting and electrical installation shall include, but not limited to, installation on site of all electrical panel boards and their accessories, of all cables, conduits, junction boxes and their accessories, of all lighting fixtures, switches, sockets, plugs and their accessories, preparation of O&M manuals, necessary electric connections for the proper operation of the complete installation, connection to electric power system, testing and commissioning and any other items and accessories deemed necessary for the complete installation and trouble free operation of the domestic lighting and electrical system.

3.020.3 Technical schedules

The following Technical Schedules, where appropriate shall be completed by Tenderers. Additional Technical Schedules shall be submitted for any alternative plant proposed by Tenderers.

PUMPSET		
1.1 PUMP		
Max. permissible sand content		g/m ³
Nominal flow		l/sec
Nominal head		m
NPSH at nominal flow		m
Manufacturer		
Required power		Kw
Efficiency at nominal flow		%
Speed		rpm
Impeller material		
Body material		
Manufacturing standards		

1.2 MOTOR		
Manufacturer		
Power at full load		kW
Efficiency at full load		%
Index of protection		
No. of starts per hour		

LIFTING & HANDLING		
Safe working load		Kg
Hoist manufacturing standards		

3. SURGE SUPPRESSION EQUIPMENT		
Surge tank material		
Working pressure		bar
Compressor manufacturer		

4. PIPES		
Manufacturer		
Material		

5. VALVES		
Manufacturer		

6. CABLES		
Manufacturer		

7. ELECTRICAL PANEL BOARD		
Enclosure IP rating		
Starter Rating		Kw

8. ACTUATOR FOR MOTORIZED VALVE (NOT APPLICABLE)		
Manufacturer		

9. U.P.S.		
Manufacturer		

10. PLC		
Make		

11. LEVEL SENSOR		
Make		
Type		

12. FLOW SENSOR		
Make		
Type		

13. PRESSURE SENSOR		
Make		
Type		

14. TEMPERATURE SENSOR		
Make		
Type		

15. DIGITAL INDICATOR		
Make		
Type		

16. MODEM (NOT APPLICABLE)		
----------------------------	--	--

Make		
------	--	--

17. TELEMANAGEMENT CENTER EQUIPMENT (CPU, Memory, I/O, Colour VDUs, Peripherals Printers) (NOT APPLICABLE)

Make		
Type		

18. SOFTWARE (NOT APPLICABLE)

Make and application name		
---------------------------	--	--

19. SYSTEM OPERATION (NOT APPLICABLE)

Configuration		
---------------	--	--

3.021 CHANGES IN COST AND LEGISLATION (BILL B – ELECTROMECHANICAL WORKS)

ITEM Nb.	DESCRIPTION	PRICE ADJUSTMENT
S4.0000	Mechanical, Electrical and Control Equipment	
S4.0100	Pumping system	
S4.0101	Submersible Motopumpset	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0200	Piping and accessories	
S4.0201	Rising column pipe	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Ta1 / Ta0 * E1 / E0 + 0.15\}$
S4.0202	Piezometric tube	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Et1 / Et0 * Yn1 / Yn0 + 0.15\}$
S4.0203	Sampling ball valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0204	Globe valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0205	Gate valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0206	Check valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0207	Air release valve with isolating valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0208	Dismantling Joint	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0209	Surge anticipation valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0210	Rubber spherical joint	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0211	Float joint	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0212	Electrical overhead crane	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0213	Manual overhead crane	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0214	Hydraulic accessories (bends, tees, pipes, flanges, gaskets, joints, bolts, nuts, supports, well head piece...)	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0300	Gas chlorination system	
S4.0301	Chlorinator complete system (including pump, ejector, preregulators, auto-transfer switch, Cl2 flowmeter, Gas masks...)	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0302	Chlorine cylinders	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0303	Chlorine leakage detection system	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0304	Ventilators	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0305	Accessories (pipes, bends, tees, joints, bolts, nuts, supports, flow switch, vacuum switch...)	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0400	Electrical system	
S4.0401	EDL Electrical Power Transformer (Provisional Sum)	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0402	Subscription to EDL	NOT APPLICABLE
S4.0403	Standby generator	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0404	Main ATS panel	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0405	Starter control panel	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0406	Electric actuator for globe valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0407	Electrical actuator for globe valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0408	Electric actuator for gate valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0409	Low voltage cables	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0410	UPS system	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0411	Grounding system - Lightning & Surge Protections	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
S4.0412	Electric accessories (cables, Lugs, clamps, connectors, conduits, cable trays, insulation, junction boxes ...)	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
S4.0500	Instrumentation and Control	
S4.0501	Piezoresistive Level measurement	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0502	Piezoresistive level measurement at reservoir	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0503	Piezoresistive pressure measurement	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0504	Manometer with three way isolating valve	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0505	Flow measurement	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0506	Flow switch	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
S4.0507	Water level protection system with 3 electrodes and relay	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0508	Temperature measurement controller	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0509	Oil leakage detection system	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0510	Telemetry cable	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Cf1 / Cf0 * E1 / E0 + 0.15\}$
S4.0511	HMI panel	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
S4.0512	Control accessories (PLC, RTU, programming, transmission cables...)	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
S4.0600	Domestic Plumbing and drainage system	NOT APPLICABLE
S4.0700	Fire extinguishers	NOT APPLICABLE
S4.0800	Electrical installation for buildings	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM – QABB ELIAS AND MRAIJAT
VOLUME 5 - BILL OF QUANTITIES PART A - PREAMBLE TO BILL OF QUANTITIES

ITEM Nb.	DESCRIPTION	UNIT
W4.0000	Mechanical, Electrical and Control Installation etc.	
W4.0100	Pumping system	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
W4.0200	Piping and accessories	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
W4.0300	Gas chlorination system	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
W4.0400	Electrical system	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
W4.0500	Instrumentation and Control	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
W4.0600	Lifting and Handling equipment	$P1 = P0 * \{0.15 * L1 / L0 + 0.70 * Pu1 / Pu0 * E1 / E0 + 0.15\}$
W4.0700	Domestic Plumbing and drainage system	NOT APPLICABLE
W4.0800	Fire extinguishers	NOT APPLICABLE
W4.0900	Electrical installation for buildings	$P1 = P0 * \{0.15 * L1 / L0 + 0.55 * Cf1 / Cf0 * E1 / E0 + 0.15 * Lma1 / Lma0 * E1 / E0 + 0.15\}$
W4.1000	Training, testing and commissioning	NOT APPLICABLE
W4.1100	Water Analysis	NOT APPLICABLE

For all the parameters figuring in the price adjustment formulas, refer to Volume 1, Conditions of Contract, Clause 70.1.

4.000 BILL C –TRANSMISSION PIPELINES

4.010 GENERAL

The hydraulic design of transmission pipelines is based on topographic surveys done during the design period. However, some or all topographical points like stakes or benchmarks may have disappeared due to works executed after this period.

For this reason, the Contractor shall be deemed to have covered himself for checking quantities and for making any necessary surveys and investigations prior to placing or ordering for materials.

4.011 TOPOGRAPHIC SURVEY

The price shall cover performing land surveying of the designed networks layout. The surveyor shall start from approved benchmarks and shall mark the stations shown on drawings, using steel pegs and high quality paint. Distance between two stakes or pegs shall not exceed 30m.

Moreover, the Contractor is supposed to visit the site to check and be familiar with the present status of the survey.

EDM devices shall be used exclusively.

New longitudinal profiles shall be issued on transparent paper and AutoCAD files and shall be submitted to the Engineer's approval.

Vertical scale 1/200 and horizontal scale 1/2000

Measurement of topographic survey shall be in horizontal kilometres.

4.012 TRIAL PIT

Trial pits shall be measured by number and shall include for excavation in any material, any type of soil and rock, to a depth not exceeding 3m, hand excavation as necessary, backfilling, reinstatement of the surface to its original condition and reinstatement of road surfaces.

Payment will only be made for trial pits ordered in writing by the Engineer. Any measures taken by the Contractor to locate existing services or determine ground condition shall be included within the respective excavation item, whether separately itemised or not, and shall not be measured for payment.

4.013 TRIAL TRENCH

Trial trenches shall be measured by linear meters and shall include for all requirements as stipulated in item 'Trial pit' above.

4.014 AS-BUILT DRAWINGS

As-built drawings shall be measured by horizontal km and shall consist of new profiles, plans and details on scale similar to the design drawings scale.

Pipes, manholes, and accessories shall be shown clearly as well as effective cover depth of the crown of the pipe and distance between pipe axis and carriage edge or sidewalk, and between manhole cover centre and electric pylons or buildings corners. Adequate number (minimum one for each road or 250 m which is less) of transversal sections showing all existing underground utilities/or facilities, should also be submitted.

Payment shall only be made for as-built drawings approved by the Engineer and submitted on paper and AutoCAD files.

4.015 SUPPLY OF DUCTILE IRON K9 PIPES INCLUDING ALL NECESSARY FITTINGS

Ductile iron K9 pipes shall be classified for payment according to diameter and shall be measured in linear meters of pipeline supplied and stored in good conditions.

The price shall cover all fittings, bends, tees, reducers, detachable joints, flanges, bolts, nuts, as well as fittings, joints and jointing material.

Only pipes, fittings, junctions, bends, etc... supplied and stored in good conditions and accepted by the Engineer shall be taken into account for payment.

4.016 SUPPLY OF HDPE PIPES INCLUDING ALL NECESSARY FITTINGS

Price shall include all the requirements as stipulated in item 4.015 above (for HDPE pipes).

4.017 TRENCH EXCAVATION

The price shall be calculated in terms of linear meters of dug trench only. The minimum width of trench is shown on the corresponding Contract drawings (refer to standard drawings).

This price shall include but shall not be limited to:

- Excavating in any type of soil, rock, structural fill, contaminated fill, clay or others.
- Excavating by hand or machine.
- Excavating in asphalted or non-asphalted roads, in fields, in valleys, in accessible or non accessible areas, including the execution of temporary access roads if needed.
- De-watering operations necessary for keeping the excavation free from water whether rain water or any other sources.
- Extra excavation depth carried out as shown on the longitudinal profiles or under the direction of the Engineer.
- Extra excavation carried out in width for laying of the HDPE duct.
- Transport of unsuitable backfilling materials to disposal sites approved by the Engineer.
- Levelling or grading and compacting the bottom of excavations.
- Supporting, protecting and maintaining existing services and utilities.
- Temporary or permanent supports to sides of excavation, roads or structures as required by the Engineer (soil supports, sheet piling, etc...) or other method proposed by the Contractor and approved by the Engineer (micro-tunnelling , concrete piles, etc...).
- Traffic regulation and safety provisions as described in Volume 1- Appendix 1 – CDR Safety, Health and Environmental Regulations.
- Repairing of all damaged utilities caused by the execution of the works.

Any excavated quantity will not be paid by the Employer under this item, if it is dumped or accidentally falls in the valley or in the field.

4.018 SAND BEDDING AND SURROUNDS

The sand bedding and surrounds shall be classified for payment according to pipe diameter and shall comply with the corresponding contract drawings (refer to standard drawings), and shall be measured by linear meters of completed pipeline.

Price shall include supply of material, testing and compaction.

4.019 LAYING OF PIPES

Laying of pipes shall be classified for payment according to diameter and shall be measured in linear meters of completed pipeline in place measured along the crown of the pipeline and the price shall include but not be limited to:

- Removal of any abandoned pipework within the excavation.
- Distributing pipes along the trench.
- Checking and cleaning pipe from dirt, oil, grease, etc..
- Supply of temporary or final supports.
- Laying of pipes.
- All necessary types of jointing, welding, etc...
- Checking pipe alignment and evaluations using topographical instruments.
- Installation of all fittings, bends, tees, reducers, dismantling joints, flanges, couplings, bolts, nuts as well as hauling, transport, unloading, and staking of pipes, fittings, joints, and jointing material.

The length measured for payment shall include the lengths of all fittings, valves and accessories installed in the line.

Only pipes, fittings, junctions, bends, etc... actually laid, jointed and tested and accepted by the Engineer shall be taken into account for payment.

4.020 BACKFILLING OF TRENCHES

Backfilling of trenches shall be classified for payment according to pipe diameter and shall be measured by linear meters along the crown of the pipeline (refer to standard drawings).

Backfilling shall include for:

- Supply of materials.
- Backfilling in layers and compaction.
- Testing and compaction
- Supply and installation of the warning tape (Marker Tape)

4.021 EXTRA OVER FOR MANUAL WORKS

The price shall include any extra costs for manual work necessary for trench excavation, bedding and surround, transport and laying of pipes, backfilling of trenches, transport and installation of accessories and fitting, construction of manholes, testing of pipes, execution of reinforced concrete surround, and any other activity necessary to complete the works to the satisfaction of the Engineer.

4.022 SUPPLY AND INSTALLATION OF AIR RELEASE VALVES

Air valves shall be measured by number for each air valve size, and nominal pressure, and shall include gate valves, riser pipe, flanges, bolts, nuts, supports and all necessary components to provide a complete installation.

Reinforced concrete chambers, covers and frames shall be measured separately by number. Cutting and reinstatement shall also be measured separately.

4.023 SUPPLY AND INSTALLATION OF PRESSURE REGULATING VALVES

Supply and installation of pressure regulating valves shall be measured by number for each diameter of pipeline and shall include the supply and installation of thrust flanges, by pass pipe, bends, tees, orifice plates, filters, butterfly valves, short piece pipes, gate valves, air release valves, manometers, collars, flanges, dismantling joints, chamber cover and frame in addition to concrete works which include concrete chamber, supports and steel reinforcement and all works necessary to form a complete installation according to standard drawings.

4.024 SUPPLY AND INSTALLATION OF PRESSURE REGULATING, PRESSURE SUSTAINING VALVE AND WATERMETER

Supply and installation of pressure regulating, pressure sustaining valves and watermeter shall be measured by number for each diameter of pipeline and by pressure class and shall include the supply and installation of thrust flanges, bypass pipe, bends, tees, orifice plates, filters, butterfly valves, short piece pipes, gate valves, flow straightener, globe valve, air release valves, manometers, collars, flanges, dismantling joints, chamber cover and frame in addition to concrete works which include complete concrete chamber, supports, steel reinforcement, step irons, access ladders, drain and all works necessary to form a complete installation according to standard drawings.

4.025 SUPPLY AND INSTALLATION OF PRESSURE SUSTAINING VALVE AND WATERMETER

Supply and installation of pressure sustaining valve and watermeter shall be measured by number for each diameter of pipeline and by pressure class and shall include the supply and installation of thrust flanges, bypass pipe, bends, tees, orifice plates, filters, butterfly valves, short piece pipes, gate valves, flow straightener, globe valve, air release valves, manometers, collars, flanges, dismantling joints, chamber cover and frame in addition to concrete works which include complete concrete chamber, supports, steel reinforcement, step irons, access ladders, drain and all works necessary to form a complete installation according to standard drawings.

4.026 SUPPLY AND INSTALLATION OF WATERMETER

Supply and installation of watermeter shall be measured by number for each diameter of pipeline and shall include the supply and installation of thrust flanges, bypass pipe, bends, tees, orifice plates, filters, butterfly valves, short piece pipes, gate valves, flow straightener, air release valves, collars, flanges, dismantling joints, chamber cover and frame in addition to concrete works which include complete concrete chamber, supports, steel reinforcement, step irons, access ladders, drain and all works necessary to form a complete installation according to standard drawings.

4.027 SUPPLY AND INSTALLATION OF WASHOUTS

Washouts shall be measured by number for each washout size and pressure class and shall include gate valves, duck foot bends, tees, flap valves, drain pipe UPVC or D.I. pipes for washout with the needed length (excavation, bedding, supply, laying and backfilling) and all necessary items to make a complete washout.

Reinforced concrete chambers, covers and frames, shall be measured separately by number. Cutting and reinstatement shall be also measured separately.

4.028 SUPPLY AND INSTALLATION OF CONNECTIONS TO EXISTING RESERVOIRS OR CATCHMENT STRUCTURES

Connection to existing reservoir shall be measured by number and shall include pipes, bends, tees, concrete works, steel reinforcement, strainers, concrete supports, inserts, float valves, filters, etc... (including excavation, bedding, compacting, supply, transportation, laying and backfilling, etc...) and all necessary items to make a complete connection system to existing reservoir.

4.029 CONNECTION TO EXISTING PIPES

Connection to existing pipes shall be measured by number of completed connection unit installed in place and the price shall include but not be limited to:

- Extra excavation works to locate the existing pipe.
- Removal of any abandoned pipework within the excavation.
- Distributing pipes along the trench.
- Checking and cleaning pipe from dirt, oil, grease, etc...
- Supply of temporary or final supports.
- All necessary types of jointing, welding, etc...
- Checking pipe alignment and elevations using topographical instruments.
- Transport the material from the warehouse and/or storage area to site.
- Supply and installation of all fittings, bends, tees, reducers dismantling joints, flanges, adaptors couplings, bolts, nuts, as well as, hauling, transport, unloading, and staking of pipes, fittings, joints and jointing material.

The unit measured for payment shall include all fittings and accessories installed in the line. Only pipes, fittings, junctions, bends, etc... actually installed, jointed and tested and accepted by the Engineer shall be taken into account for payment.

4.030 SUPPLY AND INSTALLATION OF BRIDGE OR CULVERT CROSSING

Bridge or Culvert crossing shall be classified for payment by number of completed crossing unit installed in place and the price shall include but not be limited to:

- Extra excavation works.
- Removal of any abandoned pipework within the excavation.
- Distributing pipes along the structure.
- Checking and cleaning pipe from dirt, oil, grease, etc...
- Supply of temporary and/or final supports including supply and installation of metal works needed to support the pipe.
- All necessary types of jointing, welding, etc..
- Checking pipe alignment and elevations using topographical instruments.
- Supply and installation of all fittings bends, tees, reducers dismantling joints, flanges, couplings, bolts, nuts, as well as, hauling, transport, unloading, and staking of pipes, fittings, joints, and jointing material.

The Unit measured for payment shall include all fittings, accessories installed on the line.

Only pipes, fittings, junctions, bends, etc... actually installed, jointed, tested and accepted by the Engineer shall be taken into account for payment.

4.031 CONSTRUCTION OF PRE-CAST OR CAST IN SITU, REINFORCED CONCRETE VALVE CHAMBERS

Valve chambers, where not included in another item, shall be measured by number according to chamber internal length and width and shall include for excavation, formwork, concrete, mass concrete, blinding etc..., reinforcement, rendering, external damp-proofing, painting, backfilling, floor drain, soak away, step irons access ladders, compacted gravel, sub-base and base layers, asphalt, etc... and all necessary items to make a complete chamber according to the contract drawings.

The valve chamber cover and frame shall be measured by number separately.

4.032 SUPPLY AND INSTALLATION OF VALVE CHAMBER COVER AND FRAME

Valve chamber cover and frame shall be measured by number and shall include all necessary materials and equipment including installation, labour, painting etc... in order to get an installed cover and frame according to the specifications.

4.033 SUPPLY AND INSTALLATION OF SURFACE BOX UNITS

Surface box units shall be measured by number and shall include for spindle guards, extension spindles, caps, couplings, covers, surface box units, and all necessary items to make a complete surface box unit.

4.034 CONCRETE WORKS

Cast in situ or precast concrete shall be measured by net volume shown on drawings.

Concrete, whether included in another item or separately measured, shall include for:

- All material, equipment, labour, transport, admixtures (retarders, plasticizers, waterproofing products, ...) batching, mixing, placing, vibrating, curing, testing.
- Formwork (Formwork shall be “sawn” finish to all buried external faces of concrete below a line 200mm below ground level and shall be “wrought” finish to all other faces).
- All needed excavation in all kinds of soils and rocks, use of all adequate equipment, transport of soil to disposal sites approved by the Engineer, labour, dewatering, temporary and/or final retaining structures for trenches or open digs, backfilling, compacting, cutting of asphalt.
- Forming of chamfers (25mm x 25mm) to all exposed external angles.
- Forming expansion, contraction, movement and construction joints and for all water stops, jointing materials, sealing compounds and formwork necessary for forming such joints;
- Building in of all pipes and fittings, bolts, frames, iron and steelwork and the like.
- Finishing of surfaces.
- Reinforcement.
- All necessary items to have the concrete works according to the specifications.

4.035 TESTING AND COMMISSIONING OF POTABLE WATER PIPES

Testing and commissioning shall be measured by linear meters along the pipe crown. The price shall include all the material, equipment and labour (water, pumps, barrels, manometers, valves, labour, power supply, etc...) and no payment shall be made before getting the Engineer’s approval.

4.036 ROAD REINSTATEMENT

4.036.1 Cutting

Cutting of paved roads shall be measured by linear meters along the pipe crown. It shall include for asphalt cutting at both sides of the trench, and removal of excavated material to disposal sites.

Cutting and breaking of concrete pavements shall be measured by square meters, it shall include for cutting and breaking out of concrete pavement (the width of the cut trenches will be as shown on standard drawings) and removal of excavated material to disposal sites.

The price shall include cutting works and removal of material for widening of trench for chambers or other ancillary structures and fittings.

4.036.2 Reinstatement

Reinstatement of asphalt pavement shall be classified for payment according to type of roads, as for main roads two layers of asphalt shall be applied, and one layer for the other roads, and shall be measured by square meters of completed asphalted and reinstated trench, according to the quantity actually executed but not to exceed the quantities shown on standard drawings. For trench reinstatement, the price shall include for:

- Transport of material.
- Recutting works.
- Base and sub-base courses, material.
- Compaction.
- Laying and application of material,
- Tests.
- Repairing of all defects, asphalt or concrete collapse.
- Etc..

The width of asphalt layers shall be in accordance with the standard drawings.

Reinstatement shall also include for any re-cutting works of asphalt or concrete required by collapse of trench edges and for base and sub-base courses and compaction according to drawings and complying with the specifications.

Reinstatement of concrete and concrete stair cases shall be measured by square meters of completed asphalted and reinstated trench, according to the quantity actually executed but not to exceed the quantities shown on standard drawings for trench reinstatement, the price shall include for:

- Transport of material.
- Recutting works.
- Base and sub-base courses, material.
- Compaction.
- Laying and application of material,
- Tests.
- Repairing of all defects, asphalt or concrete collapse.
- Etc..

4.037 CHANGES IN COST AND LEGISLATION (BILL C –TRANSMISSION PIPELINES)

ITEM Nb	DESCRIPTION	PRICE ADJUSTMENT FORMULA
4.0000	General	
4.0001	Site Topographic Survey	NOT APPLICABLE
4.0002	Trial pit not exceeding 3m depth	$P_1 = 60\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 40\% * P_0 * \{0.15 + 0.15 * L_1 / L_0 + 0.45 * [(1.12 * B_1 + 66) / (1.12 * B_0 + 66)] + 0.25 * F_1 / F_0\}$
4.0003	Trial trench not exceeding 3m depth	$P_1 = 60\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 40\% * P_0 * \{0.15 + 0.15 * L_1 / L_0 + 0.45 * [(1.12 * B_1 + 66) / (1.12 * B_0 + 66)] + 0.25 * F_1 / F_0\}$
4.0004	As-built drawings	NOT APPLICABLE
4.1000	Pipeworks	
4.1100	Supply of ductile iron K9 pipes including all necessary fittings (Bends, Tees, Reducers, Flanges, etc...)	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Tf_1 / Tf_0 * E_1 / E_0 + 0.15\}$
4.1200	Supply of HDPE pipes including all necessary fittings	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Et_1 / Et_0 * Yn_1 / Yn_0 + 0.15\}$
4.1300	Trench excavation	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
4.1400	Sand bedding and surrounds	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
4.1500	Laying of ductile iron pipes	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Tf_1 / Tf_0 * E_1 / E_0 + 0.15\}$
4.1600	Laying of HDPE pipes	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Et_1 / Et_0 * Yn_1 / Yn_0 + 0.15\}$
4.1800	Backfilling of Trenches including compaction and testing	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
4.1900	Supply and installation of culvert crossings	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
4.11000	Extra over for manual works including: trench excavation, sand bedding and surround, laying of pipes, backfilling of trenches and execution of reinforced concrete surround	$P_1 = P_0 * \{0.85 * L_1 / L_0 + 0.15\}$
4.2000	Accessories	
4.2100	Supply and installation of air release valves	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
4.2200	Supply and installation of pressure regulating valves	$P_1 = 0.4 * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\} + 0.6 * \{45\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\} + 10\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 45\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}\}$
4.2300	Supply and installation of pressure sustaining valves, pressure regulating valves and watermeters	$P_1 = 0.4 * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\} + 0.6 * \{45\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\} + 10\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 45\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}\}$

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM – QABB ELIAS AND MRAIJAT
VOLUME 5 - BILL OF QUANTITIES **PART A - PREAMBLE TO BILL OF QUANTITIES**

ITEM Nb	DESCRIPTION	PRICE ADJUSTMENT FORMULA
4.2400	Supply and installation of pressure sustaining valves and watermeters	$P_1 = 0.4 * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\} + 0.6 * \{45\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\} + 10\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 45\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}\}$
4.2500	Supply and installation of watermeters	$P_1 = 0.4 * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\} + 0.6 * \{45\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\} + 10\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 45\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}\}$
4.2600	Supply and installation of washouts	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
4.2700	Supply and installation of connections to existing reservoirs	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
4.2800	Supply and installation of connections to spring catchment structures	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
4.2900	Supply and installation of connections to existing pipes	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Pu_1 / Pu_0 * E_1 / E_0 + 0.15\}$
4.3000	Valve chambers and Surface box units	
4.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)	$P_1 = 45\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\} + 10\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 45\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
4.3200	Valve chamber cover	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Tf_1 / Tf_0 * E_1 / E_0 + 0.15\}$
4.3300	Surface box units for washouts	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Tf_1 / Tf_0 * E_1 / E_0 + 0.15\}$
4.4000	Concrete Works	
4.4001	Mass concrete - Class C20 for blinding	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.3\}$
4.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.3\}$
4.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels	$P_1 = 50\% * P_0 * \{0.15 * L_1 / L_0 + 0.70 * Lmc_1 / Lmc_0 * E_1 / E_0 + 0.15\} + 5\% * P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\} + 45\% * P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$
4.5000	Testing and commissioning of potable water pipes	NOT APPLICABLE
4.6000	Road Reinstatement	
4.6100	Cutting	
4.6101	Cutting of paved roads for water pipes	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
4.6102	Cutting, breaking-out and removal of concrete pavement or stair cases for water pipes	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
4.6200	Reinstatement	
4.6201	Reinstatement in one layer of paved roads including recutting works	$P_1 = 50\% * P_0 * \{0.15 + 0.15 * L_1 / L_0 + 0.45 * [(1.12 * B_1 + 66) / (1.12 * B_0 + 66)] + 0.25 * F_1 / F_0\} + 50\% * P_0$
4.6202	Reinstatement of concrete pavement or stair cases for water pipes, including base, sub-base courses and concrete pavement	$P_1 = P_0 * \{0.45 * C_1 / C_0 + 0.15 * L_1 / L_0 + 0.10 * F_1 / F_0 + 0.30\}$

For all the parameters figuring in the price adjustment formulas, refer to Volume 1, Conditions of Contract, Clause 70.1.

5.000 BILL D - BOREHOLES

5.010 MOBILIZATION

The price shall be paid for on lump sum basis including all costs and labour expenses necessary to the delivery, installation and dismantling of the drilling and testing equipments as well as all tools and devices, other than the pumping equipment. The price also includes all expenses necessary to the preparation of the site (cleaning of land and preparing access roads).

5.011 DRILLING

Execution of drilling works by rotary method for wells of different diameters.

The price shall be paid for every drilled linear meter and shall include all drilling costs, without exception (power, fuel, mud, water, air depression of parts and machinery, etc...) and the labour expenses required for drilling a well to the required diameter as well as taking sample cuttings from the ground and all measurements as stipulated in 704.2 of the Technical Specifications Vol. 3 and as per instructions from the Engineer.

5.012 GEOPHYSICAL LOGGING

The price shall be paid for every logged linear meter and shall include all logging costs without exception (logging system, probes, drawwork, power, etc..) and the labour expenses required for logging a well to the required depth.

5.013 VERTICALITY AND ALIGNMENT TEST

The price shall be paid for on lump sum basis including all costs and labour expenses necessary to conduct the tests, as well as all tools and devices (percussion machine, tripod, dummies, etc..), as stipulated in 705.1.1 of the Technical Specifications Vol. 3.

5.014 CASINGS

The price shall be paid on a linear basis and shall include the supply, transport, on-site storage and installation of casings including all the necessary accessories.

5.015 SCREENS

The price shall be paid for installed linear meter of screens including the supply, transport, on-site storage and installation of screens with all the necessary accessories.

5.016 WELL GROUTING

5.016.1 Supply of Cement

The price shall be paid for every ton of cement delivered on-site including supply, transport and on-site storage in its original packing.

5.016.2 Injection of cement in the annular space

The price shall be paid for every meter of placed grout including the preparation of the slurry (supply of the required quantities of water and sand) by using supplied cement and additives (where necessary). Grout shall be placed as stipulated in 704.9 of the Technical Specifications Vol. 3, and the Contractor shall bear all costs.

5.017 WELL DEVELOPMENT BY PUMPING

5.017.1 Supply and install of pumping equipment

The price shall be paid for every operation including all costs for supplying, transportation and installation of the pump at the specified discharge and head and later dismantle. This includes without restriction all costs and labour expenses necessary to the development of the well.

5.017.2 Well development (pumping at different rates)

The price shall be paid for on the basis of every hour of effective pumping and shall include operating the pump at progressively increasing rates including all the necessary requirements of power supply, generators, fuel, etc..

5.018 PUMPING TESTS

5.018.1 Step drawdown test

The price shall be paid for on the basis of every hour of effective pumping and shall be done with the same pumping system used in the development stage. The price shall include without restriction all the necessary labour, power supply, continuous level and flow measurements as stipulated in 704.12 of the Technical Specifications Vol. 3.

5.018.2 Constant rate test

The price shall be paid for on the basis of every hour of effective pumping, the pump shall be operated at a constant rate for 72 hours non-stop. The per hour price shall include all the requirements as stipulated in the step drawdown test above.

5.019 WATER ANALYSIS

5.019.1 Collection and delivery of water samples to an approved laboratory

The price shall be paid for on the basis of every water sampling operation and shall include all costs, sterilized supplies, transport and labour expenses necessary for water sampling as stipulated in 704.14 of the Technical Specifications Vol.3.

5.019.2 Physico-chemical analysis

The price shall be paid for on the basis of every analysis carried out including the interpretation and submittal of results.

5.019.3 Bacteriological analysis

The price shall be paid for on the basis of every analysis carried out including the interpretation and submittal of results.

5.020 REPORTS AND AS-BUILT DRAWINGS

5.020.1 Daily driller's log, detailed report and as-built drawings

The price shall be paid on a lump sum basis for the whole report and shall include the daily driller's log as stipulated in 706 of the Technical Specifications Vol. 3, and according to the Engineer's instructions.

5.020.2 Final well report

The price shall be paid for on a lump sum basis for the final report and shall include all requirements as stipulated in item "Daily driller's log" above.

5.021 CHANGES IN COST AND LEGISLATION (BILL E – BOREHOLES)

ITEM Nb	DESCRIPTION	PRICE ADJUSTMENT FORMULA
1.0000	Site Preparation	
1.0100	Site preparation and set up borehole drilling unit and later dismantle	NOT APPLICABLE
1.1000	Drilling by rotary	
1.1100	Drilling at nominal diameter 22"	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.1200	Drilling at nominal diameter 17.5"	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.1300	Drilling at nominal diameter 14 ^{3/4"}	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.2000	Well Construction	
1.2100	Supply, transport and install 18" black steel casing 5mm thick	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Ta_1 / Ta_0 * E_1 / E_0 + 0.15\}$
1.2200	Supply, transport and install 15.5" black steel casing 5mm thick	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Ta_1 / Ta_0 * E_1 / E_0 + 0.15\}$
1.2300	Supply, transport and install 12" carbon steel casing 6.35mm thick	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Ta_1 / Ta_0 * E_1 / E_0 + 0.15\}$
1.2400	Supply, transport and install 12" carbon steel bridge slotted screens 6.35mm thick	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.70 * Ta_1 / Ta_0 * E_1 / E_0 + 0.15\}$
1.3000	Verticality and alignment tests	
1.3100	Carry out verticality and alignment tests	NOT APPLICABLE
1.4000	Grouting	
1.4100	Supply and transport cement	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.4200	Pump cement in annular space	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.5000	Geophysical logging	
1.5100	Water temperature log	NOT APPLICABLE
1.5200	Water conductivity log	NOT APPLICABLE
1.5300	Spontaneous Potential log	NOT APPLICABLE
1.5400	Natural Gamma Ray log	NOT APPLICABLE
1.5500	Resistivity log	NOT APPLICABLE
1.5600	Caliper log	NOT APPLICABLE
1.5700	Geophysical report	NOT APPLICABLE
1.6000	Well Development	
1.6100	Supply, install and remove test pumping unit (12 l/s, depth 420m) and all associated equipment including discharge pipeline	NOT APPLICABLE
1.6200	Pumping and surging at different rates	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.6300	Supervise development test	NOT APPLICABLE
1.7000	Well Testing	
1.7100	Step drawdown test	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.7200	Water level recovery measurements	NOT APPLICABLE
1.7300	Constant rate test	$P_1 = P_0 * \{0.15 * L_1 / L_0 + 0.25 * F_1 / F_0 + 0.10 * Eqp_1 / Eqp_0 * E_1 / E_0 + 0.50\}$
1.7400	Water level recovery measurements	NOT APPLICABLE
1.8000	Water Analysis	
1.8100	Collection and delivery of water samples to an approved laboratory	NOT APPLICABLE
1.8200	Physico-chemical analysis	NOT APPLICABLE
1.8300	Bacteriological analysis	NOT APPLICABLE
1.9000	Reports	
1.9100	Detailed daily reports	NOT APPLICABLE
1.9200	Final well report	NOT APPLICABLE

For all the parameters figuring in the price adjustment formulas, refer to Volume 1, Conditions of Contract, Clause 70.1.

PART B

BILL OF QUANTITIES

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

MRAIJAT PUMPING STATION

ITEM Nb.	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.0000	General				
1.0001	Checking, completing, and/or performing topographic survey and site delimitation	Site	1.00		
1.0002	Site clearance	L.S.	1.00		
1.0003	Site rearrangement after construction	L.S.	1.00		
1.0004	Construction of access road	sq.m.	1,000.00		
	Sub-Total 1.0000				
1.1000	Earthworks				
1.1100	Excavation				
1.1101	Excavation in all types of soils and rocks and demolition of existing concrete structures and transport of unsuitable backfilling material to disposal sites	cu.m	800.00		
	Sub-Total 1.1100				
1.1200	Preparation of formation under buildings				
1.1201	Supply, preparation and compaction of the granular beds under the constructions foundations	cu.m	10.00		
	Sub-Total 1.1200				
1.1300	Backfilling				
1.1301	Backfilling and compaction	cu.m	200.00		
	Sub-Total 1.1300				
	Sub-Total 1.1000				
1.2000	Concrete works and accessories				
1.2100	Concrete works				
1.2101	Blinding and mass concrete Class C20	cu.m	30.00		
1.2102	Reinforced Concrete Class C30, 350 kg of cement /cu.m, for building, including formwork	cu.m	120.00		
1.2103	Steel reinforcement for buildings	Ton	12.00		
	Sub-Total 1.2100				
	Sub-Total 1.2000				
1.3000	Blockwork, cladding, and plastering				
1.3001	Hollow concrete block wall 20 cm thick	sq.m	22.00		
1.3002	Rendering or plastering of interior and exterior surfaces	sq.m	135.00		
1.3003	Exterior rendering with colored bush - hammered render	sq.m	125.00		
1.3004	Cladding with natural stone (minimum thick.5 cm)	sq.m	67.00		
1.3005	Bush - Hammered stone (Stone Jambs, Lintels, Skirting & Capping)	lin.m	42.00		
1.3006	Supply and installation of roof bricks	sq.m	40.00		
	Sub-Total 1.3000				
1.4000	Waterproofing, thermal insulation				
1.4001	Waterproofing of buildings roof slabs with thermal insulation	sq.m	36.00		
	Sub-Total 1.4000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

MRAIJAT PUMPING STATION

ITEM Nb.	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.5000	Metal and aluminium works				
1.5100	Metal works				
1.5101	Supply and installation of exterior steel doors and windows including glazing and painting.	sq.m	9.00		
1.5102	Supply and installation of metal works : steel protection bars for exterior windows, metallic ladders with or without safety hoops, gratings for channels, railings, locks and all other metal works, including painting.	kg	600.00		
	Sub-Total 1.5100				
1.5200	Aluminium works				
1.5201	Supply and installation of interior aluminium doors and exterior aluminium windows,including glazing.	sq.m	4.00		
	Sub-Total 1.5200				
	Sub-Total 1.5000				
1.6000	Finishing works				
1.6100	Industrial flooring				
1.6101	Supply and application of industrial flooring	sq.m	25		
	Sub-Total 1.6100				
1.6200	Washable Paint internal or external use coating				
1.6201	Supply and application of internal or external use coating	sq.m	125		
	Sub-Total 1.6200				
	Sub-Total 1.6000				
1.7000	Fence				
1.7001	Supply and installation of site's external fence, including painting	lin.m	50.00		
1.7002	Supply and installation of the access gate (L = 4m)	L.S.	1.00		
	Sub-Total 1.7000				
1.8000	Asphalting				
1.8001	Subgrade compaction, sub-base and base preparation, and asphalting	sq.m	150.00		
	Sub-Total 1.8000				
	TOTAL OF MREIJAT PUMPING STATION CIVIL WORKS				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

QABB ELIAS RESERVOIRS (CAPACITY 2X400 m³)

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.0000	General				
1.0001	Checking, completing, and/or performing topographic survey and site delimitation	Site	1		
1.0002	Site clearance	L.S.	1		
1.0003	Site rearrangement after construction	L.S.	1		
	Sub-Total 1.0000				
1.1000	Earthworks				
1.1100	Soil investigations				
1.1101	Boring, core sampling (minimum 3 probes required), SPT tests and report	L.S.	1		
	Sub-Total 1.1100				
1.1200	Excavation				
1.1201	Excavation in all types of soils and rocks and demolition of existing concrete structures and transport of unsuitable backfilling material to disposal sites	cu.m	2,400		
	Sub-Total 1.1200				
1.1300	Preparation of formation under reservoirs and other constructions				
1.1301	Supply, preparation and compaction of the granular beds in addition to laying the polyethylene sheet under the construction's foundations	cu.m	60		
	Sub-Total 1.1300				
1.1400	Backfilling				
1.1401	Backfilling and compaction	cu.m	250		
	Sub-Total 1.1400				
	Sub-Total 1.1000				
1.2000	Concrete works and accessories				
1.2100	Concrete works				
1.2101	Blinding and mass concrete Class C20	cu.m	20		
1.2102	Reinforced Concrete Class C30, 400 kg of cement /cu.m, for reservoirs, including formwork	cu.m	220		
1.2103	Reinforced Concrete Class C30, 350 kg of cement /cu.m, for other buildings, including formwork	cu.m	51		
1.2104	Extra over items 1.2102 and 1.2103 for fair faced concrete in reservoirs and other buildings	sq.m	1,130		
1.2105	Concrete surface leveling with mechanical float	sq.m	160		
1.2106	Cyclopean concrete	cu.m	200		
1.2107	Steel reinforcement for reservoirs and other buildings	Ton	33		
	Sub-Total 1.2100				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

QABB ELIAS RESERVOIRS (CAPACITY 2X400 m³)

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.2200	Water stop and bearing pads				
1.2201	Water stop up to 25 cm in width	lin.m	64		
1.2202	Neoprene pads between walls and roof slab	lin.m	64		
	Sub-Total 1.2200				
	Sub-Total 1.2000				
1.4000	Waterproofing, thermal insulation, and water quality control				
1.4001	Internal lining for reservoirs	sq.m	700		
1.4002	Waterproofing of reservoirs and other buildings roof slabs with thermal insulation	sq.m	170		
1.4005	Water testing and disinfection for reservoirs of capacity 2x400 m³	L.S.	1		
	Sub-Total 1.4000				
1.5000	Metal and aluminium works				
1.5100	Metal works				
1.5101	Supply and installation of exterior steel doors and windows including glazing and painting (with blue color).	sq.m	5		
1.5102	Supply and installation of metal works: steel protection bars for exterior windows, metallic ladders with or without safety hoops, gratings for channels, railings, locks, handrail and all other metal works, including painting (blue color)	kg	1,000		
	Sub-Total 1.5100				
	Sub-Total 1.5000				
1.6000	Finishing works				
1.6100	Industrial Flooring				
1.6101	Supply and application of industrial flooring	sq.m	302		
	Sub-Total 1.6100				
1.6200	Washable Paint internal or external use coating				
1.6201	Supply and application of internal or external use coating	sq.m	575		
	Sub-Total 1.6200				
	Sub-Total 1.6000				
1.7000	Fence				
1.7001	Supply and installation of site's external fence, including painting	lin.m	115		
1.7002	Supply and installation of the access gate (L = 1.20m)	L.S.	1		
	Sub-Total 1.7000				
1.8000	Reservoir Hydraulic Accessories				
1.8100	Supply and installation of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, dismantling joints, support, etc...)				
1.8101	DI pipes, DN 200	lin.m	30		
1.8102	DI pipes, DN 250	lin.m	100		
	Sub-Total 1.8100				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

QABB ELIAS RESERVOIRS (CAPACITY 2X400 m³)

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.8200	Supply and installation of gate valves				
1.8201	Gate valve PN16, DN 200	nb	2		
	Sub-Total 1.8200				
1.8300	Valve chamber floor drains				
1.8301	Supply and installation of floor drain inside the valve chamber including pipe DN 80, flap valve	nb	1		
	Sub-Total 1.8300				
1.8400	Supply and installation of suction strainers				
1.8401	Suction strainer, DN 150	nb	1		
	Sub-Total 1.8400				
1.8500	Supply and installation of level indicators				
1.8501	Level indicator	nb	1		
	Sub-Total 1.8500				
1.8600	Supply and installation of inserts				
1.8601	Insert DN 150 mm	nb	2		
1.8601	Insert DN 200 mm	nb	4		
1.8602	Insert DN 250 mm	nb	6		
	Sub-Total 1.8600				
	Sub-Total 1.8000				
	Total QABB ELIAS RESERVOIRS (CAPACITY 2X400 m³)				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

MAKSE RESERVOIR (CAPACITY 500 m³)

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.0000	General				
1.0001	Checking, completing, and/or performing topographic survey and site delimitation	Site	1		
1.0002	Site clearance	L.S.	1		
1.0003	Site rearrangement after construction	L.S.	1		
	Sub-Total 1.0000				
1.1000	Earthworks				
1.1100	Soil investigations				
1.1101	Boring, core sampling, SPT tests and report	L.S.	1		
	Sub-Total 1.1100				
1.1200	Excavation				
1.1201	Excavation in all types of soils and rocks and demolition of existing concrete structures and transport of unsuitable backfilling material to disposal sites	cu.m	800		
	Sub-Total 1.1200				
1.1300	Preparation of formation under reservoirs and other constructions				
1.1301	Supply, preparation and compaction of the granular beds in addition to laying the polyethylene sheet under the construction's foundations	cu.m	45		
	Sub-Total 1.1300				
1.1400	Backfilling				
1.1401	Backfilling and compaction	cu.m	100		
	Sub-Total 1.1400				
	Sub-Total 1.1000				
1.2000	Concrete works and accessories				
1.2100	Concrete works				
1.2101	Blinding and mass concrete Class C20	cu.m	15		
1.2102	Reinforced Concrete Class C30, 400 kg of cement /cu.m, for reservoirs, including formwork	cu.m	125		
1.2103	Reinforced Concrete Class C30, 350 kg of cement /cu.m, for other buildings, including formwork	cu.m	32		
1.2104	Extra over items 1.2102 and 1.2103 for fair faced concrete in reservoirs and other buildings	sq.m	810		
1.2105	Concrete surface leveling with mechanical float	sq.m	140		
1.2106	Cyclopean concrete	cu.m	5		
1.2107	Steel reinforcement for reservoirs and other buildings	Ton	21		
	Sub-Total 1.2100				
1.2200	Water stop and bearing pads				
1.2201	Water stop up to 25 cm in width	lin.m	35		
1.2202	Neoprene pads between walls and roof slab	lin.m	35		
	Sub-Total 1.2200				
	Sub-Total 1.2000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

MAKSE RESERVOIR (CAPACITY 500 m³)

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.4000	Waterproofing, thermal insulation, and water quality control				
1.4001	Internal lining for reservoirs	sq.m	400		
1.4002	Waterproofing of reservoirs and other buildings roof slabs with thermal insulation	sq.m	140		
1.4005	Water testing and disinfection for reservoirs of capacity 500 m³	L.S.	1		
	Sub-Total 1.4000				
1.5000	Metal and aluminium works				
1.5100	Metal works				
1.5101	Supply and installation of exterior steel doors and windows including glazing and painting (with blue color).	sq.m	4		
1.5102	Supply and installation of metal works: steel protection bars for exterior windows, metallic ladders with or without safety hoops, gratings for channels, railings, locks and all other metal works, including painting (blue color)	kg	750		
	Sub-Total 1.5100				
	Sub-Total 1.5000				
1.6000	Finishing works				
1.6100	Industrial flooring				
1.6101	Supply and application of industrial flooring	sq.m	35		
	Sub-Total 1.6100				
1.6200	Washable Paint internal or external use coating				
1.6201	Supply and application of internal or external use coating	sq.m	350		
	Sub-Total 1.6200				
	Sub-Total 1.6000				
1.7000	Fence				
1.7001	Supply and installation of site's external fence, including painting	lin.m	80		
1.7002	Supply and installation of the access gate (L = 4 m)	L.S.	1		
	Sub-Total 1.7000				
1.8000	Asphalting				
1.8001	Subgrade compaction, sub-base and base preparation, and asphalting	sq.m	35		
	Sub-Total 1.8000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

MAKSE RESERVOIR (CAPACITY 500 m³)

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.9000	Reservoir Hydraulic Accessories				
1.9100	Supply and installation of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, dismantling joints, support, etc...)				
1.9101	DI pipes, DN 100	lin.m	20		
1.9102	DI pipes, DN 125	lin.m	90		
	Sub-Total 1.9100				
1.9200	Supply and installation of gate valves				
1.9201	Gate valve PN16, DN 100	nb	1		
1.9202	Gate valve PN16, DN 125	nb	3		
	Sub-Total 1.9200				
1.9300	Valve chamber floor drains				
1.9301	Supply and installation of floor drain inside the valve chamber including pipe DN 80, flap valve	nb	1		
	Sub-Total 1.9300				
1.9400	Supply and installation of suction strainers				
1.9401	Suction strainer, DN 125	nb	1		
	Sub-Total 1.9400				
1.9500	Supply and installation of level indicators				
1.9501	Level indicator	nb	1		
	Sub-Total 1.9500				
1.9600	Supply and installation of double air release valves including isolating gate valves				
1.9601	Double air release valve including gate valve PN16, DN60 mm	nb	1		
	Sub-Total 1.9600				
1.9700	Supply and installation of water meters including Y strainers, filters, flow straighteners				
1.9701	Water meter PN16, DN 125	nb	2		
	Sub-Total 1.9700				
1.9800	Supply and installation of inserts				
1.9801	Insert DN 100 mm	nb	2		
1.9802	Insert DN 125 mm	nb	9		
	Sub-Total 1.9800				
	Sub-Total 1.9000				
	Total MAKSE RESERVOIR (CAPACITY 500 m³)				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

REHABILITATION OF QABB ELIAS PUMPING STATION AND FRENCH RESERVOIR

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.000	General Newworks are to be designed for a life of 60 years. Complementary or new design shall be carried out in compliance with BS Standard or Eurocode.				
1.001	Checking,completing, and/or performing topographic survey and site delimitation	L.S.	1.00		
1.002	Site clearance	L.S.	1.00		
1.003	Site rearrangement after construction	L.S.	1.00		
1.004	As-Built. All drawings and documents submitted by the Contractor shall have been checked and signed, shall be ready for issue and shall bear the title of the drawing, the scale, the date, the Contract number and name, the document number complying with an approved numbering system, the name and references of the contractor, the name of the employer and the engineer, the date of approval by the contractor and the signature of the person responsible for the approval.	L.S.	1.00		
	Sub-Total 1.0000				
1.1000	Earthworks				
1.1100	Demolition				
1.1101	Removing the existing plaster and damaged concrete (walls and slab)				
	- Walls	sq.m	144.00		
	- Bottom and upper Slab	sq.m	32.00		
	- Floor including Beams and slab	sq.m	32.00		
	Sub-Total 1.1100				
1.1200	Excavation				
1.1201	Excavation in all types of soils and rocks for the construction of the new retaining wall and transport of unsuitable backfilling material to disposal sites	cu.m	1.00		
	Sub-Total 1.1200				
	Sub-Total 1.1000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

REHABILITATION OF QABB ELIAS PUMPING STATION AND FRENCH RESERVOIR

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.2000	Concrete works and accessories				
1.2100	Concrete works				
1.2101	Blinding and mass concrete Class C20	cu.m	3.20		
1.2102	Reinforced Concrete Grade C37 (cubic sample - 37MPa)				
	- Concrete repair for reservoir, including:	sq.m	238.00		
	- Anchoring Rebars	u	1,181.00		
	- Reinforced Concrete for Slab on grade Th = 15cm - including formwork, slope, chamfer...	cu.m	7.35		
	- Jacketing by shotcrete or concrete, Th = 15cm, including formwork	cu.m	24.15		
	- Concrete repair for the upper outdoor slab of the reservoir, including:				
	- cleaning and debonding of damaged concrete	sq.m	25.00		
	- Apply concrete repair type SikaRep or similar	sq.m	25.00		
	- creation of concrete beam on garde to receive waterproofing flashing membrane, including rebars anchoring	l.m	10.20		
	- Supply and apply 2 rainwater drainage	u	2.00		
	- Concrete works for pumping station slab, including:				
	- cleaning and debonding of damaged concrete	sq.m	15.75		
	- Apply concrete repair type SikaRep or similar	sq.m	15.75		
	- Supply and apply a self-levelling concrete to creat slope	sq.m	15.75		
	- Creation of openings in the slab as per drawings for the installation of new pumps.	L.S	1.00		
	- Concrete repair for the existing outdoor stairs and other damaged concrete	L.S	1.00		
	- Creation of a new Manhole - Flowmeter Chamber				
	- Anchoring rebars	u	106.00		
	- Concrete wall - Grade C30	cu.m	3.20		
	- metallic frame and cover	L.S	1.00		
1.2103	Steel reinforcement	ton	5.00		
	Sub-Total 1.2000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

REHABILITATION OF QABB ELIAS PUMPING STATION AND FRENCH RESERVOIR

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.3000	Waterproofing				
1.3101	Internal Cimentitious Waterproofing, including:				
	Supply and Apply at least 2 coats of cimentitious mortar on walls and slab	sq.m	210.00		
	Concrete treatment close to existing pipes passage	L.S	1.00		
	Waterproofing Test	L.S	1.00		
1.3102	Supply and apply an External waterproofing membrane, including:				
	- Surface preparation	sq.m	25.00		
	- Supply and apply a self-levelling concrete to create slope (screed)	sq.m	25.00		
	- Bituminous membrane	sq.m	25.00		
	- Supply and apply an aluminium waterproofing flashing	l.m	23.00		
	- galvanized metallic cover	l.m	14.50		
	- Waterproofing Test	L.S	1.00		
	- Supply and apply an Extruded Polystyrene panels (Th:5cm)	sq.m	25.00		
	- Supply and apply removable tiling	sq.m	25.00		
	Sub-Total 1.3000				
1.4000	Metal works				
	- Beams	kg	1,300.00		
	- Columns	kg	218.00		
	- Bracing	kg	55.00		
	- Accessories	kg	150.00		
	- Connections to existing structure and to concrete support	L.S	1.00		
	- Anti-corrosion	L.S	1.00		
	Sub-Total 1.4000				
1.5001	Washable Paint Internal and External coating				
	- External (Pumping station and Electrical room)	sq.m	175.00		
	- Internal (pumping station)	sq.m	150.00		
1.5002	Sandblasting and Repointing				
	Sandblast the exterior cladding to clean the stones	sq.m	150.00		
	Repointing between all the joints	lin.m	375.00		
	Sub-Total 1.5000				
1.6001	Roof tiles	sq.m	40.00		
	Sub-Total 1.6000				
	Sub-Total				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

OUADI EL DELEM SPRING CATCHMENT STRUCTURE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.0000	General				
1.0001	Checking, completing, and/or performing topographic survey and site delimitation	L.S	1		
1.0002	Site clearance and Cleaning of the catchment gallery and transport of removed material to disposal sites	L.S	1		
1.0003	Site rearrangement after construction	L.S	1		
1.0004	As Built drawings	L.S	1		
	Sub-Total 1.0000				
1.1000	Earthworks				
1.1100	Excavation				
1.1101	Excavation in all types of soils and rocks and demolition of existing concrete structures and transport of unsuitable backfilling material to disposal sites	cu.m	100		
	Sub-Total 1.1100				
	Sub-Total 1.1000				
1.2000	Concrete works and accessories				
1.2100	Concrete works				
1.2101	Reinforced Concrete Class C35, 450 kg of cement /cu.m, including formwork (without reinforcement steel)	cu.m	24.0		
1.2102	Repairing concrete, mortar concrete, restoration and preservation of reinforced concrete	sq.m	37.00		
1.2103	Steel reinforcement for buildings	Ton	2.00		
1.2103	Topcrete layer for roofs, thickness between 5 cm to 10 cm	sq.m	20.0		
	Sub-Total 1.2100				
	Sub-Total 1.2000				
1.3000	Cladding, Tiling and plastering				
1.3001	Rendering or plastering of interior and exterior surfaces	sq.m	75		
	Sub-Total 1.3000				
1.4000	Waterproofing, thermal insulation, and water quality control				
1.4001	Internal lining for reservoirs	sq.m	110		
1.4002	Waterproofing of buildings roof slabs with thermal insulation	sq.m	35		
1.4003	Geotextile sheet, with a topcrete layer (thickness 10cm)	sq.m	6		
	Sub-Total 1.4000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

OUADI EL DELEM SPRING CATCHMENT STRUCTURE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.5000	Metal works				
1.5001	Supply and installation of exterior steel doors including painting.	sq.m	2.5		
1.5002	Epoxy paint for metal, stainless steel, steel pipes and others	sq.m	3		
	Sub-Total 1.5000				
1.6000	Finishing works				
1.6100	Painting				
1.6101	Supply and application of washable internal or external use coating	sq.m	15		
	Sub-Total 1.6100				
	Sub-Total 1.6000				
1.7000	Fence				
1.7001	Supply and installation of site's external fence, including painting	lin.m	75.00		
1.7002	Supply and installation of the access gate (L = 1.20m)	L.S.	1		
	Sub-Total 1.7000				
1.8000	Reservoir Hydraulic Accessories				
1.8100	Piping and accessories				
1.8101	Hydraulic accessories (bends, tees, pipes, flanges, gaskets, joints, bolts, nuts, supports, well head piece...)	LS	1		
	Sub-Total 1.8100				
	Sub-Total 1.8000				
	Total OUADI EL DELEM SPRING CATCHMENT STRUCTURE				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

RAS EL AIN SPRING CATCHMENT STRUCTURE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.0000	General				
1.0001	Checking, completing, and/or performing topographic survey and site delimitation	L.S	1		
1.0002	Site clearance and Cleaning of the catchment gallery and transport of removed material to disposal sites	L.S	1		
1.0003	Site rearrangement after construction	L.S	1		
1.0004	As Built drawings	L.S	1		
	Sub-Total 1.0000				
1.1000	Earthworks				
1.1100	Excavation				
1.1101	Excavation in all types of soils and rocks and demolition of existing concrete structures and transport of unsuitable backfilling material to disposal sites	cu.m	350		
	Sub-Total 1.1100				
1.1200	Backfilling				
1.1201	Backfilling and compaction	cu.m	300		
	Sub-Total 1.1200				
	Sub-Total 1.1000				
1.2000	Concrete works and accessories				
1.2100	Concrete works				
1.2101	Reinforced Concrete Class C35, 450 kg of cement /cu.m, including formwork (without reinforcement steel)	cu.m	30.0		
1.2102	Repairing concrete, mortar concrete, restoration and preservation of reinforced concrete	sq.m	250.00		
1.2103	Steel reinforcement for buildings	Ton	2.00		
	Sub-Total 1.2100				
	Sub-Total 1.2000				
1.3000	Waterproofing, thermal insulation, and water quality control				
1.3001	Internal lining for reservoirs	sq.m	600		
1.3002	Waterproofing asphalt coat	sq.m	250		
1.3003	External lining and coating for roof slabs	sq.m	133		
1.3004	Waterproofing plastic membrane	sq.m	250		
1.3005	Geotextile sheet, with a topcrete layer (thickness 10cm)	sq.m	250		
	Sub-Total 1.3000				
1.4000	Metal works				
1.4001	Supply and installation of exterior steel doors including painting.	sq.m	10		
1.4002	Epoxy paint for metal, stainless steel, steel pipes and others	sq.m	75		
	Sub-Total 1.4000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL A: CIVIL WORKS

RAS EL AIN SPRING CATCHMENT STRUCTURE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
1.5000	Reservoir Hydraulic Accessories				
1.5100	Piping and accessories				
1.5101	Hydraulic accessories (bends, tees, pipes, flanges, gaskets, joints, bolts, nuts, supports, well head piece...)	LS	1		
	Sub-Total 1.5100				-
	Sub-Total 1.5000				
	Total RAS EL AIN SPRING CATCHMENT STRUCTURE				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY OF BILL A: CIVIL WORKS

Nb	DESCRIPTION	TOTAL AMOUNT USD
1	MRAIJAT PUMPING STATION	
2	QABB ELIAS RESERVOIRS (CAPACITY 2X400 m³)	
3	MAKSE RESERVOIR (CAPACITY 500 m³)	
4	REHABILITATION OF QABB ELIAS PUMPING STATION AND FRENCH RESERVOIR	
5	OUADI EL DELEM SPRING CATCHMENT STRUCTURE	
6	RAS EL AIN SPRING CATCHMENT STRUCTURE	
	TOTAL	

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR EL MRAYJAT WELL PUMPING STATION

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.0000	Mechanical, Electrical and Control Equipment				
2.0100	Pumping system				
2.0101	Submersible Motopumpset Q=11.6 l/s, Hmt=467 m	nb	1		
2.0102	Hydraulic accessories (base frame, shock absorbers, supports, bolts, nuts, etc...)	LS	1		
Sub -Total 2.0100					
2.0200	Piping and accessories				
2.0201	Rising column pipe DN100	lin.m	450		
2.0202	Piezometric tube OD40	lin.m	900		
2.0203	Anti-Shock Air release valve DN60, PN16with isolating valve	nb	1		
2.0204	Sampling ball valve DN13, PN16	nb	1		
2.0205	Dismantling Joints DN80 PN16	nb	1		
2.0206	Dismantling Joints DN100 PN16	nb	2		
2.0207	Anti-Slam Spring Loaded Check Valve DN100 PN16	nb	1		
2.0208	Globe Valve DN100 PN16	nb	1		
2.0209	Gate Valve DN80 PN16	nb	1		
2.0210	Butterfly Valve DN100 PN16	nb	1		
2.0211	Surge suppression equipment (Anti-water hammer system PN 16)	LS	1		
2.0212	Hydraulic accessories (bends, tees, pipes, flanges, gaskets, joints, bolts, nuts, supports, insert well head piece...)	LS	1		
Sub -Total 2.0200					
2.0300	Gas chlorination system				
2.0301	Chlorinator complete system with a capacity of 0.21kg/hr and a back pressure of 6 bars (including pump, ejector, preregulators, auto-transfer switch, Cl2 flowmeter, Gas masks...)	nb	1		
2.0302	Chlorine cylinders	nb	3		
2.0303	Chlorine leakage detection system	nb	1		
2.0304	Ventilators	nb	2		
2.0305	Accessories (pipes, bends, tees, joints, bolts, nuts, supports, flow switch, vacuum switch...)	LS	1		
Sub -Total 2.0300					

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR EL MRAYJAT WELL PUMPING STATION

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.0400	Electrical system				
2.0401	EDL transformer 160 KVA	nb	1		
2.0402	Subscription to EDL for 160 KVA	nb	1		
2.0403	Standby Generator 250 KVA	nb	1		
2.0404	Main ATS panel 375 A	nb	1		
2.0405	Soft Starter control panel 101 kW	nb	1		
2.0406	Low voltage cable 1x(3x120+70) mm ²	lin.m	50		
2.0407	Low voltage cable 1x(3x150+70) mm ²	lin.m	930		
2.0408	Low voltage cable 1x(3x185+95) mm ²	lin.m	25		
2.0409	Electric Actuator for Globe Valve DN 100 PN 16	nb	1		
2.0410	Electric Actuator for Butterfly Valve DN 100 PN 16	nb	1		
2.0411	Electric Actuator for Gate Valve DN 80 PN 16	nb	1		
2.0412	UPS system	nb	2		
2.0413	Grounding system - Lightning & Surge Protections	LS	1		
2.0414	Electric accessories (cables, Lugs, clamps, connectors, conduits, cable trays, insulation, junction boxes ...)	LS	1		
	Sub -Total 2.0400				
2.0500	Instrumentation and Control				
2.0501	450 m deep well piezoresistive Level measurement	nb	1		
2.0502	Piezoresistive level measurement at reservoir	nb	1		
2.0503	Piezoresistive pressure measurement	nb	1		
2.0504	450 m water level protection system with 3 electrodes and relay	nb	1		
2.0505	Temperature measurement for well pump (1 per motor)	set	1		
2.0506	Telemetry cable	lin.m	1135		
2.0507	Flow measurement DN 100 PN16	nb	1		
2.0508	Flow switch DN13 PN 16	nb	1		
2.0509	Glycerine filled manometer Ø 100 with 3 way valve caliber 16	nb	2		
2.0510	HMI panel	nb	1		
2.0511	Control accessories (PLC, RTU, programming, transmissioncables, etc...)	L.S	1		
	Sub -Total 2.0500				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR EL MRAYJAT WELL PUMPING STATION

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.0600	Domestic Plumbing and drainage system	LS	1		
	Sub -Total 2.0600				
2.0700	Fire extinguishers	LS	1		
	Sub -Total 2.0700				
2.0800	Electrical installation for buildings	LS	1		
	Sub -Total 2.0800				
	Total EL MRAYJAT well pumping station, Equipment				

BILL B - ELECTRO-MECHANICAL WORKS

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.1000	Mechanical, Electrical and Control Installation etc.				
2.1010	Pumping system	LS	1		
2.1101	Piping and accessories	LS	1		
2.1102	Surge Suppression Equipment	LS	1		
2.1103	Gas chlorination system	LS	1		
2.1104	Electrical system	LS	1		
2.1105	Instrumentation and Control	LS	1		
2.1106	Domestic Plumbing and drainage system	LS	1		
2.1107	Fire extinguishers	LS	1		
2.1108	Electrical installation for buildings	LS	1		
2.1109	Training, testing and commissioning	LS	1		
2.11010	Water Analysis	LS	1		
	Total EL MRAYJAT well pumping station Works				

	Total OF EL MRAYJAT ELECTRO-MECHANICAL EQUIPMENT AND WORKS				
--	--	--	--	--	--

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR QABB ELIAS PUMPING STATION

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.0000	Mechanical, Electrical and Control Equipment				
2.0100	Pumping system				
2.0101	Single Channel Submersible Motopumpset Q=30 l/s, Hmt=35 m	nb	3		
2.0102	Hydraulic accessories (Guide pipe, Discharge connection, brackets, adapters, upper guide bracket, etc...)	LS	1		
	Sub -Total 2.0100				
2.0200	Piping and accessories				
2.0201	Double Air release valve DN60, PN16with isolating valve	nb	3		
2.0202	Sampling ball valve DN13, PN16	nb	3		
2.0203	Dismantling Joints DN125 PN16	nb	1		
2.0204	Dismantling Joints DN150 PN16	nb	3		
2.0205	Dismantling Joints DN250 PN16	nb	1		
2.0206	Dismantling Joints DN300 PN16	nb	1		
2.0207	Check Valve DN150 PN16	nb	3		
2.0208	Gate Valve DN250 PN16	nb	1		
2.0209	Gate Valve DN150 PN16	nb	3		
2.0210	Gate Valve DN125 PN16	nb	1		
2.0211	Rubber Spherical Joint DN 150 PN 16	nb	3		
2.0212	Globe Valve DN300 PN16	nb	1		
2.0213	Float Valve DN300 PN16	nb	1		
2.0214	Electrical Overhead crane Capacity 1000 kg	nb	2		
2.0215	Manual Overhead crane Capacity 250 kg	nb	1		
2.0216	Hydraulic accessories (bends, tees, pipes, flanges, gaskets, joints, bolts, nuts, supports...)	LS	1		
	Sub -Total 2.0200				
2.0300	Gas chlorination system				
2.0301	Chlorinator complete system with a capacity of 1.08 kg/hr and a back pressure of 4 bars (including pump, ejector, preregulators, auto-transfer switch, Cl2 flowmeter, Gas masks...)	nb	1		
2.0302	Chlorine cylinders	nb	10		
2.0303	Chlorine leakage detection system	nb	1		
2.0304	Ventilators	nb	2		
2.0305	Accessories (pipes, bends, tees, joints, bolts, nuts, supports, flow switch, vacuum switch...)	LS	1		
	Sub -Total 2.0300				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR QABB ELIAS PUMPING STATION

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.0400	Electrical system				
2.0401	Electrical Transformer 160 KVA	nb	1		
2.0402	Subscription to EDL	LS	1		
2.0403	Standby Generator 110 KVA	nb	1		
2.0404	Main ATS panel 240 A	nb	1		
2.0405	Variable Speed Starter control panel 30 kW	nb	3		
2.0406	Low voltage cable 1x(3x25+16) mm ²	lin.m	60		
2.0407	Low voltage cable 1x(3x95+50) mm ²	lin.m	25		
2.0408	Low voltage cable 1x(3x240+120) mm ²	lin.m	40		
2.0409	UPS system	nb	1		
2.0410	Grounding, Lightning and surge protection system	LS	1		
2.0411	Electric accessories (cables, Lugs, clamps, connectors, conduits, cable trays, insulation, junction boxes ...)	LS	1		
	Sub -Total 2.0400				
2.0500	Instrumentation and Control				
2.0501	Piezoresistive level measurement for reservoir	nb	2		
2.0502	Piezoresistive pressure measurement	nb	4		
2.0503	Temperature measurement for submersible pump (3 per motor)	set	3		
2.0504	Flow measurement DN 300 PN 16	nb	1		
2.0505	Flow measurement DN 250 PN 16	nb	1		
2.0506	Flow switch DN13 PN 16	nb	1		
2.0507	Oil Leakage Detection System	nb	3		
2.0508	Electrical float switch	set	4		
2.0509	Glycerine filled manometer Ø 100 with 3 way valve caliber 16	nb	4		
2.0510	HMI panel	nb	1		
2.0511	Control accessories (PLC, RTU, programming, transmission cables, etc...)	L.S	1		
	Total QABB ELIAS pumping station, Equipment				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR QABB ELIAS PUMPING STATION

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
---------	-------------	------	----------	---------------------	------------------------

BILL B - ELECTRO-MECHANICAL WORKS

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.1000	Mechanical, Electrical and Control Installation etc.				
2.1101	Pumping system	LS	1		
2.1102	Piping and accessories	LS	1		
2.1103	Electrical system	LS	1		
2.1104	Lifting and Handling equipment	LS	1		
2.1105	Instrumentation and Control system	LS	1		
2.1106	Training, testing and commissioning	LS	1		
	Total QABB ELIAS pumping station Works				

	Total OF QABB ELIAS ELECTRO-MECHANICAL EQUIPMENT AND WORKS				
--	---	--	--	--	--

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN QUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL B: ELECTROMECHANICAL WORKS

ELECTROMECHANICAL EQUIPMENT AND WORKS FOR QABB ELIAS PHOTOVOLTAIC SYSTEM

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
2.0001	PV Modules Suntech STP 370	watt	96200		
2.0002	DC Cables Wochn green energy 4mm2	lin.m	160		
2.0003	MC4 connectors	nb	40		
2.0004	DC installation	watt	96200		
2.0005	PV mounting Structure ZEENNI STEEL	watt	96200		
2.0006	Mechanical installation	watt	96200		
2.0007	Earthing system SSS-Elmeko	nb	1		
2.0008	Pumping Inverter LS - H 100- 37kw	nb	2		
2.0009	DC combiner with all relative accessories	nb	2		
2.0010	serial Fuses with fuse holder 20 A	nb	20		
2.0011	protection diodes 20 A reverse current >1500v	nb	10		
2.0012	DC switch double pole 160A	nb	1		
2.0013	Surge arristor	nb	2		
2.0014	Sandwish panel mechanical room at solar tent location	nb	1		
2.0015	AC-LV Cables (2 cables 3x25 cupper wire) Cable du Liban	nb	420		
2.0016	AC-LV installation	nb	1		
2.0017	Distribution boards including circuit breakers, chang over switch,protection rerays energy meter , fuese, all relative accessories PAC (ABB)	nb	1		
2.0018	Cable trays, conduits, cable ties, lugs, glands, labelling and marking etc.	nb	1		
2.0019	Civil and Structure studies and verifications such as civil designs verification, PV structure design verification, roof tolerance	nb	1		
2.0020	verification, parapets tolerance verification, soil test etc.	nb	1		
2.0021	Structure tests:	nb	1		
	1) Mechanical properties (elongation, yield and tensile).				
	2) Galvanization thickness and type.				
	3) Anodization thickness and type.				
	4) Chemical Composition test				
2.0022	PV modules and inverters tests	nb	1		
2.0023	3 rd party testing and commissioning (if applicable)	nb	1		
2.0024	Trenching and backfilling	lin.m	200		
2.0025	Mounting structure foundation	nb	35		
2.0026	Engineering, design and management	Watt	96200		
2.0027	License and approvals	nb	1		
2.0028	3years O&M and cleaning	nb	6		
2.0029	Communication hardware (routers, switches, cables, etc.)	nb	1		
	Total OF QABB ELIAS QABB ELIAS PHOTOVOLTAIC SYSTEM				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY OF BILL B: ELECTRO-MECHANICAL WORKS

Nb	DESCRIPTION	TOTAL AMOUNT USD
1	ELECTROMECHANICAL EQUIPMENT AND WORKS FOR EL MRAYJAT WELL PUMPING STATION	
2	ELECTROMECHANICAL EQUIPMENT AND WORKS FOR QABB ELIAS PUMPING STATION	
3	ELECTROMECHANICAL EQUIPMENT AND WORKS FOR QABB ELIAS PHOTOVOLTAIC SYSTEM	
	TOTAL	

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

OUADI EL DELEM GRAVITY LINE TO QABB ELIAS

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	3.264		
3.0002	Trial pit not exceeding 3m depth	nb	5.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	15.00		
3.0004	As-built drawings	km.	3.264		
	Sub-Total	3.0000			
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1101	Supply of 80 mm pipes	lin.m	4,529.00		
	Sub-Total	3.1100			
3.1200	Trench excavation				
3.1201	Trench excavation for 80 mm DI pipes	lin.m	1,999.00		
3.1202	Trench excavation for 2 pipes: 80 mm DI and 80 mm DI pipes	lin.m	1,265.00		
	Sub-Total	3.1200			
3.1300	Sand bedding and surrounds				
3.1301	Sand bedding for 80 mm DI pipes	lin.m	1,999.00		
3.1302	Sand bedding for 2 pipes: 80 mm DI and 80 mm DI pipes	lin.m	1,265.00		
	Sub-Total	3.1300			
3.1400	Laying of ductile iron pipes				
3.1401	Laying of 80 mm pipes	lin.m	4,529.00		
	Sub-Total	3.1400			
3.1500	Backfilling of trenches including compaction and testing				
3.1501	Backfilling of trenches for 80 mm DI pipes	lin.m	1,999.00		
3.1502	Backfilling of trenches for 2 pipes: 80 mm DI and 80 mm DI pipes	lin.m	1,265.00		
	Sub-Total	3.1500			
	Sub-Total	3.1000			
3.2000	Accessories				
3.2100	Supply and installation of air release valves				
3.2101	Anti-shock double air release valve including GV PN16, DN 60 mm	nb	4.00		
	Sub-Total	3.2100			
3.2200	Supply and installation of pressure regulating valves				
3.2201	Pressure regulating valve PN16, for pipe DN 80 mm DI	nb	1.00		
	Sub-Total	3.2200			

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

OUADI EL DELEM GRAVITY LINE TO QABB ELIAS

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.2300	Supply and installation of pressure sustaining valves, pressure regulating valves and watermeters				
3.2301	Pressure sustaining valve + Pressure regulating valve + watermeter PN16, for pipe DN 80 mm DI	nb	1.00		
	Sub-Total 3.2300				
3.2400	Supply and installation of watermeters				
3.2401	Watermeter PN16, for pipe DN 80 mm DI	nb	1.00		
	Sub-Total 3.2400				
3.2500	Supply and installation of washouts				
3.2501	Washout PN16, DN 80 mm	nb	4.00		
	Sub-Total 3.2500				
3.2600	Supply and installation of connections to existing structures				
3.2601	Connection to existing reservoir	nb	1.00		
3.2602	Connection to existing catchment structure	nb	1.00		
	Sub-Total 3.2600				
	Sub-Total 3.2000				
3.3000	Valve chambers and Surface box units				
3.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.3101	Valve chamber internal size 125 x 100 cm x cm	nb	4.00		
3.3102	Valve chamber internal size 150 x 150 cm x cm	nb	4.00		
	Sub-Total 3.3100				
3.3200	Valve chamber cover				
3.3201	Valve chamber cover Grade A	nb	8.00		
	Sub-Total 3.3200				
3.3300	Surface box units for washouts				
3.3301	Supply and installation of surface box unit	nb	4.00		
	Sub-Total 3.3300				
	Sub-Total 3.3000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

OUADI EL DELEM GRAVITY LINE TO QABB ELIAS

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.4000	Concrete works				
3.4001	Mass concrete - Class C20 for blinding	cu.m	20.00		
3.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	20.00		
3.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels	cu.m	40.00		
	Sub-Total 3.4000				
3.5000	Testing and commissioning of potable water pipes				
3.5001	Testing and commissioning of 80 mm DI pipes	lin.m	4,529.00		
	Sub-Total 3.4000				
3.6000	Road Reinstatement				
3.6100	Cutting				
3.6101	Cutting of paved roads for water pipes	lin.m	180.00		
	Sub-Total 3.5100				
3.6200	Reinstatement				
3.6201	Reinstatement in one layer of paved roads including recutting works	sq.m	155.00		
	Sub-Total 3.6200				
	Sub-Total 3.6000				
	Total OUADI EL DELEM GRAVITY LINE TO QABB ELIAS				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

OUADI EL DELEM GRAVITY LINE TO EL MRAIJAT

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	1.393		
3.0002	Trial pit not exceeding 3m depth	nb	5.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	15.00		
3.0004	As-built drawings	km.	1.393		
	Sub-Total	3.0000			
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1101	Supply of 80 mm pipes	lin.m	1,393.00		
	Sub-Total	3.1100			
3.1200	Trench excavation				
3.1201	Trench excavation for 80 mm DI pipes	lin.m	1,393.00		
	Sub-Total	3.1200			
3.1300	Sand bedding and surrounds				
3.1301	Sand bedding for 80 mm DI pipes	lin.m	843.00		
	Sub-Total	3.1300			
3.1400	Laying of ductile iron pipes				
3.1401	Laying of 80 mm pipes	lin.m	1,393.00		
	Sub-Total	3.1400			
3.1500	Backfilling of trenches including compaction and testing				
3.1501	Backfilling of trenches for 80 mm DI pipes	lin.m	1,393.00		
	Sub-Total	3.1500			
3.1600	Extra over for manual works including: trench excavation, sand bedding and surround, laying of pipes, backfilling of trenches and execution of reinforced concrete surround, etc.				
3.1601	Extra over for 80 mm DI pipes with reinforced concrete surround	lin.m	550.00		
	Sub-Total	5.1900			
	Sub-Total	3.1000			

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

OUADI EL DELEM GRAVITY LINE TO EL MRAIJAT

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.2000	Accessories				
3.2100	Supply and installation of air release valves				
3.2101	Anti-shock double air release valve including GV PN16, DN 60 mm	nb	2.00		
	Sub-Total 3.2100				
3.2200	Supply and installation of pressure sustaining valves, pressure regulating valves and watermeters				
3.2201	Pressure sustaining valve + Pressure regulating valve + watermeter PN16, for pipe DN 80 mm DI	nb	1.00		
	Sub-Total 3.2200				
3.2300	Supply and installation of watermeters				
3.2301	Watermeter PN16, for pipe DN 80 mm DI	nb	1.00		
	Sub-Total 3.2300				
3.2400	Supply and installation of washouts				
3.2401	Washout PN16, DN 80 mm	nb	2.00		
3.2402	Washout PN25, DN 80 mm	nb	1.00		
	Sub-Total 3.2400				
3.2500	Supply and installation of connections to existing structures				
3.2501	Connection to existing reservoir	nb	1.00		
3.2502	Connection to existing catchment structure	nb	1.00		
3.2503	Connection to existing pipe	nb	2.00		
	Sub-Total 3.2500				
	Sub-Total 3.2000				
3.3000	Valve chambers and Surface box units				
3.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.3101	Valve chamber internal size 125 x 100 cm x cm	nb	2.00		
3.3102	Valve chamber internal size 150 x 150 cm x cm	nb	3.00		
	Sub-Total 3.3100				
3.3200	Valve chamber cover				
3.3201	Valve chamber cover Grade A	nb	5.00		
	Sub-Total 3.3200				
3.3300	Surface box units for washouts				
3.3301	Supply and installation of surface box unit	nb	3.00		
	Sub-Total 3.3300				
	Sub-Total 3.3000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

OUADI EL DELEM GRAVITY LINE TO EL MRAIJAT

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.4000	Concrete works				
3.4001	Mass concrete - Class C20 for blinding	cu.m	20.00		
3.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	20.00		
3.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels	cu.m	213.00		
	Sub-Total 3.4000				
3.5000	Testing and commissioning of potable water pipes				
3.5001	Testing and commissioning of 80 mm DI pipes	lin.m	1,393.00		
	Sub-Total 3.4000				
3.6000	Road Reinstatement				
3.6100	Cutting				
3.6101	Cutting of paved roads for water pipes	lin.m	354.00		
	Sub-Total 3.5100				
3.6200	Reinstatement				
3.6201	Reinstatement in one layer of paved roads including recutting works	sq.m	305.00		
	Sub-Total 3.6200				
	Sub-Total 3.6000				
	Total OUADI EL DELEM GRAVITY LINE TO EL MRAIJAT				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

RAS EL AIN GRAVITY LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	1.05		
3.0002	Trial pit not exceeding 3m depth	nb	6.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	16.00		
3.0004	As-built drawings	km.	1.05		
	Sub-Total	3.0000			
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1107	Supply of 300 mm pipes	lin.m	1,050.00		
	Sub-Total	3.1100			
3.1300	Trench excavation				
3.1307	Trench excavation for 300 mm DI pipes	lin.m	1,050.00		
	Sub-Total	3.1300			
3.1400	Sand bedding and surrounds				
3.1407	Sand bedding for 300 mm DI pipes	lin.m	910.00		
	Sub-Total	3.1400			
3.1500	Laying of ductile iron pipes				
3.1506	Laying of 300 mm pipes	lin.m	1,050.00		
	Sub-Total	3.1500			
3.1800	Backfilling of trenches on other roads including compaction and testing				
3.1807	Backfilling of trenches for 300 mm DI pipes	lin.m	1,050.00		
	Sub-Total	3.1800			
3.1900	Extra over for manual works including: trench excavation, sand bedding and surround, laying of pipes, backfilling of trenches and execution of reinforced concrete surround, etc.				
3.1901	Extra over for 300 mm DI pipes with reinforced concrete surround	lin.m	140.00		
	Sub-Total	3.1900			
	Sub-Total	3.1000			
3.2000	Accessories				
3.2200	Supply and installation of air release valves				
3.2207	Anti-shock double air release valve including GV PN16, DN 100 mm	nb	1.00		
	Sub-Total	3.2200			

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

RAS EL AIN GRAVITY LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.2300	Supply and installation of pressure sustaining valve + watermeter				
3.2301	Pressure sustaining valve + watermeter PN16, for pipe DN 300 mm DI	nb	1.00		
	Sub-Total 3.2300				
3.2400	Supply and installation of watermeters				
3.2401	Watermeter PN16, for pipe DN 300 mm DI	nb	1.00		
	Sub-Total 3.2400				
3.2500	Supply and installation of washouts				
3.2501	Washout PN16, DN 150 mm	nb	2.00		
	Sub-Total 3.2500				
3.2600	Supply and installation of connections to existing structures				
3.2601	Connection to existing reservoir	nb	1.00		
3.2602	Connection to existing spring catchment works	nb	1.00		
	Sub-Total 3.2600				
	Sub-Total 3.2000				
3.3000	Valve chambers and Surface box units				
3.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.3104	Valve chamber internal size 150 x 125 cm x cm	nb	1.00		
3.3105	Valve chamber internal size 150 x 150 cm x cm	nb	2.00		
	Sub-Total 3.3100				
3.3200	Valve chamber cover				
3.3201	Valve chamber cover Grade A	nb	3.00		
	Sub-Total 3.3200				
3.3300	Surface box units for washouts				
3.3301	Supply and installation of surface box unit	nb	2.00		
	Sub-Total 3.3300				
	Sub-Total 3.3000				
3.4000	Concrete works				
3.4001	Mass concrete - Class C20 for blinding	cu.m	20.00		
3.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	20.00		
3.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels and reinforced concrete surround	cu.m	130.00		
	Sub-Total 3.4000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

RAS EL AIN GRAVITY LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.6000	Testing and commissioning of potable water pipes				
3.6015	Testing and commissioning of 300 mm DI pipes	lin.m	1,050.00		
	Sub-Total 3.6000				
	Total RAS EL AIN GRAVITY LINE				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

QABB ELIAS LIFT LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	0.066		
3.0002	Trial pit not exceeding 3m depth	nb	1.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	5.00		
3.0004	As-built drawings	km.	0.066		
	Sub-Total	3.0000			
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1101	Supply of 250 mm pipes	lin.m	66.00		
	Sub-Total	3.1100			
3.1200	Supply of HDPE pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1210	Supply of PE80 - PN10 HDPE pipes				
3.1211	Supply of 63 mm pipes for telemetry ducts (tel.)	lin.m	66.00		
3.1212	Supply of 90 mm pipes for cables	lin.m	66.00		
	Sub-Total	3.1200			
3.1300	Trench excavation				
3.1301	Trench excavation for 3 pipes: 250 mm DI, 63 mm (tel.), and 90 mm HDPE pipes	lin.m	66.00		
	Sub-Total	3.1300			
3.1400	Sand bedding and surrounds				
3.1401	Sand bedding for 3 pipes: 250 mm DI, 63 mm (tel.), and 90 mm HDPE pipes	lin.m	66.00		
	Sub-Total	3.1400			
3.1500	Laying of ductile iron pipes				
3.1501	Laying of 250 mm pipes	lin.m	66.00		
	Sub-Total	3.1500			
3.1600	Laying of HDPE pipes				
3.1610	Laying of PE80 - PN10 HDPE pipes				
3.1611	Laying of 63 mm pipes for telemetry ducts (tel.)	lin.m	66.00		
3.1612	Laying of 90 mm pipes for cables	lin.m	66.00		
	Sub-Total	3.1600			
3.1700	Backfilling of trenches including compaction and testing				
3.1701	Backfilling of trenches for 3 pipes: 250 mm DI, 63 mm (tel.), and 90 mm HDPE pipes	lin.m	66.00		
	Sub-Total	3.1700			
	Sub-Total	3.1000			

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

QABB ELIAS LIFT LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.2000	Valve chambers and Surface box units				
3.2100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.2101	Draw-pit for telemetry ducts size 60 x 60 cm x cm	nb	4.00		
	Sub-Total 3.2100				
3.2200	Valve chamber cover				
3.2201	Valve chamber cover Grade A	nb	4.00		
	Sub-Total 3.2200				
	Sub-Total 3.2000				
3.3000	Concrete works				
3.3001	Mass concrete - Class C20 for blinding	cu.m	2.00		
3.3002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	2.00		
3.3003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels	cu.m	2.00		
	Sub-Total 3.3000				
3.4000	Testing and commissioning of potable water pipes				
3.4011	Testing and commissioning of 250 mm DI pipes	lin.m	66.00		
	Sub-Total 3.4000				
3.5000	Road Reinstatement				
3.5100	Cutting				
3.5101	Cutting, breaking-out and removal of concrete pavement or stair cases for water pipes	sq.m	66.00		
	Sub-Total 3.5100				
3.5200	Reinstatement				
3.5201	Reinstatement of concrete pavement or stair cases for water pipes, including base, sub-base courses and concrete pavement	sq.m	125.00		
	Sub-Total 3.5200				
	Sub-Total 3.5000				
	Total QABB ELIAS LIFT LINE				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

MRAIJAT LIFT LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	1.080		
3.0002	Trial pit not exceeding 3m depth	nb	5.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	15.00		
3.0004	As-built drawings	km.	1.080		
	Sub-Total	3.0000			
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1101	Supply of 125 mm pipes	lin.m	1,080.00		
	Sub-Total	3.1100			
3.1200	Supply of HDPE pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1210	Supply of PE80 - PN10 HDPE pipes				
3.1211	Supply of 63 mm pipes for telemetry ducts (tel.)	lin.m	1,080.00		
	Sub-Total	3.1200			
3.1300	Trench excavation				
3.1301	Trench excavation for 2 pipes: 125 mm DI and 63 mm (tel.) pipes	lin.m	960.00		
	Sub-Total	3.1300			
3.1400	Sand bedding and surrounds				
3.1401	Sand bedding for 2 pipes: 125 mm DI and 63 mm (tel.) pipes	lin.m	830.00		
	Sub-Total	3.1400			
3.1500	Laying of ductile iron pipes				
3.1501	Laying of 125 mm pipes	lin.m	960.00		
	Sub-Total	3.1500			
3.1600	Laying of HDPE pipes				
3.1610	Laying of PE80 - PN10 HDPE pipes				
3.1611	Laying of 63 mm pipes for telemetry ducts (tel.)	lin.m	960.00		
	Sub-Total	3.1600			
3.1700	Backfilling of trenches including compaction and testing				
3.1701	Backfilling of trenches for 2 pipes: 125 mm DI and 63 mm (tel.) pipes	lin.m	960.00		
	Sub-Total	3.1700			

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

MRAIJAT LIFT LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.1800	Supply and installation of culvert crossing				
3.1801	Supply and installation of culvert crossing for 125 mm DI and 63 mm HDPE pipes	nb	1.00		
	Sub-Total 3.1800				
	Sub-Total 3.1000				
3.2000	Accessories				
3.2100	Supply and installation of air release valves				
3.2101	Anti-shock double air release valve including GV PN16, DN 60 mm	nb	1.00		
	Sub-Total 3.2100				
3.2200	Supply and installation of watermeters				
3.2201	Watermeter PN16, for pipe DN 125 mm DI	nb	1.00		
	Sub-Total 3.2200				
3.2300	Supply and installation of washouts				
3.2301	Washout PN16, DN 80 mm	nb	2.00		
	Sub-Total 3.2300				
3.2400	Supply and installation of connections to existing structures				
3.2401	Connection to existing reservoir	nb	1.00		
	Sub-Total 3.2400				
	Sub-Total 3.2000				
3.3000	Valve chambers and Surface box units				
3.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.3101	Draw-pit for telemetry ducts size 60 x 60 cm x cm	nb	23.00		
3.3102	Valve chamber internal size 125 x 100 cm x cm	nb	1.00		
3.3103	Valve chamber internal size 150 x 150 cm x cm	nb	2.00		
	Sub-Total 3.3100				
3.3200	Valve chamber cover				
3.3201	Valve chamber cover Grade A	nb	26.00		
	Sub-Total 3.3200				
3.3300	Surface box units for washouts				
3.3301	Supply and installation of surface box unit	nb	2.00		
	Sub-Total 3.3300				
	Sub-Total 3.3000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

MRAIJAT LIFT LINE

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.4000	Concrete works				
3.4001	Mass concrete - Class C20 for blinding	cu.m	10.00		
3.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	10.00		
3.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels and reinforced concrete surround	cu.m	87.00		
	Sub-Total 3.4000				
3.5000	Testing and commissioning of potable water pipes				
3.5011	Testing and commissioning of 125 mm DI pipes	lin.m	1,080.00		
	Sub-Total 3.5000				
3.6000	Road Reinstatement				
3.6100	Cutting				
3.6101	Cutting of paved roads for water pipes	lin.m	256.00		
	Sub-Total 3.6100				
3.6200	Reinstatement				
3.6201	Reinstatement in one layer of paved roads including recutting works	sq.m	273.00		
	Sub-Total 3.6200				
	Sub-Total 3.6000				
	Total MRAIJAT LIFT LINE				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

COMPLETION OF THE DRINKING WATER NETWORK IN JLALA AND SHTAURA

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	0.700		
3.0002	Trial pit not exceeding 3m depth	nb	5.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	4.00		
3.0004	As-built drawings	km.	0.700		
	Sub-Total 3.0000				
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1101	Supply of 250 mm pipes	lin.m	700.00		
	Sub-Total 3.1100				
3.1300	Trench excavation				
3.1301	Trench excavation for pipes 250 mm	lin.m	700.00		
	Sub-Total 3.1300				
3.1400	Sand bedding and surrounds				
3.1401	Sand bedding for pipes 250 mm	lin.m	700.00		
	Sub-Total 3.1400				
3.1500	Laying of ductile iron pipes				
3.1501	Laying of 250 mm pipes	lin.m	700.00		
	Sub-Total 3.1500				
3.1700	Backfilling of trenches including compaction and testing				
3.1701	Backfilling of trenches for pipes 250 mm	lin.m	700.00		
	Sub-Total 3.1700				
3.1800	Supply and installation of culvert crossing				
3.1801	Supply and installation of culvert crossing for 250 mm pipes	nb	2.00		
	Sub-Total 3.1800				
	Sub-Total 3.1000				
3.2000	Accessories				
3.2100	Supply and installation of air release valves				
3.2101	Anti-shock double air release valve including GV PN16, DN 60 mm	nb	2.00		
	Sub-Total 3.2100				
3.2200	Supply and installation of watermeters				
3.2201	Watermeter PN16, for pipe DN 250 mm	nb	2.00		
	Sub-Total 3.2200				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

COMPLETION OF THE DRINKING WATER NETWORK IN JLALA AND SHTAURA

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.2300	Supply and installation of washouts				
3.2301	Washout PN16, DN 80 mm	nb	2.00		
	Sub-Total 3.2300				
3.2400	Supply and installation of connections to existing pipes				
3.2401	Connection to existing pipes 250 mm with all the necessary fittings	nb	2.00		
	Sub-Total 3.2400				
	Sub-Total 3.2000				
3.3000	Valve chambers and Surface box units				
3.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.3102	Valve chamber internal size 125 x 100 cm x cm	nb	4.00		
3.3103	Valve chamber internal size 150 x 150 cm x cm	nb	5.00		
	Sub-Total 3.3100				
3.3200	Valve chamber cover				
3.3201	Valve chamber cover Grade A	nb	9.00		
	Sub-Total 3.3200				
3.3300	Surface box units				
3.3301	Supply and installation of surface box unit	nb	7.00		
	Sub-Total 3.3300				
	Sub-Total 3.3000				
3.4000	Concrete works				
3.4001	Mass concrete - Class C20 for blinding	cu.m	8.00		
3.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	12.00		
3.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels and reinforced concrete surround	cu.m	8.00		
	Sub-Total 3.4000				
3.5000	Testing and commissioning of potable water pipes				
3.5011	Testing and commissioning of 250 mm DI pipes	lin.m	700.00		
	Sub-Total 3.5000				
3.6000	Road Reinstatement				
3.6100	Cutting				
3.6101	Cutting of paved roads for water pipes	lin.m	700.00		
	Sub-Total 3.6100				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

COMPLETION OF THE DRINKING WATER NETWORK IN JLALA AND SHTAURA

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.6200	Reinstatement				
3.6201	Reinstatement in one layer of paved roads including recutting works	sq.m	1,000.00		
	Sub-Total 3.6200				
	Sub-Total 3.6000				
	Total COMPLETION OF THE DRINKING WATER NETWORK IN JLALA AND SHTAURA				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

CONSTRUCTION OF HOUSE CONNECTIONS IN UPPER SAADNAYEL, JDITA AND MAKSEH

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0002	Trial pit not exceeding 2m depth	nb	5.00		
3.0003	Trial trench not exceeding 1.5m depth	lin.m	15.00		
	Sub-Total 3.0000				
3.1000	Pipeworks				
3.1100	Construction of house connection				
3.1101	Construction of house connection with all the necessary fittings including asphalt-cutting excavation	lin.m	1,500.00		
	Sub-Total 3.1100				
	Total CONSTRUCTION OF HOUSE CONNECTIONS IN UPPER SAADNAYEL, JDITA AND MAKSEH				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY OF BILL C: TRANSMISSION LINES

Nb	DESCRIPTION	TOTAL AMOUNT USD
1	OUADI EL DELEM GRAVITY LINE TO QABB ELIAS	
2	OUADI EL DELEM GRAVITY LINE TO EL MRAIJAT	
3	RAS EL AIN GRAVITY LINE	
4	QABB ELIAS LIFT LINE	
5	MRAIJAT LIFT LINE	
6	COMPLETION OF THE DRINKING WATER NETWORK IN JLALA AND SHTAURA	
7	CONSTRUCTION OF HOUSE CONNECTIONS IN UPPER SAADNAYEL, JDITA AND MAKSEH	
	TOTAL	

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL D: BOREHOLES

EL MRAIJAT BOREHOLE

ITEM Nb.	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
4.0000	Site Preparation				
4.0100	Site preparation and set up borehole drilling unit and later dismantle	LS	1		
	Sub-Total 4.0000				
4.1000	Drilling by rotary				
4.1100	Drilling at nominal diameter 22"	lin.m	20		
4.1200	Drilling at nominal diameter 17.5"	lin.m	180		
4.1300	Drilling at nominal diameter 14 ^{3/4} "	lin.m	150		
4.1400	Drilling at nominal diameter 12 ^{1/4} "	lin.m	150		
	Sub-Total 4.1000				
4.2000	Well Construction				
4.2100	Supply, transport and install 18" black steel casing 5mm thick	lin.m	20		
4.2200	Supply, transport and install 15.5" black steel casing 5mm thick	lin.m	200		
4.2300	Supply, transport and install 12.5" carbon steel casing 6mm thick	lin.m	350		
4.2400	Supply, transport and install 10" carbon steel casing 6mm thick	lin.m	400		
4.2500	Supply, transport and install 10" carbon steel bridge slotted screens 6mm thick	lin.m	100		
	Sub-Total 4.2000				
4.3000	Grouting				
4.3100	Supply and transport cement	kg	2750		
4.3200	Pump cement in annular space	lin.m	20		
	Sub-Total 4.3000				
4.4000	Well Development				
4.4100	Supply, install and remove test pumping unit (11.6 l/s, depth 480m) and all associated equipment including discharge pipeline	nb	1		
4.4200	Pumping and surging at different rates	hr.	16		
4.4300	Supervise development test	LS	1		
	Sub-Total 4.4000				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND MRAIJAT
VOLUME 5 -PART B- BILL OF QUANTITIES

BILL D: BOREHOLES

EL MRAIJAT BOREHOLE

ITEM Nb.	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
4.5000	Well Testing				
4.5100	Step drawdown test	hr.	16		
4.5200	Water level recovery measurements	hr.	16		
4.5300	Constant rate test	hr.	72		
4.5400	Water level recovery measurements	hr.	24		
	Sub-Total 4.5000				
4.6000	Water Analysis				
4.6100	Collection and delivery of water samples to an approved laboratory	nb	6		
4.6200	Physico-chemical analysis	nb	3		
4.6300	Bacteriological analysis	nb	3		
	Sub-Total 4.6000				
4.7000	Reports				
4.7100	Detailed daily reports	LS	1		
4.7200	Final well report	nb	1		
	Sub-Total 4.7000				
	TOTAL EI MRAIJAT BOREHOLE				

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY OF BILL D: BOREHOLES

Nb	DESCRIPTION	TOTAL AMOUNT USD
1	EL MRAIJAT BOREHOLE	
	TOTAL	

FIRST PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY

Nb	DESCRIPTION	TOTAL AMOUNT USD
1	BILL A: CIVIL WORKS	
2	BILL B: ELECTROMECHANICAL WORKS	
3	BILL C: TRANSMISSION LINES	
4	BILL D: BOREHOLES	
	TOTAL	

SECOND PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

COMPLETION OF THE DRINKING WATER NETWORK IN TAALABAYA

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.0000	General				
3.0001	Site Topographic Survey	km.	2.700		
3.0002	Trial pit not exceeding 3m depth	nb	20.00		
3.0003	Trial trench not exceeding 3m depth	lin.m	16.00		
3.0004	As-built drawings	km.	2.700		
	Sub-Total 3.0000				
3.1000	Pipeworks				
3.1100	Supply of ductile iron K9 pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1101	Supply of 250 mm pipes	lin.m	300.00		
	Sub-Total 3.1100				
3.1200	Supply of HDPE pipes including all necessary fittings (bends, tees, reducers, flanges, etc...)				
3.1210	Supply of PE80 - PN10 HDPE pipes				
3.1211	Supply of 63 mm pipes	lin.m	1,200.00		
3.1212	Supply of 50 mm pipes	lin.m	1,200.00		
	Sub-Total 3.1200				
3.1300	Trench excavation				
3.1301	Trench excavation for pipes 250 mm	lin.m	300.00		
3.1302	Trench excavation for pipes 63 mm	lin.m	1,200.00		
3.1303	Trench excavation for pipes 50 mm	lin.m	1,200.00		
	Sub-Total 3.1300				
3.1400	Sand bedding and surrounds				
3.1401	Sand bedding for pipes 250 mm	lin.m	300.00		
3.1402	Sand bedding for pipes 63 mm	lin.m	1,200.00		
3.1403	Sand bedding for pipes 50 mm	lin.m	1,200.00		
	Sub-Total 3.1400				
3.1500	Laying of ductile iron pipes				
3.1501	Laying of 250 mm pipes	lin.m	300.00		
	Sub-Total 3.1500				
3.1600	Laying of HDPE pipes				
3.1610	Laying of PE80 - PN10 HDPE pipes				
3.1611	Laying of 63 mm pipes	lin.m	1,200.00		
3.1612	Laying of 50 mm pipes	lin.m	1,200.00		
	Sub-Total 3.1600				
3.1700	Backfilling of trenches including compaction and testing				
3.1701	Backfilling of trenches for pipes 250 mm	lin.m	300.00		
3.1702	Backfilling of trenches for pipes 63 mm	lin.m	1,200.00		
3.1703	Backfilling of trenches for pipes 50 mm	lin.m	1,200.00		
	Sub-Total 3.1700				

SECOND PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

COMPLETION OF THE DRINKING WATER NETWORK IN TAALABAYA

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.1800	Supply and installation of culvert crossing				
3.1801	Supply and installation of culvert crossing for 250 mm pipes	nb	1.00		
3.1801	Supply and installation of culvert crossing for 63 mm pipes	nb	1.00		
	Sub-Total 3.1800				
	Sub-Total 3.1000				
3.2000	Accessories				
3.2100	Supply and installation of air release valves				
3.2101	Anti-shock double air release valve including GV PN16, DN 60 mm	nb	1.00		
	Sub-Total 3.2100				
3.2200	Supply and installation of watermeters				
3.2201	Watermeter PN16, for pipe DN 250 mm	nb	1.00		
	Sub-Total 3.2200				
3.2300	Supply and installation of washouts				
3.2301	Washout PN16, DN 80 mm	nb	1.00		
	Sub-Total 3.2300				
3.2400	Supply and installation of connections to existing pipes				
3.2401	Connection to existing pipes 250 mm with all the necessary fittings	nb	1.00		
	Sub-Total 3.2400				
	Sub-Total 3.2000				
3.3000	Valve chambers and Surface box units				
3.3100	Construction of pre-cast or cast in situ, concrete valve chamber (excluding cover and frame)				
3.3102	Valve chamber internal size 125 x 100 cm x cm	nb	2.00		
3.3103	Valve chamber internal size 150 x 150 cm x cm	nb	2.00		
	Sub-Total 3.3100				
3.3200	Valve chamber cover				
3.3201	Valve chamber cover Grade A	nb	4.00		
	Sub-Total 3.3200				
3.3300	Surface box units				
3.3301	Supply and installation of surface box unit	nb	3.00		
	Sub-Total 3.3300				
	Sub-Total 3.3000				

SECOND PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

BILL C: TRANSMISSION LINES

COMPLETION OF THE DRINKING WATER NETWORK IN TAALABAYA

ITEM Nb	DESCRIPTION	UNIT	QUANTITY	UNIT RATE USD	TOTAL AMOUNT USD
3.4000	Concrete works				
3.4001	Mass concrete - Class C20 for blinding	cu.m	2.00		
3.4002	Mass concrete - Class C25 for pipe supports, thrust blocks, anchors, pipe bedding and surround at river crossing.	cu.m	3.00		
3.4003	Reinforced concrete - Class C25 for pipe anchors, supports, protection slabs, thrust blocks, drainage and irrigation channels and reinforced concrete surround	cu.m	2.00		
	Sub-Total 3.4000				
3.5000	Testing and commissioning of potable water pipes				
3.5011	Testing and commissioning of 250 mm DI pipes	lin.m	300.00		
3.5011	Testing and commissioning of 63 mm pipes	lin.m	1,200.00		
3.5011	Testing and commissioning of 50 mm pipes	lin.m	1,200.00		
	Sub-Total 3.5000				
3.6000	Road Reinstatement				
3.6100	Cutting				
3.6101	Cutting of paved roads for water pipes	lin.m	1,700.00		
	Sub-Total 3.6100				
3.6200	Reinstatement				
3.6201	Reinstatement in one layer of paved roads including recutting works	sq.m	2,500.00		
	Sub-Total 3.6200				
	Sub-Total 3.6000				
	Total COMPLETION OF THE DRINKING WATER NETWORK IN TAALABAYA				

SECOND PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY OF BILL C: TRANSMISSION LINES

Nb	DESCRIPTION	TOTAL AMOUNT USD
8	COMPLETION OF THE DRINKING WATER NETWORK IN TAALABAYA	
	TOTAL	

SECOND PART OF WORKS

CONSTRUCTION OF WATER WORKS IN OUADI ED DELEM-QABB ELIAS AND
MRAIJAT
VOLUME 5 - PART B - BILL OF QUANTITIES

SUMMARY

SUMMARY

Nb	DESCRIPTION	TOTAL AMOUNT USD
5	BILL C: TRANSMISSION LINES	
	TOTAL	

SUMMARY

Nb	DESCRIPTION	TOTAL AMOUNT USD
FIRST PART OF WORKS		
1	BILL A: CIVIL WORKS	
2	BILL B: ELECTROMECHANICAL WORKS	
3	BILL C: TRANSMISSION LINES	
4	BILL D: BOREHOLES	
	TOTAL VALUE FOR FIRST PART OF WORKS	
SECOND PART OF WORKS		
5	BILL C: TRANSMISSION LINES	
	TOTAL VALUE FOR SECOND PART OF WORKS	
	GRAND TOTAL VALUE OF THE OFFER	