Lebanese Republic
Council for Development and Reconstruction

Ministry of Education and Higher Education

LEAP - Lebanon Emergency Assistance Project

Rehabilitation of Shelters (Public Schools)

Batch 4 – Lot 2 – Donieh, Tripoli

Tender Documents

Volume 3 – Bill of Quantities

(Part 1 of 2)

October 2026

KREDO
SAYDEH ST., CARMEL BLDG., P.O. BOX 166864
ACHRAFIEH, BEIRUT, LEBANON
TEL: 961-1-204957/ 8/ 9 - FAX: 961-1-336399

Lebanon Emergency Assistance Project (LEAP)

Tender Preparation and Construction Supervision for the Rehabilitation of Schools–Shelters

---

LEAP-CS-MEHE4- BATCH 4 – Bill of Quantities

Table of Contents

LEAP-CS-MEHE4- Batch 4 – Lot 2 – Donieh, Tripoli

- **Batch 4 – Lot 2 - Donieh, Tripoli (Part 1 of 2)**
  - ***General Preamble***
  - ***General Requirements***
  - ***BOQ of 9 Schools***

- **Batch 4 – Lot 2 - Donieh, Tripoli (Part 2 of 2)**
  - ***BOQ of 9 Schools***

LEAP-CS - MEHE4- Batch 4
Lot 2 – Donieh, Tripoli (21 Schools)

No.	School Name	CERD/TVET	Governorate	Caza
1	El Beddaoui Public High School ***(did not shelter displaced people during the war)*** ثانوية البداوي الرسمية	CERD 1420	North	Minieh - Donieh
2	El Beddaoui Second Public Kindergarten روضة البداوي الثانية الرسمية	CERD 1520	North	Minieh - Donieh
3	El Minie Public High School - English Section ثانوية المنية الرسمية فرع الانكليزي	CERD 1625	North	Minieh - Donieh
4	Bqaa Safrine Mixed Public School ***(did not shelter displaced people during the war)*** بقاعصفرين الرسمية المختلطة	CERD 497	North	Minieh - Donieh
5	Educator Victor Bitar - KfarHabou Mixed Public School المربي فكتور بيطار	CERD 470	North	Minieh - Donieh
6	Merkebta Mixed Public School مركبتا الرسمية المختلطة	CERD 450	North	Minieh - Donieh
7	El Zahriye - El Tabbaneh Public School for Girls مدرسة الزاهرية التبانة للبنات	CERD 1629	North	Tripoli
8	El Qobbeh New Primary Public School for Girls القبة الجديدة الابتدائية الرسمية للبنات	CERD 431	North	Tripoli
9	El Qobbeh New Mixed Public School القبة الجديدة الرسمية المختلطة	CERD 1542	North	Tripoli
10	El Qalamoun Public School for Boys القلمون الرسمية للصبيان	CERD 446	North	Tripoli
11	El Mina Mixed Public Kindergarten ***(did not shelter displaced people during the war)*** روضة الميناء المختلطة الرسمية	CERD 1634	North	Tripoli
12	El Nahda Public School for Girls النهضة الرسمية للبنات	CERD 392	North	Tripoli
13	May First Public School for Girls مي الاولى الرسمية للبنات	CERD 1607	North	Tripoli
14	Abi Firas El Hamadani Mixed Public School ابي فراس الحمداني الرسمية المختلطة	CERD 419	North	Tripoli
15	Ebn Rashed Public School for Girls ابن رشد الرسمية للبنات	CERD 423	North	Tripoli
16	Dahr El Maghr Third Public Kindergarten روضة ضهر المغر الثالثة الرسمية	CERD 1627	North	Tripoli
17	Baal Mohsen Mixed Public Kindergartens تجمع روضة بعل محسن الرسمية المختلطة	CERD 1338	North	Tripoli
18	Baal Mohsen Mixed Public School بعل محسن الرسمية المختلطة	CERD 1456	North	Tripoli
19	May Second Public School for Girls مي الثانية الرسمية للبنات	CERD 357	North	Tripoli
20	El Jdideh Public School for Boys الجديدة الرسمية للبنين	CERD 363	North	Tripoli
21	Farah Antoun Public School for Boys فرح انطون الرسمية للبنين	CERD 375	North	Tripoli

Grand Summary Table

Lot #: Lot 2 - Donieh, Tripoli

CERD	School Name (EN)	Batch 4 - Lot 2	Amount (US $)
	General Requirements	Batch 4 - Lot 2	
1520	El Beddaoui Second Public Kindergarten	Batch 4 - Lot 2	
1625	El Minie Public High School - English Section	Batch 4 - Lot 2	
470	Educator Victor Bitar - KfarHabou Mixed Public School	Batch 4 - Lot 2	
450	Merkebta Mixed Public School	Batch 4 - Lot 2	
1629	El Zahriye - El Tabbaneh Public School for Girls	Batch 4 - Lot 2	
431	El Qobbeh New Primary Public School for Girls	Batch 4 - Lot 2	
1542	El Qobbeh New Mixed Public School	Batch 4 - Lot 2	
446	El Qalamoun Public School for Boys	Batch 4 - Lot 2	
392	El Nahda Public School for Girls	Batch 4 - Lot 2	
1607	May First Public School for Girls	Batch 4 - Lot 2	
419	Abi Firas El Hamadani Mixed Public School	Batch 4 - Lot 2	
423	Ebn Rashed Public School for Girls	Batch 4 - Lot 2	
1627	Dahr El Maghr Third Public Kindergarten	Batch 4 - Lot 2	
1338	Baal Mohsen Mixed Public Kindergartens	Batch 4 - Lot 2	
1456	Baal Mohsen Mixed Public School	Batch 4 - Lot 2	
357	May Second Public School for Girls	Batch 4 - Lot 2	
363	El Jdideh Public School for Boys	Batch 4 - Lot 2	
375	Farah Antoun Public School for Boys	Batch 4 - Lot 2	

* Total Amount of Bill of Quantities …… $0.00
* Discount by Tenderer (_____ %) …… $0.00
* Provisional Sum for Unforseen Items $50,000.00

* Total Amount of Tender (VAT Not Applicable)

* Total Amount of Tender in Words:

Preamble

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
1	**INTRODUCTION**
1.01	The rules contained in this Preamble apply equally to both proposed and executed works.
1.02	The Bills of Quantities are to be read and construed in association with the Drawings, the Specification and this Preamble. Information which is given on the Drawings and/ or in the Specification is identified by cross references included in the descriptions of work in the Bill of Quantities.
1.03	Where work cannot be fully described or where the quantity of work required cannot be accurately determined, it is given as an item or a Provisional Sum.
1.04	Unless the term meter, used in this Preamble, is proceeded by the words square or cubic it is deemed to be linear.
1.05	The rates inserted by the Tenderer in the Bill of Quantities shall be in words and figures. In the case of discrepancy between the two, the rates written in words shall govern.
2	**QUANTITIES**
2.01	Quantities set out in the Bills of Quantities are the estimated quantities and they shall not be taken as the actual and correct quantities for ordering and purchasing of materials
2.02	Works shall be measured net as fixed in position in accordance with the rules contained in this preamble or except where otherwise stated in a measurement rule applicable to the work.
2.03	Dimensions used in calculating quantities are taken to the nearest integer (0.5 and over is regarded as 1 and less than 0.5 is disregarded).
2.04	Quantities measured in tonnes are given to two places of decimals. Quantities measured in other units of mass are given to the nearest whole unit except that any quantity less than one unit is given as one unit.
2.05	Unless otherwise stated, where minimum deductions for voids are dealt with in this Preamble they refer only to openings which are within the boundaries of measured areas. Openings which are at the boundaries of measured areas are always deducted irrespective of size.

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
3	**DESCRIPTIONS**
3.01	Headings to groups of items in the Bill of Quantities are to be read as part of the descriptions of the items to which the headings apply.
3.02	Dimensions are stated in descriptions generally in the sequence, length, width, height. Where ambiguity could arise, the dimensions are identified.
3.03	Dimensions given in descriptions are in millimeters unless otherwise indicated.
3.04	Unless otherwise specifically stated in the Bill of Quantities or herein, the following are deemed to be included in all work:
	- labor and all costs in construction therewith,
	- materials, products, goods and all costs in connection therewith,
	- Contractor's equipment, including but not limited to construction plant, scaffolding, tools, vehicles and the like and all costs in connection therewith,
	- assembling, fitting and fixing materials, products and goods in position,
	- any method of fixing, fixing to any nature of base or background including preparation and providing fixing materials,
	- breaking down for transport and installation and subsequent reassembly of composite items manufactured off site,
	- waste of materials,
	- square, raking and curved cutting,
	- work at any location or height,
	- work in small, isolated quantities,
	- protection of all work,

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
	- protection of all existing structures, utilities, site improvements, trees and vegetation, features, pavements and other facilities on and adjacent to the site, which are to remain upon completion of the work, - all other enabling tasks associated and subsidiary components and items of work which are indicated or reasonably inferred from the Drawings and/ or Specification and necessary to perform and complete the work described, - establishment and overhead charges and profit.
3.05	Except where items are included in the Bill of Quantities and are priced separately by the Contractor therein, provision of the following are deemed to be included with all work: - site administration and security, - insurances, - bonds and guarantees, - water for the Works, - lighting and power for the Works, - temporary accommodation for the use of the Contractor and the Engineer, - temporary telephones and the cost of calls for the use of the Contractor and the Engineer, - temporary roads, hardstandings, crossings and the like, - temporary fencing, hoardings, screens, fans, footways, guardrails, gantries and the like, - giving notices and making applications, including the payment of fees and charges in connection therewith, - safety, health and welfare of workpeople, - compliance with traffic regulations - maintenance of public and private roads, services and adjoining property,

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
	- control of noise and pollution, prevention of fire and compliance with all other statutory and general obligations, - removing rubbish, protective casings and coverings, and cleaning the Works on completion, - drying the Works, - testing and commissioning of service installations including the provision of fuel, - samples of materials and testing of materials including providing equipment for testing, - design, co- ordination, installation and as- built record drawings and the like, - preparation and submittal of reports, records, certificates, notices, proposals, designs, details, calculations and other information and data required by the Specification, - allow in unit rates for all other requirements, services, provisions, liabilities and obligations contained in the General Requirements and Conditions of Contract. - Maintaining, adapting, clearing away and making good are deemed to be included with the items for temporary works. - Payment of any customs and other import duties, harbor and port dues, wharf age, landing, pilotage and any other charges or dues including demurrage charges on any Goods or other things required for or in connection with the Works entering or leaving the country.

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description

4 **SYMBOLS, ABBREVIATIONS & DEFINITIONS**

4.01 The following symbols and abbreviations are used in this Preamble and in the Bills of Quantities:

Lump Sum …. LS
Linear Meter …. m
Square Meter …. m²
Cubic Meter …. m³
Centimeter …. cm
Millimeter …. mm
Number …. №
Kilogramme …. kg
Tonne …. T
Percentage …. %
Nominal Diameter …. Φ
Quantity …. Qty
Drawing …. Drg / Dwg
Mega Pascal …. MPa

4.02 The following definitions apply to all work:

- 'horizontal' means level or sloping work not exceeding 15º from the horizontal
- 'sloping' means sloping work exceeding 15º but not exceeding 80º to the horizontal,
- 'vertical' means work exceeding 80º from the horizontal,
- 'curved' means curved in any direction or in more than one direction and to any radius or radii and includes curved work to domes, vaults and the like.

4.03 The term 'extra over' means that work so described involves extra cost over the basic work in which it occurs. No deduction of the quantity of basic work is made for the extra over work.

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
5	**MECHANICAL ENGINEERING SERVICES PREAMBLE**
5.01	Mechanical equipment has been measured in complete items unless otherwise stated in the specification and bill item. The rates for all items shall include for supplying all materials, fixing, terminating and connecting all accessories and components for a complete and functional item.
5.02	The Contractor shall consult the relevant sections of the specification when query or doubt arise.
5.03	The Contractor shall consult with, and employ specialist sub-contractors for specific items of work as identified in the specification. All costs associated with such works shall be included in the tender. Specialist sub-contractors will be of recognized expertise, acceptable to the engineer.
5.04	All items of mechanical plant shall be connected to the control and power systems by wiring out from the mechanical control centers. All wiring shall be carried out by competent and qualified electricians under the mechanical scope of works.
5.05	Rates/prices entered against the items shall include for all costs in connection with the following:
a.	Connection items of plant and equipment as necessary to the control and power systems.
b.	Provision of starter's, protective devices, automatic change over/load shedding facilities, remote & local isolation/emergency shut off as appropriate, control functions and alarms to achieve the intent outlined in the Control Section of the Specification. All motors to be of the 'Low Energy' type as specified.
c.	Off loading, storing, connecting up, protecting as necessary, testing, flushing, cleaning, charging, balancing, commissioning and testing individual items of plant as well as complete systems installations all as specified & directed by Engineer.
d.	Supports, brackets and fixings of every description required to complete the works.
e.	Cutting or forming all holes, mortises, chases and the like in the structure to facilitate the various works and making good in all trades as necessary;
f.	Coordination with other associated trades, designers and specialists, at the time preparing shop drawings and during the works progress.
g.	Cost of the items in the BOQ includes all works, materials and labors of all items mentioned above.

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
6	**ELECTRICAL ENGINEERING SERVICES PREAMBLE**
6.01	Rates for all items of equipment and materials shall be inclusive of all labor, electric power during installation and testing oxygen, acetylene, water, transport, rigging, temporary works, stores, offices, instruments insurance, customs, duties, overhead, profit certificates, samples, tests, supply of all information and data, supply of catalogues, charts, curves, submittals, certified drawings and all other information and services called for in the specification, all fully connected up and good working order. Rates shall also include for:
a.	All builders work in connection with fixing of supports brackets, clips as required
b.	Cutting or forming all openings, mortises, chases, etc., in floors, walls and ceiling required for the installation and making good after
c.	Construction of manholes, handholes and the like
d.	Fitting of access doors in walls and ceilings.
e.	Supplying and fixing supports, brackets and clips as required.
f.	Cutting away and making good after all trades for frames, sleeves, cables, cable trays, chases for conduits and fixing of electrical boxes, conduits, accessories.
g.	Excavating and back filling trenches for cables, pipes and providing and laying precast concrete protective tiles.
h.	Repair, repaint and generally make good and leave in perfect condition all the work executed by him under the contract.
I.	All other work in connection with the installation that is not measured separately.
j.	Electrical equipment is enumerated unless otherwise stated and the rates shall include for supplying all materials labor, plant, fixing, terminating and connecting accessories, etc.

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
k.	Feeder cables are measured in linear meters from the boards to equipment, or from the distribution board to sub-main, etc. Rates shall include for the supply of materials, laying, terminating, trenching, cable trays, ducting, etc.
l.	Lighting points are enumerated and the rates shall include all necessary wires, conduits, boxes and accessories, etc., required to provide power from the LP boards switch panels and switches are measured separately.
m.	Lighting fittings are enumerated and the rates shall include the supply, installation and connections.
n.	Disconnecting/Isolating switches are enumerated and the rates shall include all necessary wires, conduits, boxes etc. If the switches are fed by cables, then the cables are measured separately.
o.	Lighting switches, sockets, fan/coil unit spur boxes, fused spurs for fans, kitchen, laundry equipment outlets, toilet fans points are enumerated and the rates for each shall include all wiring, conduits, accessories etc.
p.	Earthing systems to include for all materials, labor, fixing, terminating, earth pits, rods, conductors, excavations.
q.	Main distribution board, sub-mains, lighting and power panels, panel boards, etc., are enumerated items and rates shall include all the board installed completely as specified and as shown on the drawings. (cables are measured separately)
r.	End of session bell system is one item. Bells and bell push button, are enumerated and include all conducting, wiring, controls, and all necessary accessories.
s.	Lightning protection system, roof conductors, tie conductors down conductors are measured in linear meters completely installed.
t.	Earth pits are enumerated. The cost shall include all materials, wiring, fixing, supports, etc., and bolting copper conductors to rebars to have a complete working system.

Preamble

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description
u.	The rates for automatic transfer switches include the switches completely installed with all ancillary equipment, control, modules to have a complete working system.
v.	Cost of the items in the BOQ includes all works, materials and labors of all items mentioned above.

End of Preamble

Bill № 1: General Requirements

Bill № 1: General Requirements

Lot #: Lot 2
Lot Name: Donieh, Tripoli

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
	Notes				
	These General Requirements are applicable to the whole of the Works. If the Tenderer wishes to price any of the items contained herein, then each such item, clause, or sub-clause must be individually priced. The Tenderer shall not enter lump sums covering more than one or all items, clauses and sub-clauses. If the General Requirements item has not been priced it will be deemed that the value of such item, clause or sub-clause is included in the rates for measured items elsewhere in the Bill of Quantities.				
1	**Preliminaries**				
1.01	Insurance				
	Provide the following insurances from an approved insurance company, all as detailed in the Conditions of Contract.				
	- Professional Indemnity Insurance.				
	- Contractor's All Risk Insurance.				
	- Plant and Equipment Insurance.				
	- Workmen Compensation Insurance.				
	- Third Party Insurance.	LS	1		
	Lump Sum in Words:				
1.02	Programme of Works				
	Prepare and submit to the Engineer for approval a detailed Programme for the construction showing the proposed order & method to execute the Works, the dates upon which the various elements, trades, sections and items of Works will be started and completed, and the cash flow estimate, complete including monthly forty-five day program, all necessary revisions and updates, monitoring, all supporting data, computer analysis schedules, and all other related works, all to Engineer's satisfaction.	LS	1		
	Lump Sum in Words:				
	Total Bill № 1: General Requirements				

General Summary

Lot #: Lot 2 - Donieh, Tripoli

Description	Amount (US $)
Bill № 1: General Requirements	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Provisional Sum for Unforseen Items	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№	3		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№	1		
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	7		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№	8		
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№			
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²	650		
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²	10		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	1,000		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	150		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	150		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	12		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№			
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Beddaoui Second Public Kindergarten

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	20		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№			
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	2,000		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	200		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	200		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	16		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№	2		
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№			
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Minie Public High School - English Section

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	30		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№	250		
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m	15		
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²	60		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	4,200		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	180		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	250		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№	8		
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№	2		
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	14		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№	25		
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№	8		
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№	4		
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№	22		
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS	1		
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Educator Victor Bitar - KfarHabou Mixed Public School

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m	40		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	30		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№			
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	1,400		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	100		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	100		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	13		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№			
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: Merkebta Mixed Public School

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	20		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№	12		
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	2,800		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	250		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	250		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	12		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№			
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS	1		
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Zahriye - El Tabbaneh Public School for Girls

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	8		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№			
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	100		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	50		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	50		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	11		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№	1		
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№	2		
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№	5		
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Primary Public School for Girls

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№	50		
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m	30		
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№	4		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№	1		
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№	7		
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m^2			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	1,000		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	250		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	250		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	10		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№	4		
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№	1		
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS	1		
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qobbeh New Mixed Public School

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№	24		
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№	1		
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	2,500		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	250		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	250		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	14		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№	1		
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№			
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Qalamoun Public School for Boys

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....

Bill № 2: Civil and Architectural Works

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**SITE PREPARATION AND DEMOLITION**				
1.1	**Demolishing and Removal of Debris**				
1.1.1	The works include all types of demolition and the removal of debris and damaged elements such but not limited to, the following:				
-	Existing plastering and concrete items such as foundations, columns, slabs, etc.				
-	Damaged Tiling (floors and walls)				
-	Toilet fixtures and pipes installation of all sizes				
-	Counter tops, bases and sinks				
-	Water tanks of different types				
-	Hollow concrete block walls or concrete walls of all sizes				
-	Demolition of the existing ramps / Stairs and the execution of the given plans and specifications				
-	Including the necessary equipment for the removal of debris and all resulting materials				
-	etc.	LS	1		
	Rate or Lump Sum in Words:				
2	**SITE PREPARATION AND DEMOLITION**				
2.4	**School Fences with Related Gates**				
2.4.2	Rehabilitate Existing Fence (Strengthening & Rehabilitation)				
	Work to include				
-	Rehabilitate and support all the existing fence as per drawings				
-	Determine the places that requires support				
-	Preparation of shop drawings				
-	Replace all broken elements				
-	Redo all damaged elements and to be similar to existing elements				
-	Finishing works as existing (plastering, paints, stone cladding, etc.)				
-	Rehabilitate existing steel protection (Replace all damaged part by new similar to existing and paint with epoxy as specified)				
-	Replace existing chain link by new one (Galvanized)				
-	Reconstruct the broken and damaged parts and rehabilitate as it was with all similar materials including steel parts with related epoxy paint as per the engineer instructions	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**MASONRY**				
4.1	**Hollow or Solid Concrete Blocks and Claustra**				
	Supply and install concrete blocks as per drawings				
	Work to include:				
-	All places as per the drawings, and the Engineer instructions.				
-	Materials				
-	Cement mortar and the use of extruded nets and reinforcement by means of metal gates and the placement of angles of galvanized steel iron of concrete columns thickness of 4 mm every 60 cm				
-	Labors and all items needed and instructions by the Engineer				
4.1.4	15 cm hollow concrete blocks	m²			
	Rate or Lump Sum in Words:				
5	**METAL WORKS**				
5.1	**Provide New Steel Work (Door & Windows)**				
5.1.3	Provide new double glazed aluminum windows with new burglar proof protection	№			
	Rate or Lump Sum in Words:				
5.2	**Rehabilitate and Maintain the Existing Steel Work (Burglar Proof Protection + Opening)**				
	Rehabilitate the existing steel windows or doors as per specifications and drawings and the Engineer instruction				
	Work to include:				
-	Remove all damaged members and replace by new ones				
-	Rub completely to secure all parts and use putty to make faces smooth				
-	Apply two layers of anti rust paint				
-	Apply putty				
-	Apply three layers of epoxy external paint				
-	All needed items as per the Engineer instructions				
5.2.1	Rehabilitate existing steel doors	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.2.2	Rehabilitate existing steel gates	№			
	Rate or Lump Sum in Words:				
5.2.6	Rehabilitate and paint existing steel window	№			
	Rate or Lump Sum in Words:				
5.5	**Rehabilitate and Maintain Steel Handrail**				
-	Rehabilitate the existing metal handrail and remove the damaged members and replace by new				
-	Reinforce the existing handrail with similar members in addition to the rail and all necessary accessories				
-	Remove existing paint & clean deeply as per SSPC code and ISO 8501				
-	Apply one layer of epoxy base paint				
-	Apply putty				
-	Apply epoxy paint as per specification				
	All needed items as per the Engineer instructions				
5.5.1	Floor Mounted	m			
	Rate or Lump Sum in Words:				
6	**WOOD AND PLASTICS**				
6.1	**Joinery Works**				
6.1.1	Rehabilitate Existing Kitchen Cupboards				
	Rehabilitate existing cupboards, cabinets, drawers, counters, etc., for the existing kitchen. Works to include replacing damaged elements, accessories, material, labor, equipment, maintaining support, change of the top of counter by new resin counter as specified, etc. As per engineer's approval.				
-	Repair wood elements in accordance with AWI Quality Standards requirements.				
-	Repair framing and sash members with mortise and Tenon joints. Ensure joints and connections are flush, hairline, and weather-tight.				
-	Scarf joints permitted when wood matches in color and grain texture. Form sills and stools in one piece.				
-	Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet allowing installation and dynamic movement of perimeter seal.				
6.1.1.1	Kitchen Cupboards	m			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8	**DOOR AND WINDOWS**				
8.1	**Wooden Doors and Windows**				
	Supply and install all timber work with all related items				
	The joinery works should be of the first class type and as per specifications and drawings				
	Work to include:				
-	Material and labors				
-	All accessories to be heavy duty (Hinged, Lock, Glass vision, as required, etc.)				
-	The frame for any width (Steel, Wood, etc.)				
-	Paint as follows:				
-	Anti rust layers				
-	Putty + one layer of undercoat				
-	Three layers of epoxy paint				
-	Apply and fix 6mm wired clear glass				
-	View Permitting glass opening where needed				
-	remove the existing timber panels				
-	repair the edges				
-	The Contractor should submit shop drawings				
-	All needed items as the Engineer instructions				
8.1.1	**Timber Doors**				
	Supply and install flush timber door as per drawings with laminated plastic facing and the door should have 10cm width frame between the plywood and fill with timber beads by tongue and groove each 5cm, and the door edges should behead wood and fixed by tongue and groove frames should be as specified, with fixed glass panel vision window, and similar to existing, and to the Engineer's instructions				
-	Works included, all accessories and fittings, pre-painting and finishing paint sides of doors and box frames.				
-	All works should be done as per the Engineer instructions				
8.1.1.2	Provide new single leaf wooden door with view frame	№			
	Rate or Lump Sum in Words:				
8.1.1.3	Provide WC partition door	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3	**Rehabilitate the Existing Timber Doors**				
	As stated in the Preambles of Item 8.1				
	In addition, rehabilitate the existing timber doors:				
	The minimum amount of existing timber should be removed to allow an effective repair to be formed.				
	Cut out deteriorated area of timber in sloping splice to give optimum area of surface to be glued & fixed.				
	Well-seasoned timber to be used in forming a repair with the line and density of grain (number of growth rings) of new timber matching the existing as closely as possible.				
	For all joinery work, timber with shakes, fissures, warping, heartwood, sapwood or numerous/large knots should be avoided for use in repair. Always work new material to the line of the existing and avoid unnecessary trimming of original timber. Repairs should follow any existing deformations in the line of the wood element (e.g. door or window).				
	Avoid mixing timber species between new and existing in a repair as joint between the two is likely to fail from different rates of expansion and contraction during dry & damp conditions. Where possible, spliced repairs to be designed to ensure moisture is towards the outer face of timber and that moisture does not lay on the repair joint.				
	The length of the splice is governed by section of timber and the nature of component being repaired and it should be designed to ensure an effective bond between new and existing sections of timber. Where wood element are to be dismantled as part of the repair process, always mark and record the constituent parts before dismantling. similarly, number of glass panes/quarries before removal.				
	If applicable carefully soften putty or remove wood trim and then remove glass. Use glue, to connect a new outer section of bottom rail to the existing sound timber. Drill and insert new wooden pins or fix using brass screws from inside.				
	Casements or sashes are often in sound condition but the joints have become loose due to the break down of glue and loose wedges.				
	The wedges will often be easily removable and will probably be unsuitable for re-use. It may be for the joints to be pulled together successfully.				
	Attach door frame and shims to perimeter opening to accommodate construction tolerances & all irregularities.				
	Align door plumb and level, free of warp or twist. Maintain dimensional tolerances and alignment with adjacent work. Install operating hardware.				
8.1.3.1.1	Rehabilitate and paint existing single leaf timber doors with related accessories	№	41		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.1.3.1.2	Rehabilitate existing double leaf door	№			
	Rate or Lump Sum in Words:				
8.1.3.1.4	Rehabilitate wooden windows	№			
	Rate or Lump Sum in Words:				
8.2	**Aluminum Doors and Windows**				
	Fabricate, supply and install aluminum works as manufactured by SIDEM 2000 first choice with all necessary accessories as per the drawings and the Engineer instructions, cost to include all doors and windows:				
-	Reveals hard stone 3cm thick, all around for external opening				
-	Apply EPDM around door and windows where necessary				
-	Single glass 6 mm				
-	Double glass 6-12-6 mm (Outer Glass should be Tempered)				
-	Hinges and locks				
-	Joint Filler				
-	Mosquito Screen				
-	Mesh				
-	All items needed as per the Engineer instructions				
-	All as specified and base on an approved shop drawings after exact dimensions				
8.2.1	**New Aluminum Panels (Double Glass)**				
	Supply and install the fabricated aluminum panels with double glass (6 - 12 - 6 mm) (Outer Glass should be Tempered)				
8.2.1.1	Provide new aluminum double glazed window & door panel	№			
	Rate or Lump Sum in Words:				
8.2.2	**New Aluminum Internal Door**				
	Supply and install aluminum door with frame and related strengthening stud, Works to include:				
	Materials, and accessories				
-	Labors				
-	All needed items as per the engineer instructions.				
-	Repair all around the opening				
8.2.2.1	Provide new aluminum partition door as indicated.	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
8.2.3	**Rehabilitation Existing Glazed Aluminum Panels (s)**				
	Replacing Broken Glass. Fixing Hardware Issues: Check the functionality of latches, hinges, and other hardware. If any parts are broken, replace them with new ones to ensure the window operates smoothly. After repairs, apply a high-quality sealant around the edges to prevent moisture intrusion. If the paint is peeling or faded, consider repainting the frame with a metal paint formulated for aluminum to enhance durability and appearance.				
8.2.3.1	Rehabilitate existing windows	№	10		
	Rate or Lump Sum in Words:				
9	**FINISHES**				
9.1	**Cement Plaster**				
	Supply and install sand cement plaster on concrete and block wall surfaces as specified				
	The plaster layer should be own a base rough layer				
	The plaster works should be on level points and each point should be at 1.5 m from the second only				
	Work to include:				
-	Materials and accessories (galvanized, wire mesh, cover beds, etc.)				
-	Labors				
-	All addition watering				
-	All tools				
-	Plaster thickness more than 2 cm				
-	All needed items as per drawings and the Engineer instructions				
9.1.1	**Internal and External Plaster Works**				
9.1.1.1	Supply and apply one layer of sand cement plaster over a rough textured layer of plaster				
	Price included all accessories, material, scaffolding and labor, etc.	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.1.2	**Repair of Existing Plaster (Internal - External) (Cracks, etc.)**				
9.1.2.1	Rehabilitate and repair cracked and damaged plaster indoor and outdoor				
	Work to include:				
-	Determine the location and remove all loose items around the area				
-	Remove the cracked plaster layer				
-	Remove the pulled out layers				
-	Clean the places with suitable materials				
-	Fill all cracks after widening by (No Suggestions) or approved equal.				
-	Remove loose and other deteriorated materials prior to the new repair. Take special care not to damage the adjacent original materials. Prepare mortar joints for installation of lateral reinforcement where it is required. Use thin steel bars to clean joints to maximum depth possible. Remove loose mortar. Mix mortar with minimal amount of water (potable) prior to use. All separation cracks between perpendicular walls shall be filled grout to reduce additional movement from wind loads and thermal expansion-contraction.				
-	Clear debris from crack by probing, brushing, and blowing.				
-	Force non-shrink mortar mixture into crack as deep as possible with hands, wood and metal probes. Use as dry a mix as possible. Use stone bats to fill larger crack voids. Ensure mortar is forced into smaller/deeper cracks. Mortar grout will be fluid in order to flow into crack. Either grout bags or gravity flow shall be used depending on the conditions. Fil Protect repairs from rapid drying by misting, shading, protecting from dry wind cracks in a series of applications rather than one large application. Final application shall not be flush with the surface, but shall be one half the width of the crack below the surface. Remove all tool marks with brush.				
-	Apply the finish rough plaster layer				
-	Install galvanized steel mesh 20 cm width at least				
-	Apply the second smooth plaster layer	LS			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2	**Tiling Works**				
	Supply and install all tiling items for floors, with the skirting				
	Work to include all materials and labors and the Contractor should use all necessary rods and levels as per the Engineer instructions				
	Price to include:				
-	Sand below tiles				
-	Materials, tiles, mortars				
-	Labors				
-	Rubbing				
-	Filling between tiles				
-	Filling the skirting				
-	Remove unsuitable items				
-	Cleaning the places				
-	All needed items as per the Engineer instructions				
9.2.1	**New Full Mass Colored Ceramic for Floors**				
	Ceramic tiles and tilework as specified and detailed, installed complete; Including for substrate preparation, cement: sand screeds or plaster backing coats; setting, jointing and grouting; tile trim and accessories; sealants; and all other related ancillaries as indicated or required				
9.2.1.1	Supply and install anti skid colored full mass ceramic tiles for classroom (first choice) for all floor toilets, kitchen and laboratory (existing and new)	m²			
	Rate or Lump Sum in Words:				
9.2.1.2	Skirting same type of floors or as existing or required	m			
	Rate or Lump Sum in Words:				
9.2.2	**New Glazed Colored Ceramic for Walls**				
9.2.2.1	Supply and install glazed colored ceramic for walls Include Ceramic Corner (first choice)	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.3	**New Tiles for stairs**				
	Supply and install tiles first choice for the new stair (treads 3cm thick - Risers 2cm thick) and landing - tiling 2cm and for all floors or otherwise specified color type and quality to be submitted for approval, works to include:				
-	Labor, materials and installations				
-	Under tile fill				
-	Mortar				
-	Lining				
-	Step (Tread + riser) and landing and all type of skirting				
-	And needed items to complete the works as per the Engineer instructions				
9.2.3.2	Granite 2cm Thick (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.3.3	Mosaic Similar to existing 4cm Thick minimum (Tread and Riser)	m			
	Rate or Lump Sum in Words:				
9.2.4	**Repair existing broken floor tiles and skirting (all types) and reinstall by new, similar to existing for all rooms and corridors**				
9.2.4.1	Rehabilitate and repair all damaged and broken tiles, and skirting for any type (marble - ceramic - mosaic - Cement). Remove broken or damaged pieces to be replaced without affecting the adjacent undamaged areas				
	Work to include:				
-	Remove all debris as specified				
-	All materials and labors				
-	Difference tiles (shapes thickness, dimension, pattern) as needed.				
-	Cutting and repair				
-	Grouting				
-	Polish and rubbing				
-	All needed items as per Engineer comments and complete to Engineer approval.	LS	1		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.2.5	**Rehabilitate Existing Stair Treads and Riser**				
	Remove the broken treads and risers, install and supply new ones similar to the existing with the needed side bases, width as per site dimension with skirting and tiles for landing				
	The work to be as per the Engineer instructions				
9.2.5.1	Existing Mosaic Stair	m			
	the price including Skirting tiles & Landing				
	Rate or Lump Sum in Words:				
9.2.10	**Laminate Vinyl Tiles**				
9.2.10.1	Provide Laminate Vinyl Tiles similar to existing. The removal of existing vinyl tiles, rolls, proper levelling, surfacing of the existing concrete by casting a special layer of new concrete to ensure proper installation of the new vinyl layer as specified and as per standards. Price to include skirting	m²			
	Rate or Lump Sum in Words:				
9.4	**Gypsum Works**				
9.4.1	**New Gypsum Suspended Ceiling (Panel, Tiles):**				
9.4.1.1	Supply and install gypsum board tiles suspended ceiling (60 x 60 cm or panel board with paint)				
	Work to include:				
-	Remove the existing gypsum board tiles and move them to outside				
-	Labors				
-	Materials				
-	Accessories				
-	Angles				
-	Special Heavy duty metal suspension system				
-	All needed items as per the Engineer instructions and approval	m²			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
9.5	**Painting**				
9.5.1	**Wall and Ceilings Paint Works**				
	Wall paint include preparation of the base surfaces to receive the paints and apply the specified layers of putty and paint from the best quality as per specifications and as indicated in drawings				
	The base surfaces should be clean and smooth and free from any pulled out old paints before starting application of the specified primer/undercoat.				
	Apply 2 layers of putty then after smoothening, then 3 layers of the approved paint materials.				
	All works and items should be as per manufacturer recommendation, compatible with each other and as per the Engineer instructions and approval, ***All paint types must be lead-free and Low VOC (Volatile Organic Compounds)***				
9.5.1.2	Super Rubber Paint for old walls and ceilings	m²	2,000		
	Rate or Lump Sum in Words:				
9.5.1.4	Oil Paints for old walls and ceilings	m²	250		
	Rate or Lump Sum in Words:				
9.5.2	**Outside Walls Paint (Old and New Walls and Ceilings)**				
9.5.2.1	Paint for external old and new walls, smooth touch				
	Work to include:				
-	Removal of any paint or obstacle				
-	Rehabilitate the surfaces and make them goods				
-	Polyurethane where needed for cracks				
-	Apply one coat of undercoat				
-	Apply 2 coats of external paint or rolled textured paint				
-	Apply one layer of external transparent paint (acrylic styrene copolymer elastic water proof)				
-	All needed scaffolding and materials for the best execution of the works				
-	All works and items should be as per manufacturer and the Engineer instructions and approval.	m²	250		
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10	**SPECIALTIES**				
10.1	**Bathrooms Accessories**				
-	Remove and cart away old damaged fixtures				
-	Supply and install all needed accessories and make good their places and their surroundings				
-	Place all frame, cover joints (stainless steel) anti-corrosion				
-	Install items and their contact with the surfaces				
-	All works should be done as per the Engineer instructions				
10.1.4	**Mirror for Lavatories**				
	Supply and install 6mm glass mirror for lavatories with colored PVC frames as show on drawings and as stated in the specifications with all needed items and accessories				
	The mirror should be placed on 3mm thick plywood from the back				
	All works should be done as the Engineer instructions				
10.1.4.1	Mirror (Dimension as per site conditions and engineer instruction)	№			
	Rate or Lump Sum in Words:				
10.3	**Resin Work**				
10.3.1	**Drinking Basin**				
	Supply and install drinking basin as shown on drawings of resin layers 12 mm thick fixed on galvanized steel skeleton 4 x 4 cm hollow sections and as shown on drawings				
	Work to include:				
-	Materials				
-	Labors				
-	Galvanized steel skeleton				
-	All needed items and as instructed by the Engineer				
10.3.1.1	Drinking Basin -Length (up to 2.20 m)	№			
	Rate or Lump Sum in Words:				
10.3.1.6	Drinking Basin -Length (4.11 to 6.20 m)	№			
	Rate or Lump Sum in Words:				

Bill № 2: Civil and Architectural Works

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
10.3.4	**Kitchen Counter**				
	Supply and install complete counter resin type with sink (resin) for teachers' kitchen of 18mm thick including coved splash back 20cm height and the work to include:				
-	All fixing elements				
-	All stainless steel hangers				
-	All necessary accessories				
-	All needed items and as instructed by the Engineer				
10.3.4.2	Kitchen Counter - Length (1.11 to 1.75m)	№			
	Rate or Lump Sum in Words:				
	Total Bill № 2: Civil and Architectural Works				

Bill № 3: Mechanical Engineering Services

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**GENERAL TECHNICAL REQUIREMENTS**				
1.1	**General Mechanical Requirements**				
1.1.2	Prepare the shop drawings for all mechanical works and obtain approval from the Engineer before the start of executing any work.	Item	1		
	Rate or Lump Sum in Words:				
1.2	**Rehabilitation Works General Requirements**				
	Provide all necessary rehabilitation works and make all Mechanical systems in good condition complete including maintenance, cleaning, relocation works, replacing damaged items and equipment, removing and carting away resulting materials and equipment, testing and commissioning, and all other related works to ensure all Mechanical systems are properly working and functional.				
1.2.1	Maintenance and rehabilitation of existing plumbing works, including sanitary fixtures, floor drains, roof drains, manholes, pumps, WC tanks, adding where applicable all necessary valves, flush valves, etc., and all other necessary works.	Item	13		
	Rate or Lump Sum in Words:				
2	**SANITARY, WASTE & RAIN WATER PIPE WORK INSTALLATION**				
2.3	**Drain Cover**				
	Supply and install floor drain cover (P.E) 5 mm thick on drainage pipe and to be the same level of the floor tiling. Work to include all civil works and as per the Engineer instructions				
2.3.1	Cover for FCO	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**WATER PIPE WORK INSTALLATION**				
3.1	**Water Tanks**				
	Supply & install polyethylene water tank (3 layers) or more with all necessary supply and over flow connections all as per the Engineer instructions				
3.1.2	2000 liters PE water tank	№			
	Rate or Lump Sum in Words:				
5	**SANITARY FIXTURES**				
5.1	**W.C. for Kids**				
	Supply and install K.G. W.C. Flush valve with cover as manufactured by Duravit - Bambi No. 018509 or approved equal, 35 cm height max. from finished floor with timber cover.				
	Cost to include all related connections angle valves and necessary accessories as per the Engineer instructions.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.1.1	EWC-03 (Wall Hang - 52 x 32 cm)	№			
	Rate or Lump Sum in Words:				
5.2	**W.C. For Non Kids**				
	Supply and install W.C. for non kids, Flush valve with cover as manufactured by Ideal Standard Item No. E876801 also the hose, or approved equal and to be 40 cm from floor finish with timber cover.				
	The work to include the installation, liking, cleaning with all necessary connection, angle valves and necessary accessories similar to the K.G.W.C.				
	Each W.C. should be equipped with a Flushing Hose (Grohe or Ideal standard or approved equal)				
5.2.1	EWC-01 (Wall Hang - 52 x 36 cm)	№			
	Rate or Lump Sum in Words:				
5.2.3	AWC-01 (Asian water closet)	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.3	**Lavatories for Kids in the K.G.**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal, 45 x 36 cm, and fixed at 60 cm high from the floor finish. Cost to include all necessary connections, angle valves and accessories as required				
5.3.1	LAV-03 (semi-pedestal wash basin - 45 x 35 cm)	№			
	Rate or Lump Sum in Words:				
5.4	**Lavatories for Non Kids**				
	Supply and install semi pedestal wash basin similar to Ideal Standard No. 742001 or approved equal and fixed at 82 cm high from the floor finish. Cost to include all necessary connections, angle valves, traps and necessary accessories as specified.				
5.4.1	LAV-01 (semi-pedestal with mixers 55 x 45 cm)	№			
	Rate or Lump Sum in Words:				
5.5	**Urinal**				
	Supply and installation of high quality urinal units complete with proper wall fixation with anti-dust materials including drainage & water supply connection as per the approved shop drawings.				
	Cost to include all necessary accessories, valves, sensors to provide workable system.				
5.5.1	Urinal	№			
	Rate or Lump Sum in Words:				
5.6	**Self Close Taps on Kids & Students Lavatories**				
	Supply and install self close taps to be fixed in the lavatory body as manufactured by Grohe Item No. 36-173 with all required works and drain accessories including trap, to be connected to the new water supply and drain and as instructed by the Engineer				
5.6.1	Self Close Taps	№			
	Rate or Lump Sum in Words:				

Bill № 3: Mechanical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
5.7	**Wall Type Self Close Taps on Drinking Basins**				
	Supply and install self close taps to be fixed in the drinking basin body as manufactured by Grohe Item No. 36-176 with all required works and drain accessories including trap and to be connected to the new water supply and drain and as instructed by the Engineer				
5.7.1	Wall Type Self Close Taps	№	3		
	Rate or Lump Sum in Words:				
5.8	**Kitchen Sink Accessories**				
	Supply and install kitchen sink accessories such as chrome trap, angle valve, mixers as specified				
5.8.1	Kitchen Sink Accessories	№			
	Rate or Lump Sum in Words:				
	Total Bill № 3: Mechanical Engineering Services				

Bill № 4: Electrical Engineering Services

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
1	**BASIC ELECTRICAL REQUIREMENTS**				
	The Contractor should revise all the drawings and compare them with the site conditions and redo all the design works with the necessary calculations for all the electrical installations and works. Moreover, the Contractor should submit shop drawings and as-built drawings for the maintenance use in the future.				
	The contractor should provide all the necessary maintenance works for all Electrical systems related to the KG school to ensure its proper works.				
	At the end of the project, the contractor should submit complete As-Built Drawings for all executed works with exact dimensions & sizes for easy maintenance work in the future.				
1.1	**Fixing and Repairing**				
	Check & repair all the existing cables, wires, socket outlets, lighting fixtures, lighting switches, electric fans, and protect all exposed wiring as per the site conditions, and to the satisfaction of the Engineer.				
	All as per the drawings, specifications and Engineer instructions				
1.1.1	Lighting fixtures	LS			
	Rate or Lump Sum in Words:				
1.1.2	Wires and cables	LS			
	Rate or Lump Sum in Words:				
1.1.3	Sockets and switches	LS			
	Rate or Lump Sum in Words:				
1.1.4	Circuit breakers	LS			
	Rate or Lump Sum in Words:				
1.1.9	All needed electrical works … etc.	LS			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
3	**GENERAL LIGHTING INSTALLATIONS**				
3.1	**Lighting Fixtures**				
	Supply, install and test the lighting fixtures complete with all the necessary wires conduits, boxes and accessories required to provide power to each lighting fitting from LP including the earth wire as per the drawings, specifications and Engineer instructions.				
	The Contractor should submit samples of each lighting fixture for approval.				
3.1.1	TYPE C1: Twin T8 LED Tube, surface-mount luminaire for interior, 40W, 4000K, 4700Lm. Polycarbonate, light grey, with injected polyurethane double gasket and clear UV stabilized polycarbonate cover, cos φ ≥ 0.9	№			
	Rate or Lump Sum in Words:				
3.1.3	TYPE C2: as same as TYPE C1 but Pendent mounted	№			
	Rate or Lump Sum in Words:				
3.1.4	TYPE A2 / A3: 600x600 mm LED Panel 3600lm, 33W, 4000K, 80CRI surface-mount/recessed, die-cast aluminum, IP20	№			
	Rate or Lump Sum in Words:				
3.1.6	TYPE N4 / N3: LED - 900lm - 12.5W - 3000K - 80CRI - WW Surface mounted / Recessed Downlight Round - 120 deg	№			
	Rate or Lump Sum in Words:				
3.1.10	Replace Existing lighting fixtures with TYPE L (LED)	№			
	Rate or Lump Sum in Words:				

Bill № 4: Electrical Engineering Services

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Item	Description	Unit	Quantity	Unit Rate (USD)	Amount (USD)
4	**FIRE ALARM SYSTEM**				
	Supply and install all necessary fittings, wires conduits, boxes, plates, relays, bell modules, EOL resistors and accessories as described and as shown on drawings and all necessary connection to the management stations as intended to the satisfaction of the engineer.				
4.6	Break Glass	№			
	Rate or Lump Sum in Words:				
	Total Bill № 4: Electrical Engineering Services				

General Summary

General Summary

Lot #: Lot 2 - Donieh, Tripoli
Shelter: El Nahda Public School for Girls

Description	Amount (US $)
Bill № 2: Civil and Architectural Works	.....
Bill № 3: Mechanical Engineering Services	.....
Bill № 4: Electrical Engineering Services	.....
* Total Amount of Bill of Quantities ……	.....
* Discount by Tenderer (_____ %) ……	.....
* Total Amount of Tender (VAT Not Applicable) ……	.....

* Total Amount of Tender in Words:

.....

.....

.....