

مناقصة عمومية لتلزم أعمال مشروع إنشاء هنكار (Hangar) لصالح المديرية العامة للدفاع المدني

مُلخَص عن الصفقة

إسم الإدارة	المديرية العامة للدفاع المدني
عنوان الإدارة	عين الرمانة - شارع غندور وسمعان- بناية بيضا
رقم التسجيل	2404 / د.م
تاريخ التسجيل	٢٢ فبراير ٢٠٢٢
عنوان الصفقة	تعديل دفتر الشروط الخاص رقم 2236/د.م تاريخ 2026/10/12 المتعلق بإجراء مناقصة عمومية لتلزم أعمال مشروع إنشاء هنكار (Hangar) لصالح المديرية العامة للدفاع المدني
موضوع الصفقة	تعديل دفتر الشروط الخاص رقم 2236/د.م تاريخ 2026/10/12 المتعلق بإجراء مناقصة عمومية لتلزم أعمال مشروع إنشاء هنكار (Hangar) لصالح المديرية العامة للدفاع المدني
طريقة التلزم	مناقصة عمومية على أساس السعر الأدنى الإجمالي لكامل الصفقة
نوع التلزم	أشغال
مدة صلاحية العرض	30/ يوما" من التاريخ النهائي لتقديم العروض
ضمان العرض	//1,000,000,000// ل.ل. مليار ليرة لبنانية
مدة صلاحية ضمان العرض	58/ يوما" من التاريخ النهائي لتقديم العروض
ضمان حسن التنفيذ	تحدد قيمة ضمان حسن التنفيذ بنسبة 4 % من قيمة العقد
الإرساء	يسند التلزم مؤقتاً" إلى العارض المقبول من الناحيتين الإدارية والفنية والذي قدّم السعر الأدنى الإجمالي لكامل الصفقة
مكان استلام دفتر الشروط	عين الرمانة- شارع غندور وسمعان- بناية بيضا- الطابق الثامن بعد توقيع إيصال بالتسلم والتسليم
مكان تقديم العروض	عين الرمانة- شارع غندور وسمعان- بناية بيضا- الطابق الثامن
مكان تقييم العروض	عين الرمانة- شارع غندور وسمعان- بناية بيضا- الطابق العاشر
مدة التنفيذ	المباشرة بالتنفيذ ضمن مدة أقصاها أسبوعين من تاريخ نفاذ العقد .
عملة العقد	الدولار الأميركي
دفع قيمة العقد	وفقاً" لأحكام دفتر الشروط الخاص
مهلة التنفيذ	سنة واحدة

م



قرار رقم ٢٤٥٤/د.م.

يتعلق بتعديل دفتر الشروط الخاص رقم 2236/د.م تاريخ 2026/10/12 المتعلق بإجراء
مناقصة عمومية لتلزم أعمال مشروع إنشاء هنكار (Hangar)
لصالح المديرية العامة للدفاع المدني

بناءً على أحكام المادة 21 من قانون الشراء العام رقم 244 تاريخ 2021/7/19، التي تجيز للإدارة إجراء
تعديلات على دفتر الشروط سواء بمبادرة منها أو نتيجة لطلب استيضاح .

المادة الأولى: يعدل الملحق رقم (5) المتعلق بجدول الاسعار والملحق رقم (6) المتعلق بالكشف التقديري
المرفقين بدفتر الشروط الخاص رقم 2236/د.م تاريخ 2026/10/12 بالمناقصة العمومية لتلزم
أعمال مشروع إنشاء هنكار (Hangar) لصالح المديرية العامة للدفاع المدني ، وفقاً
للمستندات المرفقة ربطاً .

والباقي دون تعديل .

المادة الثانية : يُنشر هذا التعديل على المنصة الإلكترونية المركزية لدى هيئة الشراء العام وعلى الموقع
الإلكتروني الخاص بالمديرية العامة للدفاع المدني www.civildefense.gov.lb

بيروت ، في ٢٢ من أيلول ٢٠٢٦

المدير العام للدفاع المدني

العميد الركن عماد خريش



مرفق ربطاً :

- الملحق رقم (5) المشمول بالتعديل الأخير
- الملحق رقم (6) المشمول بالتعديل الأخير

الملحق رقم (5) – جدول الاسعار في المناقصة العمومية لتزيم أعمال مشروع إنشاء هنكار لصالح المديرية العامة للدفاع المدني

جدول الأسعار

رقم البند	المواصفات	الوحدة	الكمية	السعر الإجمالي	السعر الإفرادي
1	تركيب هنغار قياس 24 X48 METRES حسب الخرائط المرفقة	عدد	4		
2	Base plates 22 PCS	M2	22		
3	Vertical Columns 18 x 6	MTR	432		
4	Vertical Columns 6.63 x 4	MTR	106.08		
5	threaded rods 1 mtr	pcs	528		
6	washer	pcs	528		
7	nut	pcs	528		
8	VC IPE360 Plates rafter connectors	PCS	16		
9	Rafters 18 x 12 mtr	MTR	864		
10	Haunches LR 18 x 2 mtr	MTR	144		
11	Rafters Plates LR	PCS	72		
12	screws 16 mm	PCS	432		
13	washers 16 mm	PCS	432		
14	nuts 16 mm	PCS	432		
15	Rafters Plates Middle	PCS	144		
16	screws 16 mm	PCS	432		
17	washers 16 mm	PCS	432		
18	nuts 16 mm	PCS	432		
19	Front/Rear Closing 24.60 x 2	MTR	196.8		
20	PLATES	PCS	64		
21	screws 16 mm	PCS	256		
22	washers 16 mm	PCS	256		
23	nuts 16 mm	PCS	256		
24	Left side supportive beams 48 X 6	MTR	1152		
25	right side supportive beams 48 X 6	MTR	1152		
26	beams brackets left	pcs	216		
27	beams brackets right	pcs	216		
28	screws	pcs	2592		
29	washers	pcs	2592		
30	nuts	pcs	2592		
31	sandwich panels left (wall 5 cm)	pcs	192		
32	sandwich panels right (wall 5 cm)	pcs	192		
33	drainage left galvanized sheet 2 mm	M2	151.68		
34	drainage right galvanized sheet 2 mm	M2	151.68		
35	front side supportive beams	mtr	336		
36	front side supportive beams	mtr	26		
37	rear side supportive beams	mtr	336		
38	rear side supportive beams	mtr	26		
39	beams brackets front	PCS	104		
40	beams brackets rear	PCS	104		



	832	PCS	10mm	screws front/rear	41
	832	PCS	10mm	washers	42
	832	PCS	10mm	nuts	43
	48	sheet	6x1	sandwich panels front (wall 5 cm)	44
	48	sheet	0.95x1	sandwich panels front(wall 5 cm)	45
	96	sheet	multiple cuts	sandwich panels front (wall 5 cm)	46
	48	sheet	6x1	sandwich panels rear(wall 5 cm)	47
	48	sheet	0.95x1	sandwich panels rear(wall 5 cm)	48
	96	sheet	multiple cuts	sandwich panels rear(wall 5 cm)	49
	48	mtr	16 x 8	FRONT side doors structure	50
	128	mtr	8x8	FRONT side doors structure	51
	290	mtr	6x3	FRONT side doors structure	52
	16	pcs	16 cm	supporting wheels	53
	48	sheet	4.8 x6	sandwich panels(wall 5 cm)	54
	48	mtr	16 x 8	Back side doors structure	55
	128	mtr	8x8	Back side doors structure	56
	290	mtr	6x3	Back side doors structure	57
	16	pcs	16 cm	supporting wheels	58
	48	sheet	4.8 x6 SHEET	sandwich panels(wall 5 cm)	59
	4224	MTR	22 x 48	Roof top purlins C180X2MM	60
	792	PCS	14.4*17*6 mm	BRACKETS	61
	3168	PCS	10mm	screws front/rear	62
	3168	PCS	10mm	washers	63
	3168	PCS	10mm	nuts	64
	1280	PCS	12 MM	purlins connecting rods	65
	5120	PCS	12MM	WASHERS	66
	5120	PCS	12MM	NUTS	67
	4	PCS	48*0.6 PCS	hat galvanized 2 mm	68
	384	sheet	12*1 SHEET	sandwich panels roof (7.5 cm)	69
	352	pcs	25*6.3	Column/base reinforcement 15mm	70
	22000	pcs		Drill head screws multiple 9 to 11 cm approx	71
	40	PCS	110 mm	Gutter pipes UPVC (6 mtr)	72
	160	pcs	110mm	pipe clamp with rubber	73
المجموع					
الضريبة على القيمة المضافة 11%					
المجموع العام					



**الملحق رقم (6) - جدول الكشف التقديرى فى المناقصة العمومية لتلزم أعمال مشروع إنشاء هنكار
لصالح المديرية العامة للدفاع المدني**

الكشف التقديرى			
رقم البند	المواصفات	الوحدة	السعر الإفرادى بالأحرف
1	تركيب هنغار قياس 24 X48 METRES حسب الخرائط المرفقة	عدد	
2	Base plates 22 PCS	M2	50*50*1.5 cm
3	Vertical Columns 18 x 6	MTR	IPE360
4	Vertical Columns 6.63 x 4	MTR	IPE360
5	threaded rods 1 mtr	pcs	24 mm
6	washer	pcs	24 mm
7	nut	pcs	24 mm
8	VC IPE360 Plates rafter connectors	PCS	38*17*1.5cm
9	Rafters 18 x 12 mtr	MTR	IPE360
10	Haunches LR 18 x 2 mtr	MTR	IPE360
11	Rafters Plates LR	PCS	74*17*1.5cm
12	screws 16 mm	PCS	
13	washers 16 mm	PCS	
14	nuts 16 mm	PCS	
15	Rafters Plates Middle	PCS	74*17*1.5cm
16	screws 16 mm	PCS	
17	washers 16 mm	PCS	

	PCS		nuts 16 mm	18
	MTR	IPE200	Front/Rear Closing 24.60 x 2	19
	PCS	22*10*1.5 cm	PLATES	20
	PCS		screws 16 mm	21
	PCS		washers 16 mm	22
	PCS		nuts 16 mm	23
	MTR	10x5	Left side supportive beams 48 X 6	24
	MTR	10x5	right side supportive beams 48 X 6	25
	pcs	22.5*17*6mm	beams brackets left	26
	pcs	22.5*17*6mm	beams brackets right	27
	pcs	10mm	screws	28
	pcs	10mm	washers	29
	pcs	10mm	nuts	30
	pcs	6 x 1	sandwich panels left (wall 5 cm)	31
	pcs	6 x 1	sandwich panels right (wall 5 cm)	32
	M2	48*0.79	drainage left galvanized sheet 2 mm	33
	M2	48*0.79	drainage right galvanized sheet 2 mm	34
	mtr	10x5	front side supportive beams	35
	mtr	10x5	front side supportive beams	36
	mtr	10x5	rear side supportive beams	37
	mtr	10x5	rear side supportive beams	38
	PCS	22.5*17*6mm	beams brackets front	39
	PCS	22.5*17*6mm	beams brackets rear	40

	PCS	10mm	screws front/rear	41
	PCS	10mm	washers	42
	PCS	10mm	nuts	43
	sheet	6x1	sandwich panels front (wall 5 cm)	44
	sheet	0.95x1	sandwich panels front(wall 5 cm)	45
	sheet	multiple cuts	sandwich panels front (wall 5 cm)	46
	sheet	6x1	sandwich panels rear(wall 5 cm)	47
	sheet	0.95x1	sandwich panels rear(wall 5 cm)	48
	sheet	multiple cuts	sandwich panels rear(wall 5 cm)	49
	mtr	16 x 8	FRONT side doors structure	50
	mtr	8x8	FRONT side doors structure	51
	mtr	6x3	FRONT side doors structure	52
	pcs	16 cm	supporting wheels	53
	sheet	4.8 x6	sandwich panels(wall 5 cm)	54
	mtr	16 x 8	Back side doors structure	55
	mtr	8x8	Back side doors structure	56
	mtr	6x3	Back side doors structure	57
	pcs	16 cm	supporting wheels	58
	sheet	4.8 x6 SHEET	sandwich panels(wall 5 cm)	59
	MTR	22 x 48	Roof top purlins C180X2MM	60
	PCS	14.4*17*6 mm	BRACKETS	61
	PCS	10mm	screws front/rear	62
	PCS	10mm	washers	63

	PCS	10mm	nuts	64
	PCS	12 MM	purlins connecting rods	65
	PCS	12MM	WASHERS	66
	PCS	12MM	NUTS	67
	PCS	48*0.6 PCS	hat galvanized 2 mm	68
	sheet	12*1 SHEET	sandwich panels roof (7.5 cm)	69
	pcs	25*6.3	Column/base reinforcement 15mm	70
	pcs		Drill head screws multiple 9 to 11 cm approx	71
	PCS	110 mm	Gutter pipes UPVC (6 mtr)	72
	pcs	110mm	pipe clamp with rubber	73

✈

